

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

sr dste dnr acting for and on behalf of The President of India invites E-Tenders against Tender No **DNRSandTSig2026-1** Closing Date/Time 09/02/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Replacement of existing signaling gears (PI) with Electronic Interlocking System (EI system) at Bela stations in PNBE-GAYA section under Danapur Division.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	09/02/2026 15:00	Date Time Of Uploading Tender	16/01/2026 17:04
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	77806394.26	Tendering Section	S AND T
Bidding Style	Single Rate for Each Schedule Item	Bidding Unit	
Earnest Money (Rs.)	539000.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	26/01/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Annexure - Z (Schedule-1)							5273046.06	
1	Please see Item Breakup for details.				1316550.00	300.52	5273046.06	Above/ Below/Par
	Description:- SOR items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Annexure - Z (Schedule-2)							4101044.72	
2	Please see Item Breakup for details.				1329177.65	208.54	4101044.72	Above/ Below/Par
	Description:- Non SOR Items							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C-Annexure - Z (Schedule-3)							36979117.57	
1	c	1.00	Numbers	221617.43	221617.43	AT Par	221617.43	Above/ Below/Par
	Description:- "Supply, Installation, Testing & Commissioning of Earth Leakage Detector for monitoring different AC & DC supplies Multichannel (12 channel) conforming to RDSO /SPN/256/2002 with latest amendments.-12 Channel Inspection-RDSO"							
2	c	5000.00	Numbers	105.83	529150.00	AT Par	529150.00	Above/ Below/Par
	Description:- Supply of Disconnect type Terminal,screwless, 2 IN 2 OUT(as per spec. no. RDSO/SPN/189/2004 or latest)along with all accessories including separators for fixing on Cable Termination Rack/Location boxes for Cable Termination Purpose. Inspection-RDSO							
3	c	5000.00	Numbers	1.45	7250.00	AT Par	7250.00	Above/ Below/Par
	Description:- Fixing installation of disconnect terminal (Wago or similar) onrelay rack/ctr/location with steel carrier rail.							
4	c	300.00	Kilometre	116.29	34887.00	AT Par	34887.00	Above/ Below/Par
	Description:- Transportation of material by 15 MT capacity truck.							
5	c	3.00	Per Trip	10395.06	31185.18	AT Par	31185.18	Above/ Below/Par
	Description:- Loading , Unloading of heavy S&T material by 15MT truck							
6	c	2.00	Numbers	98602.19	197204.38	AT Par	197204.38	Above/ Below/Par
	Description:- Supply, Installation, testing & commissioning of MAPLE 4C/Fabio of equivalent 1U, 19 Inch rack mountable device consisting of Min. four E1 ports and three slots and one populated with 2W/4W E&M supporting upto eight interfaces, Balance two slots empty, units shall support both 230V AC/48V DC power supply including 50 pin cable one No. for supporting both 2W/4W E & W, AC adopter one number. Make: Mro-tek, Real time, Cygnus, Cisco or equivalent. Inspection- RITES with manufacturer GC & TC.							
7	c	1.00	Set	430487.30	430487.30	AT Par	430487.30	Above/ Below/Par
	Description:- "Supply, Installation, Testing & commissioning of Data Logger System for Rly. S&T. Installation as per RDSO Specification no. IRS:S:99/2006 with latest amendment with 1024 Digital Input and 32 Analog inputs along with PC & Multi Function Colour Printer. Inspection-RDSO"							
8	c	1.00	Pair	61403.66	61403.66	AT Par	61403.66	Above/ Below/Par
	Description:- "Supply, installation, Testing & commissioning of internal Dual card RS232 to EI convertor suitable for datalogger for item no. 21(a). Inspection-Consignee"							
9	c	1.00	Numbers	23063.26	23063.26	AT Par	23063.26	Above/ Below/Par
	Description:- "Supply , Installation, Testing & Commissioning of External E1 to serial converter Inspection-Consignee"							
10	c	1.00	Station	428744.03	428744.03	AT Par	428744.03	Above/ Below/Par
	Description:- "Supply and installation of Early streamer Emission lighting conductor (ESEL) fully autonomous having lower series of energy collecting electrodes upper series of spark -generating electrodes, as in built micro controller for detection of lightning down ward leader and releasing upward ladder at that very precise moment to ensure nuisance free, fail safe ,real need based operation any and every time ,sealed in a stainless -steel housing fixed at the center of its central rod which has full electrical connectivity direct up to earth point ,gain in triggering time of 25 micro sec giving 75 meters radius, level I high protection, real life & high voltage laboratory tested, CPRI tested. Inspection-RITES"							
11	c	1.00	Station	7964.05	7964.05	AT Par	7964.05	Above/ Below/Par
	Description:- "Supply and erection of a mast/high mast suitable for ESE Technology based lighting protection installation ,mechanically robust good corrosion and fire resistance 5 meter (including 2 meter FRP) long GI/MS painted, along with guying kit foundation and other accessories erquird for installation of the mast. Inspection-Consignee"							
	c	200.00	Metre	1468.90	293780.00	AT Par	293780.00	Above/ Below/Par

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

12								
	Description:- "Supply and laying of 70 sq. mm. PVC insulated flexible tinned electrolytic copper down conductor placed in a metallic/PVC protectivecovering wherever exposed to human intervention including saddles and all accessories etc. as required. Inspection-Consignee"							
13	c	1.00	Station	62075.00	62075.00	AT Par	62075.00	Above/ Below/Par
	Description:- "Supply & installation of resettable 6 digit LCD lighting strike recorder /transient event counter with 10 year long life lithium battery in an all whether proff box of IP67 grade protection along with clamps etc. as required. Inspection-Consignee"							
14	c	1.00	Station	48934.76	48934.76	AT Par	48934.76	Above/ Below/Par
	Description:- "Supply and fixing of Equipotential Earth Bonding unit between electrical & equipment earthing in a explosion proof IP68 enclosure with inspection chamber for equipotential bonding during a surge. Inspection-Consignee"							
15	c	2.00	Numbers	6578.17	13156.34	AT Par	13156.34	Above/ Below/Par
	Description:- Supply and Provision of indicative type Class D Surge Protection Device for 24V DC/48V DC (spark gap type), with Potential Free contacts and installed as per the instructions of the Engineer in charge at site (OBO, DEHN, PHOENIX, LPI, ZOTUP, HAKEL or better make). All other miscellaneous materials required for installation shall be supplied by the contractor. Inspection-Consignee							
16	c	25.00	Metre	1504.31	37607.75	AT Par	37607.75	Above/ Below/Par
	Description:- Supply and laying of 25 x 3 mm. pure electrolytic copper tape through suitable 'class B' G.I pipe for loop earthing and bonding as per site requirement .Inspection-Consignee							
17	c	500.00	Metre	132.52	66260.00	AT Par	66260.00	Above/ Below/Par
	Description:- Supply of 10 sq mm multi strand single core PVC insulated copper cable as per IS:694 in the equipment as per site requirement. Inspection-Consignee							
18	c	250.00	Metre	202.55	50637.50	AT Par	50637.50	Above/ Below/Par
	Description:- Supply of 16 sq mm multi strand single core PVC insulated copper cable as per IS:694 in the equipment as per site requirement. Inspection-Consignee							
19	c	250.00	Metre	402.55	100637.50	AT Par	100637.50	Above/ Below/Par
	Description:- Supply of 35 sq mm multi strand single core PVC insulated copper cable as per IS:694 in the equipment as per site requirement. Inspection-Consignee							
20	c	1.00	Station	112912.73	112912.73	AT Par	112912.73	Above/ Below/Par
	Description:- "Supply of materials and installation for making high conductive ,non corrosive maintenance free yet erperable "Electro chemical gel earth pit using earth enhancing compound of 30 kg kit CPRI tested rod of 3 inch dia ,8 fit long and 0.12 inch thick made of K type electrolytic copper with top removal gel filling cap seepage holes .stainless steel fastners ,HDP lockable earth pit cover cum inspection chamber and allrequired accessories including desinemodification to acheive the required earth termination rod resistance value below 1 ohm. Inspection-Consignee"							
21	c	10.00	Set	26731.95	267319.50	AT Par	267319.50	Above/ Below/Par
	Description:- Supply and installation of basic Earthing kit 1 set as per RDSO Spec. No. RDSO/SPN/197/2008 or latest consisting of: (i) Copper bonded high tensile low carbon steel earth electrode 3.0 Mtr. Long dia 17 mm. , specially designed for electrical grounding - 1 no. (ii) Earth Enhancement compound in 10Kgs bag- 3 Nos. (iii) Copper tape of 25mm x 6mm x 300mm= 2 Nos. (iv)Copper tape of 25mm x 6mm x 200mm to terminate on earth electrode= 01 No.(v) Supply of insulated connecting cable to connect equipment bus bar 10 meter each earth. Installation of unit earth which includes digging, inserstion,filling , trenching, laying, welding and & Provision of exothermic weld one to connecting cable to the earth electrode and another to the copper tape/35 sqmm multi strand single core PVC insulated copper cable to the copper strip/tape/busbar welded to the copper tape to be fixed inside the Equipment/Relay Rack/Apparatus caseas per RDSO spec. Inspection-RDSO							
22	c	3000.00	Metre	1317.73	3953190.00	AT Par	3953190.00	Above/ Below/Par
	Description:- Transportation of HDT machine with accessories including handling of stores materials, preparation of site and boring for placing of 110 MM inner dia HDPE/DWC pipes for crossing of S&T cable together at Bridges/ Culverts/Track/ pucca road Crossing, Boring trench shall be minimum 3 Mtr below the river bed and 1 Mtr below the Track/Road /Pucca Road crossing area. This includes supply of HDPE/DWC pipes and accessories, cost of fuels & all other items which will be required for laying of cable through it. The work shall be executed as per instruction of site engineer.- (a) Boring upto length 150 Mtrs. (Pipes Inspection Consignee)							
23	c	2.00	Set	73185.36	146370.72	AT Par	146370.72	Above/ Below/Par
	Description:- Supply of reliability improvement kit suitable to work with UFSBI as per RDSO/SPN/147/2005 or latest. It comprises A) Supply of automatic media change over of modems working on redundant channels for data transmission on OFC/quad/Microwave radio (any two media)=01 pair. B) Secondary modem for UFSBI for use with secondary media OFC/Quad =1 pair. C) Type C&D power line (VF24V AC/DC-02 nos V20C/3PH 150V -02 Nos.) and data line SPD (MDP 4D/5T-02 nos) comprising suitable to work with 1 pair UFSBI =01 set. D) Power Monitor & soft start unit PMSS=01 pair Note : Complatable for all type of UFSBI system ie Delttron/Webfill/others if any. Inspection- Consignee							
24	c	2.00	Set	12906.60	25813.20	AT Par	25813.20	Above/ Below/Par
	Description:- "Installation, wiring and testing of Automatic media change over of modems with its accessories as per site Engineer"							
25	c	5.00	Numbers	28000.00	140000.00	AT Par	140000.00	Above/ Below/Par
	Description:- Supply of Signal post Telephone with talk back facility consisting of 1 master +1 slave , operation voltage 110V AC/12V DC. Inspection-Consignee							
26	c	1.00	Numbers	269382.80	269382.80	AT Par	269382.80	Above/ Below/Par
	Description:- "Supply, Installation, Testing and Commissioning of Remote monitoring and predictive maintenance System (RMPMS)-Supply and installation of Microprocessor based Event Logger station unit for point machine machine and DC track circuit monitoring in relay room as per schedule. It includes supply of RMPMS (Remote monitoring and predictive maintenance System) Edge & Field Gateway in compliance to FIG 3 system Architecture as per RDSO FRS dated July-2025 or Latest with following- A) Field Gateway : As per FRS clause 6.9.1 Primary Media :Zigbee/LORA & Secondary Media :OFC/Copper/WIFI, Protocol (Filed to station):As per FRS clause 6.5 MQTT/ SNMP2/MODBUS B)Edge Gateway: As per FRS clause 6.9.5 Railnet & 4G,Protocol(Station to cloud):As per FRS clause 6.4 :OPC UA, Optional MQTT/ HTTP/ HTTPS/ FTP ,C) Local Console: Station Specific data of all gears shall available to gate way and shall be accessible even in absence of internet to maintainer ,D) JWeb server: As per FRS clause 7.9 Gateway shall be remote accessible over 4g as well as ethernet for Updating firmware ,Operating System ,Data log & export configuration, also provision to export data to any desired IP. Configuring polling interval, Calibrations of FTU channels Configuring wireless channel for each FTU from either RF/ LORA/WLAN .E)Analog Input :60 or Higher F) Serial Port :Rs 232,Rs 485,G) Provision for LAN & WAN port. H) Data Handling Capacity :512 input or higher as per latest RDSO/Board guidelines. Inspection-RITES"							
27	c	2.00	Numbers	188892.69	377785.38	AT Par	377785.38	Above/ Below/Par
	Description:- Supply of 48 channel FTU (Field Transmission Unit) signal, track and Point machine variant as per schedule. Supply of Field IOT device /Field Transmission Unit with following specs :A) Design Shall be Modular rack/sub rack design, B) Provision for Voltage Transducer,C) Communication: Primary Media: Zigbee/ LORA & Secondary Media:OFC/Copper/WIFI, Protocol (Filed to station): MQTT/SNMP2/MODBUS, D) Power Supply : 24v DC & 110 v AC both, E) Provision for Fuse & Diode on analog channel ,F)Provision to Cluster Near by Location ,G) Generic Architecture: Shall be compatible for all type of Gears:Track/Signal/Point Machine/Axle Counter. 40/48 Analog Channel RACK BASED MODULAR FTU (Field Transmission Unit). Inspection-RDSO							
28	c	20.00	Numbers	94878.80	1897576.00	AT Par	1897576.00	Above/ Below/Par

DANAPUR DIVISION-S AND T/EAST CENTRAL RLY TENDER DOCUMENT

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

29	c	100.00	Numbers	4763.07	476307.00	AT Par	476307.00	Above/ Below/Par
	Description:- Supply of 20 channel FTU (Field Transmission Unit) signal, track and Point machine variant as per schedule. Supply of Field IOT device /Field Transmission Unit with following specs :A) Design Shall be Modular rack/sub rack design, B) Provision for Voltage Transducer,C) Communication: Primary Media: Zigbee/LORA & Secondary Media:OFC/Copper/WIFI, rotocol (Filed to station): MQTT/SNMP2/MODBUS, D)Power Supply : 24v DC & 110 v AC both, E) Provision for Fuse & Diode on analog channel,F)Provision to Cluster Near by Location, G) Generic Architecture: Shall be compitible for all type of Gears:Track/Signal/Point Machine/Axle Counter. 16 /20 Analog Channel RACK BASED MODULAR FTU (Field Transmission Unit). Inspection-RDSO							
30	c	400.00	Numbers	164.79	65916.00	AT Par	65916.00	Above/ Below/Par
	Description:- Installation & commissioning of current sensor/transducer for each data point.							
31	c	1.00	Numbers	8505.92	8505.92	AT Par	8505.92	Above/ Below/Par
	Description:- Installation & commissioning of event logger station unit.							
32	c	1.00	Station	38933.12	38933.12	AT Par	38933.12	Above/ Below/Par
	Description:- Installation Wireless with FTU & Event Logger unit of station for signalling gears.							
33	c	1.00	Station	163450.35	163450.35	AT Par	163450.35	Above/ Below/Par
	Description:- Development of Software for cloud based WEB Portal for monitoring of preventive maintenance of signaling gears of yard. Inspection-RDSO							
34	c	1.00	Station	444520.95	444520.95	AT Par	444520.95	Above/ Below/Par
	Description:- Supply of Smart Station Network maintenance system including its database:Application software with its relevant patches and database and database of SQL server / MS SQL/MYSQL or oracle to be established for each station users for maintaining of station assests.Server application will be installed at Cloud and station user can login in the server machine by its user credentials and work in the modules. Inspection-RDSO							
35	c	4.00	Numbers	2565.41	10261.64	AT Par	10261.64	Above/ Below/Par
	Description:- Installation, Erection & Wiring of CLS unit, Post, Ladder & Base, LED unit including paying out of tail cable from location box & earthing of CLS (LED type). This includes supply of non metallic (FRP) colour light signal housing multi-unit type for Rly. signalling, suitable for RE area, 3 aspect complete without lenses, lamps and signal transformer as per drg. no. SA23003/A/M/ADV.ALT-8 and per spec. no. RDSO/SPN/194/2006 (VER-1.0) or latest and FRP material as RDSO spec no RDSO/SPN/151/1997 or latest. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note - Signal should be compatible to 'LED' type Inspection:- RDSO Note: Installation, Erection & Wiring of signalling unit includes LED signal litghtening unit including Current Regulator & Health Monitoring unit. This also includes protection of unit from rain water- Execution							
36	c	4.00	Numbers	38936.51	155746.04	AT Par	155746.04	Above/ Below/Par
	Description:- Installation, Erection & Wiring of CLS unit, Post, Ladder & Base, LED unit including paying out of tail cable from location box & earthing of CLS (LED type). This includes supply of nonmetallic (FRP) colour light signal housing multi-unit type for Rly. signalling, suitable for RE area, 3 aspect complete without lenses, lamps and signal transformer as per drg. no. SA23003/A/M/ADV.ALT-8 and per spec. no. RDSO/SPN/194/2006 (VER-1.0) or latest and FRP material as RDSO spec no RDSO/SPN/151/1997 or latest. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note - Signal should be compatible to 'LED' type Inspection:- RDSO Note: Installation, Erection & Wiring of signalling unit includes LED signal litghtening unit including Current Regulator & Health Monitoring unit. This also includes protection of unit from rain water -Supply Inspection Consignee							
37	c	7.00	Numbers	2318.09	16226.63	AT Par	16226.63	Above/ Below/Par
	Description:- Installation, Erection & Wiring of CLS unit, Post, Ladder & Base, LED unit including paying out of tail cable from location box & earthing of CLS (LED type). This includes supply of nonmetallic (FRP) colour light signal housing multi-unit type for Rly signalling, suitable for RE area, 2 aspect complete without lenses, lamps and signal transformer as per drg. no SA23003/A/M/ADV ALT-8 and per spec. no RDSO/SPN/194/2006 (VER- 1.0) or latest and FRP material as RDSO spec no RDSO/SPN/151/1997 or latest. All drawings should be as per latest Material to be procured from RDSO's approved firm only Note - Signal should be compatible to 'LEDY type. Inspection - RDSO Note-Installation, Erection & Wiring of signalling unit includes LED signal litghtening unit including Current Regulator & Health Monitoring- Execution							
38	c	7.00	Numbers	36637.73	256464.11	AT Par	256464.11	Above/ Below/Par
	Description:- Installation, Erection & Wiring of CLS unit, Post, Ladder & Base, LED unit including paying out of tail cable from location box & earthing of CLS (LED type). This includes supply of nonmetallic (FRP) colour light signal housing multi-unit type for Rly signalling, suitable for RE area, 2 aspect complete without lenses, lamps and signal transformer as per drg. no SA23003/A/M/ADV ALT-8 and per spec. no RDSO/SPN/194/2006 (VER- 1.0) or latest and FRP material as RDSO spec no RDSO/SPN/151/1997 or latest. All drawings should be as per latest Material to be procured from RDSO's approved firm only Note - Signal should be compatible to 'LEDY type. Inspection - RDSO Note-Installation, Erection & Wiring of signalling unit includes LED signal litghtening unit including Current Regulator & Health Monitoring - Supply Inspection Consignee							
39	c	2.00	Numbers	712.66	1425.32	AT Par	1425.32	Above/ Below/Par
	Description:- Installation, Erection paying out of tail cable from location box and wiring of Calling-On signal/Guard repeater, LED unit on same post below Main signal. This includes supply of nonmetallic (FRP) Calling-On signal housing unit type for railway signalling, suitable for RE area, without lense, lamp and holder, compatible to LED signal unit as per RDSO drg. no. SA24351/ADV or latest and as per RDSO spec. no. RDSO/SPN/194/2006 (VER-1.0) or latest. FRP material spec. as per RDSO/SPN/151/1997 or latest. This includes cost of protection cover (wire mesh guard of expanded metal of size 2inchx linch) and mounting bracket with U-clamps nuts & washer All drawings should be as per latest. Note- Inspection by RITES (for value of material above Rs. 1 lac) Inspection by consignee (for value of material below than Rs 1 lac) Note- Installation, Erection & Wiring of signalling unit includes LED signal litghtening unit including Current Regulator & Health Monitoring unit. This also includes protection of unit from rain water -Execution							
40	c	2.00	Numbers	12236.88	24473.76	AT Par	24473.76	Above/ Below/Par
	Description:- Installation, Erection paying out of tail cable from location box and wiring of Calling-On signal/Guard repeater, LED unit on same post below Main signal. This includes supply of nonmetallic (FRP) Calling-On signal housing unit type for railway signalling, suitable for RE area, without lense, lamp and holder, compatible to LED signal unit as per RDSO drg. no. SA24351/ADV or latest and as per RDSO spec. no. RDSO/SPN/194/2006 (VER-1.0) or latest. FRP material spec. as per RDSO/SPN/151/1997 or latest. This includes cost of protection cover (wire mesh guard of expanded metal of size 2inchx linch) and mounting bracket with U-clamps nuts & washer All drawings should be as per latest. Note- Inspection by RITES (for value of material above Rs. 1 lac) Inspection by consignee (for value of material below than Rs 1 lac) Note- Installation, Erection & Wiring of signalling unit includes LED signal litghtening unit including Current Regulator & Health Monitoring unit. This also includes protection of unit from rain water - Supply Inspection-Consignee							
41	c	7.00	Numbers	555.26	3886.82	AT Par	3886.82	Above/ Below/Par
	Description:- Installation, Erection of Shunt Signal unit with base and post and paying out of tail cable from location box and wiring of shunt signal, LED unit as per technical spec. This includes supply of non-metallic (FRP) shunt signal housing multi-unit type (without lenses, lamps) with base & post and without signal transformer for Rly signalling suitable for RE area without lens, lamp & holder, compatible to LED signal unit as per RDSO drg no. 23840/ADV/ALT-2 or latest and as per RDSO spec no RDSO/SPN/194/2006 (VER-1.0) or latest FRP material spec. no. as per RDSO/SPN/151/1997 or latest All drawings should be as per latest. Material to be procured from RDSO's approved firm only. FRP unit - Inspection by RDSO Base & post - Inspection by Consignee. Note:-Installation, Erection & Wiring of signalling unit includes LED signal litghtening unit including Current Regulator & Health Monitoring unit. This also includes protection of unit from rain- Execution							
	c	7.00	Numbers	16528.11	115696.77	AT Par	115696.77	Above/ Below/Par

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

42	Description:- Installation, Erection of Shunt Signal unit with base and post and paying out of tail cable from location box and wiring of shunt signal, LED unit as per technical spec. This includes supply of non-metallic (FRP) shunt signal housing multi-unit type (without lenses, lamps) with base & post and without signal transformer for Rly signalling suitable for RE area without lens, lamp & holder, compatible to LED signal unit as per RDSO drg no. 23840/ADV/ALT-2 or latest and as per RDSO spec no RDSO/SPN/194/2006 (VER-1.0) or latest FRP material spec. no. as per RDSO/SPN/151/1997 or latest All drawings should be as per latest. Material to be procured from RDSO's approved firm only. FRP unit - Inspection by RDSO Base & post - Inspection by Consignee. Note:-Installation, Erection & Wiring of signalling unit includes LED signal lightning unit including Current Regulator & Health Monitoring unit. This also includes protection of unit from rain- Supply Inspection-Consignee							
43	c	100.00	Metre	2940.24	294024.00	AT Par	294024.00	Above/ Below/Par
	Description:- Supply and placing of Injection moulded cable channel of size width (int/ext) 240/340 mm, height (int/ext) 155mm/230 mm, length approx 1 meter (tolerance in dimensions +/-10 mm), weight per mtr atleast -8 Kg (Top and bottom). Material - Polyolefin- Engineering Plastic, with fire protection class K-1 in accordance with DIN 53438 part-II, Breaking Load (minimum) ->12 Kilo Newton or latest at room temperature, for laying signalling/ telecom/ power cables, channel attachable to each other with male female swallow tail connectors and having suitable detachable cover. Technical Specification & Testing parameter/ Procedure as per RDSO-Ref No. : STS/Cable Laying Practices Vol-IV dtd. 09.05.2018. Supply-Inspection-Consignee							
44	c	100.00	Numbers	5651.00	565100.00	AT Par	565100.00	Above/ Below/Par
	Description:- Installation of Earth Electrode including supply of MS Flat for clamp Signalling equipment such as apparatus cases, Signal posts, etc.							
45	c	250.00	Kg	98.62	24655.00	AT Par	24655.00	Above/ Below/Par
	Description:- Supply of 8 SWG GI wire (4mm dia) suitable for track circuit rail bonding. As per IRS Specification S:13 @ 45 46 @. Inspection-Consignee							
46	c	2.00	Kilometre	113914.80	227829.60	AT Par	227829.60	Above/ Below/Par
	Description:- Supply & Laying of HDPE pipe of dia 40/33 mm dia with remaining materials in the trenches as per RDSO spec no. RDSO/SPN/TC/45/2013 Rev.2 Amndt No 2 or latest. It includes transportation of HDPE pipe from railway store to site & returning of left over material as per directions of engineer in charge/site engineer.-Supply Inspection-Consignee							
47	a	2.00	Kilometre	11759.90	23519.80	AT Par	23519.80	Above/ Below/Par
	Description:- Supply & Laying of HDPE pipe of dia 40/33 mm dia with remaining materials in the trenches as per RDSO spec no. RDSO/SPN/TC/45/2013 Rev.2 Amndt No 2 or latest. It includes transportation of HDPE pipe from railway store to site & returning of left over material as per directions of engineer incharge/site engineer- Execution							
48	c	2.00	Kilometre	19204.52	38409.04	AT Par	38409.04	Above/ Below/Par
	Description:- Laying/drawing of OFC through HDPE pipe/PVC pipe for OFC by blowing as advised by site engineer.							
49	c	4.00	Numbers	32992.57	131970.28	AT Par	131970.28	Above/ Below/Par
	Description:- Supply and installation of Optical fibre cable joint enclosure and making straight through joints for 24 fibre cable and testing. This includes splicing and making pits of size 1.2M dia x 1.2 M depth with top cover slab as per drawing 3. Supply- Inspection-Consignee							
50	c	4.00	Numbers	14951.45	59805.80	AT Par	59805.80	Above/ Below/Par
	Description:- SUPPLY AND INSTALLATION OF OFC TERMINATION BOX FOR 24 FIBRE CABLE AND SPLICING OF FIBRE WITH PIG TAILS CABLES AS PER SPECIFICATION DRAWING AND STIPULATION OF TENDER DOCUMENTS. THIS INCLUDES TESTING OF OFC, SUPPLY OF TEAK WOOD PLANK ,ALUMINIUM LADDER ETC.Supply- Inspection-Consignee							
51	c	2.00	Numbers	40306.62	80613.24	AT Par	80613.24	Above/ Below/Par
	Description:- Supply and installation of OFC distribution frame as per SPEC. DOT/G/FDF-01/01JAN-93 or latest and splicing of OFC inside the termination box with provision of taking out Fibres of OFC as required and testing of all fibre . This includes supplu and fixing of Hard wood board of size 3ftx5ftx1.5ft in with wall fixing arrangemnets and all accessories. Supply- Inspection-Consignee							
52	c	20.00	Numbers	824.74	16494.80	AT Par	16494.80	Above/ Below/Par
	Description:- SUPPLY OF PIG TAIL (10M LONG) WITH FC/PC CONNECTOR AS PER TEC SPECIFICATION NO. G/OJF-01/ 03 JUN'99 WITH LATEST AMENDMENTS. Supply- Inspection-Consignee							
53	c	20.00	Numbers	1196.57	23931.40	AT Par	23931.40	Above/ Below/Par
	Description:- SUPPLY OF PATCH CORD (10M LONG) WITH FC/PC CONNECTOR ON BOTH SIDE AS PER TEC.Spec.No.. G/OJF-01/03 JUN'99 WITH LATEST AMENDMENTS. Supply- Inspection-Consignee							
54	c	200.00	Metre	54.61	10922.00	AT Par	10922.00	Above/ Below/Par
	Description:- SUPPLY OF INDOOR POWER CABLE OF DIFFERENT SIZES AS PAR IRS- S-76/89 OR LATEST- 4 SQ.MM. Supply- Inspection-Consignee							
55	c	10.00	Numbers	2883.27	28832.70	AT Par	28832.70	Above/ Below/Par
	Description:- SUPPLY OF OPTICAL FIBRE CABLE SPLICE CLOSURE (24 FIBRE) AS PER TEC SPECIFICATION NO.G/OJC-02/01 MAR'99 WITH LATEST AMENDMENTS Supply- Inspection-Consignee							
56	c	1.00	Station	26092.18	26092.18	AT Par	26092.18	Above/ Below/Par
	Description:- TESTING OF ALL FIBRES OF THE OPTIC FIBRE CABLE, QUAD, PIJF CABLE, ADM,MUX AND OTHER ACCESSORIES INSTALLED ABOVE AND FINAL COMMISSIONING OF OPTICAL FIBRE COMMUNICATION LINK CONFORMING TO RAILWAY'S SPECIFICATION INCLUDING END TO END TESTING FOR REALIZATION OF OPTICAL FIBRE SYSTEM.							
57	c	200.00	cum	5891.01	1178202.00	AT Par	1178202.00	Above/ Below/Par
	Description:- Providing and laying in position cement concrete of 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate 20 mm nominal size) including cement for laying of cable in Duct as per instruction of site engineer. Payment will be as per actual work in Cum.							
58	c	32.00	Numbers	8910.77	285144.64	AT Par	285144.64	Above/ Below/Par
	Description:- Supply of Battery Charger - Track Feed Up to 10 Amp, Spec. No.IRS-S-89/93 (Amd.-2) or Latest. Inspection- RDSO							
59	c	36.00	Numbers	328441.19	11823882.84	AT Par	11823882.84	Above/ Below/Par
	Description:- Supply of Multi Section Digital Axle Counter (MSDAC) complete with all accessories, cable required with each track device, cards, track device, Track side Electronics/DAC fieldunits, Central Evaluator (Central Evaluator unit should be housed in a prefabricated Rack to bes uplied along with thesystem), Relay unit, Event logger, Diagnostic terminal etc. required for different Detection Points & Track Sections as per Specification No.RDSO/SPN/176/2013Ver.3 or latest as required to make the system functional. All the materials shall be supplied as per annexures of tender document. Supply &installation of Maintenance free earth & Location/ Mushroom if required by OEM to make the system complete functional. Note: Per DP supply includes all the required accessories such as cables for wiring, relays, different indoor & outdoor cards, earthing of DP, L/Boxes/ Mushroom, LVetc as required. MSDAC Interface Circuit, Relayfor LVPR and Track section and tool kit to besupplied. Unit= DP=No.Supply- Inspection-RDSO							
60	c	36.00	Numbers	18812.45	677248.20	AT Par	677248.20	Above/ Below/Par
	Description:- Installation, testing & Commissioning of Multi section digital axle counter (MSDAC) as per Specification No. RDSO/SPN/176/2013Ver.3 or latest. Unit=DP=Number.							
61	a	5.00	Numbers	42642.99	213214.95	AT Par	213214.95	Above/ Below/Par
	Description:- Supply of Electronic L.C. Gate Telephone system with voice recorder, as per RDSO Specification No RDSO/SPN/TC/51/11. Rev.3.0 or latest- Master Telephone with inbuilt voice logger. Inspection-RDSO							

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

62	c	5.00	Numbers	4095.00	20475.00	AT Par	20475.00	Above/ Below/Par
	Description:- Installation of Electronic L.C. Gate Telephone system with voice recorder, as per RDSO Specification No. RDSO/SPN/TC/51/11. Rev.3.0 or latest- Master Telephone.							
63	c	10.00	Numbers	5993.74	59937.40	AT Par	59937.40	Above/ Below/Par
	Description:- Supply of Electronic L.C. Gate Telephone system with voice recorder - Slave telephone as per RDSO Specification No.RDSO/SPN/TC/51/11. Rev.3.0 or latest, Slave Telephone. Inspection-RDSO							
64	c	10.00	Numbers	535.50	5355.00	AT Par	5355.00	Above/ Below/Par
	Description:- Installation of Electronic L.C. Gate Telephone system with voice recorder - Slave telephone as per RDSO Specification No. RDSO/SPN/TC/51/11. Rev.3.0 or latest, Slave Telephone							
65	c	15.00	Numbers	7680.27	115204.05	AT Par	115204.05	Above/ Below/Par
	Description:- Supply of power supply system 24V power pack with MF battery-7AH For LC Telephone , suitable for L.C. Gate Telephone with voice recorder as per RDSO Specification No. RDSO/SPN/TC/51/11. Rev.3.0 or latest. Inspection-RDSO							
66	c	15.00	Numbers	661.50	9922.50	AT Par	9922.50	Above/ Below/Par
	Description:- Installation of power supply system 24V power pack with MF battery-7AH For LC Telephone , suitable for L.C. Gate Telephone with voice recorder as per RDSO Specification No. RDSO/SPN/TC/51/11. Rev.3.0 or latest.							
67	c	1.00	Station	4001.46	4001.46	AT Par	4001.46	Above/ Below/Par
	Description:- Preperation & printing of Station Working Rule Diagram (SWRD) on AUTO CAD based on approved SIP, ESP etc. as per the extant practice being followed in E.C. Railway. Contrctor shall supply one print of the SWRD (praper printSize as requird) as draft for approval and comments. Once the approval is given shall tracing of the SWRD on good quality flim paper of thickness not less than 75 microns for signature of all officials. On approval the contractor shall supply 10 copys blue prient of the tracing. The approved SWRD shall be finally supplied on 2 CDs.							
68	c	1.00	Station	16005.88	16005.88	AT Par	16005.88	Above/ Below/Par
	Description:- "Preparation of Station Working Rule (SWR) in English and Hindi based on approved SIP, ESP etc as per the extent practice being followed in E. C. Railway. The contractor shall supply two paper print of the SWR as draft for approval and comments .Once the approval is given he shall supply two paper prients of the SWR for final approval and signature of the concerned officials. on obtaining the final approval the contractor shall supply 10 sets of the SWR duly photo copies from the original signed off copies of SWR .Theapproved SWR shall be finally supplied on 2 CDs."							
69	c	120.00	Numbers	4952.00	594240.00	AT Par	594240.00	Above/ Below/Par
	Description:- Supply of Relay Non-AC immune , plug in type, style QN1, neutral line, 24V or 50V DC, 12F/4B contacts metal to carbon with plug board, retaining clip and connectors confirming to BRS : 930, IRS: S - 34 and IRS: S - 23 (As applicable) or similar Inspection-RDSO							
70	c	120.00	Numbers	4952.00	594240.00	AT Par	594240.00	Above/ Below/Par
	Description:- Supply of Relay Non-AC immune , plug in type, style QN1, neutral line, 24V or 50V DC, 8F/8B contacts metal to carbon with plug board, retaining clip and connectors confirming to BRS : 930, IRS: S - 34 and IRS: S - 23 (As applicable) or similar Inspection-RDSO							
71	c	80.00	Numbers	5142.40	411392.00	AT Par	411392.00	Above/ Below/Par
	Description:- Supply of Relay AC Immune, plug-in type, style 'QNA1'. Neutral line, 24V DC 12F/4B contacts, Front and back contacts metal to carbon, complete with plug board, retaining clip and connectors conforming to BRS: 931A, IRS S - 60, IRS : S - 34, IRS : S -23 (As applicable). or similar Inspection-RDSO							
72	c	90.00	Numbers	5142.40	462816.00	AT Par	462816.00	Above/ Below/Par
	Description:- Supply of Relay AC Immune, plug-in type, style 'QNA1', Neutral line, 24V DC 8F/8B contacts, Front and back contacts metal to carbon, complete with plug board, retaining clip and connectors conforming to BRS: 931A, IRS S - 60, IRS : S - 34, IRS : S - 23 (As applicable). or similar Inspection-RDSO							
73	c	1.00	Numbers	730558.54	730558.54	AT Par	730558.54	Above/ Below/Par
	Description:- Supply of OFC Hybrid Multi service 19" rack mountabledevice IPV6 ready with Auto Change Over featureV.21/V23 interface device supporting OSPF / IS-IS/BGP / LDP & L2 /L3features for switch and PDH / Elfacility MPLS PDMUJX . LVCD/Digital Axle Counter/MSDAC purpose with four tributary slots & front panelQuad indication status vide LEDs, Optical support vide4SFP port supporting TDMoIP / IPMPLS in the unitsupporting dual core OFC and Four 100/1000mbpsEthernet port (POE required at site supporting 802.3af/ at) for surveillance/smoke detector,optical SFP portsprovided distance support to be 20 KMs, unit to havetwo E&M card / module each card / module supportingfour 2W/4W configurable & four quad port 2W/4W oreach module without change over feature of 8 portE&M as per site condition. Each port configurable tosupport axle counter/UFSBI/control phone/EC/RTU andone telnet/SNMP port, unit to support 04 El ports inaddition to 04 El ports for internal mapping of PDHtime slots & SFP ports of TDMoIP/ IPMPLS dual DCpower supply 48VDC VDC support , unit to supportchange over mechanism automatic between E&M(V.21) to El port & optical fiber TDMoIP (SFP) & quadpath for E&M interface option, cable to be providedalong with each E&M module . Equipment should beable integrate with direct optical fibre & STM El &IPMPLS 1Gbps ports FABIO 2CX+/OFC/ DC & module2W/4W four port E&M(1+1) protection, the unit to beable to integrate on 1Gbps with IPMPLS devices andcan be networked ; Voice Module 10 port FXO : 01number , 10 port FXS unit to be capable to accommodate and map on El or 1Gbps as required Make:-FABIO 2CX + / RAD / CISCO / WAVES /TANSY or similar. Inspection RITES							
74	c	1.00	Numbers	34648.24	34648.24	AT Par	34648.24	Above/ Below/Par
	Description:- Installation of Integrated Multiplexer supplied above							
75	c	1.00	Numbers	156757.40	156757.40	AT Par	156757.40	Above/ Below/Par
	Description:- Supply, installation & commissioning of 230V AC/48V DC, 50 Amp with 25A (2+1) SMPS based power plant as per Spec .No. RDSO/SPN /TL/ 23/99 (Ver.3) or latest. Inspection-RDSO							
76	a	1.00	Numbers	123220.99	123220.99	AT Par	123220.99	Above/ Below/Par
	Description:- Supply, installation, Charging, commissioning and Transportation of 48Volt/300 AH VRLA (Valve Regulated (Sealed) Lead Acid) Battery (each set consists of 24 nos. of 2V, 300AH cell) as per RDSO Spc. No. IRS-S-93/96(A) (Amd.-1) or latest Make : Amara Raja or Similar along with inter cell connectors. Battery stand & all associated accessories as detailed in annexure as advised by Site Engineer. Charging should be approved by Railway Engineer In-Charges.- 48 V ,300 AH (24 nos. of 300 AH cells of 2.0 volt each.) VRLA Inspection-RDSO							
77	c	2.00	Set	228834.45	457668.90	AT Par	457668.90	Above/ Below/Par
	Description:- Supply, installation, testing & commissioning of Modular Power supply Arrangement for VDU (42"-85") and Industrial PC (Embedded PC) with input and output redundancy arrangement and hot pluggable modules in set. One set Consists of :- 1. Input O-Ring diode Module with potential free-1 no contacts (PFC) for two 110V DC sources from IPS and Single 110V DC Bus. Quantity : 1 No. (as per RDSO TAN No. STS/E/TAN/3012 Version 3.0 Dated.03.11.22 or latest for VDU/ Embedded PC power supply arrangement) 2.Isolated Inverters (Master/Slave), Input 110 V DC, Output : 110/120 V AC 500 VA Quantity : 2 Nos. 3. Isolated DC-DC Converters, Input 110V DC, Out Put 24V DC/10A , Quantity : 2 nos. 4.3U SS Rack with back Panel mother Board/front panel power connectors inverter auto changer over switch and all required changeover switch and all required protection circuits (3U height for main rack 132.5mm +/- 10% & 1U height for mounting 44.5mm +/-10%) Quantity; 1 No. (Total 4 items). Inspection-RDSO							
78	c	1.00	Numbers	375048.14	375048.14	AT Par	375048.14	Above/ Below/Par

DANAPUR DIVISION-S AND T/EAST CENTRAL RLY TENDER DOCUMENT

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

	Description:- Supply of standard 19" Rack Mountable LER 60 Gbps Full duplex Forwarding capacity or higher , 1+1 Redundant control plane, 1+1 redundant DC power supply to support 4x10GSFP+ ports (distributed in Minimum two cards) , 8x1GSFP Ports & 4x1G ports copper for RJ45 SFP (distributed in Minimum two cards)+ 16E1(2x8 Port or 1x16 Port)(G.703) CES interface, modules not included , LER to have sufficient slots (clause 1.5 to support all the required interfaces) The router should support all the software features, MTCTE Certification, Environmental Standards and Security features as mentioned in RDSO technical document no STT/TAN/IP-MPLS/2020 Ver 2.0 or latest for the LER Router and RDSO letter RDSOTELE0LKO(TECH)/8/2020-Telecom Directorate/ RDSO dated. 29.03.2023 or latest. Inspection-RDSO							
79	c	1.00	Numbers	12328.15	12328.15	AT Par	12328.15	Above/ Below/Par
	Description:- Installation, Commissioning & Testing of LER IP MPLS Routers including supply & installation of all the accessories like Power cable, Earthing Cable, Optical PatchCords of 3 mtr- 4 Nos for LER& 8 Nos for LSR s, Cat 6 PatchCords of 1 mtr -4 Nos, one 6AMCB for each LSR and LSR wiring etc. as required for Routers. Supply- Inspection- Consignee							
80	c	1.00	Numbers	49320.65	49320.65	AT Par	49320.65	Above/ Below/Par
	Description:- Supply & Installation of 19" 42U 1200mm Depth Telecom Rack with Standard Accessories (Closed type) with front door Glass type, all doors should be removable type [Detailed Specification in Technical Document]. (Inspection: RITES/Third Party agency) Supply- Inspection- Consignee							
81	c	1.00	Numbers	304849.54	304849.54	AT Par	304849.54	Above/ Below/Par
	Description:- Supply of all equipment for VoIP control communication with provision for 8 analog ports at a station except control phones, ringers, and analog railway phones. Networking equipment along with Network Rack(6U) shall be provided which shall include :- Managed Router with Minimum 02 No.s 10/100/1000 Base Tx Ethernet WAN ports as per IEEE 802.3u specification and 4 No.s switching ports, ports shall be combo ports to support either RJ 45 UTP or SFP for Optical fibre connectivity as per field requirement - Layer 2 Managed POE Switch - Minimum 8 Port. Inspection-RDSO							
82	c	1.00	Numbers	20600.00	20600.00	AT Par	20600.00	Above/ Below/Par
	Description:- Installation & Commissioning of VoIP control communication equipment at a station. This includes proper wiring of data cables, power cables, telephone cables, housing of equipment in the racks/cabinets etc. All installation material like PVC pipes, flexible pipes, electrical MCB/ switch/socket/boards etc. has to be arranged by the bidder. Railways shall provide PIJF cable pairs from the OFC room till the SM room.							
83	c	1.00	Set	154247.24	154247.24	AT Par	154247.24	Above/ Below/Par
	Description:- Supply, Installation, Testing & Commissioning of Networkable Single loop addressable Fire alarm Control panel expandable upto 2 loops & interface with GSM/LTE module working as per RDSO/SPN/217/2021 ver-3 or latest. The control panel shall be networkable to Zonal /Divisional Headquarters preferably over TCP/IP and shall have clock synchronization facility. This schedule includes supply of TCP/IP converter/ Networking card. The control panel shall have provision of Graphical software to enable remote monitoring of entire fire detection and alarm system of a station from Head Quarters. The control panel shall be designed to work on power supply of 110V/230V AC as well as on DC battery backup of adequate capacity to work upto 24 hrs. Backup. The Power supplies like batteries and chargers shall be supplied by the contractor. The Control Panel shall have means for the user to visualize and interact with the complete Automatic Fire Detection and Alarm System layout through a user-friendly software executable on a standard Windows based Personal Computer. It shall be possible to download data and extend alarms from Control Panel through suitable ports like RS485/RS232/USB/TCP/IP into a PC/Laptop available with SSE at the installation and remote location (Divisional Control room) operating on Windows platform. The software for downloading and analysing fault data shall be provided & shall be compatible with the latest windows operating system. Detection, actuation, and control system shall have provision for automatic as well as manual operation. The GSM/LTE module for interfacing with Control panel duly providing compatible SIM with SMS facility on minimum of 5 numbers (users) and all other accessories. Spares cost are also included & to be supplied as per RDSO para no. 4.15 Supply-RDSO							
84	c	1.00	Set	306211.18	306211.18	AT Par	306211.18	Above/ Below/Par
	Description:- Supply, Installation ,testing and commissioning of single channel laser or High power LED based Aspiration detection unit (for AC room) with area covering 5000 sq. ft. with programmable 4 stage alarm generation and with 4 addressable modules. It should have auto cleaning facility in optical chamber, electronic discrimination of particle size, ultrasonic air flow sensing auto learn feature with TCP/IP network capability, the aspiration system shall also include external power supply unit with battery backup. Approval-UL/LPCB/VDS listed and shall comply to specification No.RDSO/SPN/217/2021 ver-3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
85	c	30.00	Numbers	4250.36	127510.80	AT Par	127510.80	Above/ Below/Par
	Description:- "Supply, installation testing & commissioning of Heat and smoke multi sensor with back box with integral short circuit isolator as per specification No. RDSO/SPN/217/2021 ver-3 or latest and required to be provided at suitable locations inside the diesel generator room, battery room, ASM room, and other S&T service rooms as directed by the Railway site Engineer. The location of fixing is to be meticulously decided so that full advantage of the system is achieved. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO"							
86	c	1.00	Numbers	8783.92	8783.92	AT Par	8783.92	Above/ Below/Par
	Description:- Supply, Installation and Testing, commissioning of Audio Visual alarm (Hooter and strobe) with back box controlled through addressable control model. Visual Alarms (Strobe): It shall be preferably flashing type RED/WHITE Color. Audio Alarms (Hooter): It shall be preferably with Piezoelectric type sounder. The sound level shall be preferably adjustable type up to 90dB at a distance of 1m as per specification No. RDSO/SPN/217/2021 Ver - 3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
87	c	1.00	Numbers	6051.04	6051.04	AT Par	6051.04	Above/ Below/Par
	Description:- Supply, Installation and Testing, commissioning of Analogue Addressable and resettable Manual call point with back box with integral short circuit isolator, Analogue addressable protocol having status LED for alarming & standby mode, Binary coded dip switch addressing. It shall have inbuilt fault isolator or alternate arrangement which shall isolate the Manual Call Point in case of open/short circuit fault within it as per specification No. RDSO/SPN/217/2021 ver-3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
88	c	1.00	Numbers	4657.46	4657.46	AT Par	4657.46	Above/ Below/Par
	Description:- "Supply, installation, Testing and Commissioning of Analogue Addressable type Isolator modules device for isolating in case of any fault, complying to the RDSO/SPN/217/2021 ver-3 or latest. Inspection by Rep. of Railway Engineer. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO"							
89	c	1.00	Numbers	4828.56	4828.56	AT Par	4828.56	Above/ Below/Par
	Description:- Supply, Installation, Testing and Commissioning of Relay module with back box and all other accessories as per RDSO/SPN/217/2021 ver-3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
90	c	1.00	Numbers	91103.08	91103.08	AT Par	91103.08	Above/ Below/Par
	Description:- Supply, installation, testing & communication of Linear Heat Sensing (LHS) Interface module with all accessories for integration with main line fire alarm control panel as per RDSO specification No. RDSO/SPN/217/2021 ver-3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
91	c	50.00	Metre	522.74	26137.00	AT Par	26137.00	Above/ Below/Par
	Description:- Supply, Installation Testing and commissioning of Analogue type Linear Heat Sensing cable with required module to be integrated on main Fire Alarm Panel as per specification No. RDSO/SPN/217/2021 ver-3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
92	c	100.00	Metre	165.20	16520.00	AT Par	16520.00	Above/ Below/Par
	Description:- Supply, Installation Testing and commissioning of FRLS/Fire Survival Circuit Integrity Cables and power cable with all accessories for connection of Fire Alarm devices specification No. RDSO/SPN/217/2021 ver-3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
93	c	100.00	Metre	624.22	62422.00	AT Par	62422.00	Above/ Below/Par

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

	Description:- Supply, Installation, Testing & Commissioning of UL/LPCB/VDS listed CPVC Pipe with suitable diameter as per requirements & pipe accessories for the Aspiration detection shall comply to RDSO/SPN/217/2021 ver-3 or latest. Spares cost are also included & to be supplied as per RDSO para no. 4.15. Supply- Inspection-RDSO							
94	c	10.00	Numbers	4337.68	43376.80	AT Par	43376.80	Above/ Below/Par
	Description:- Supply of CO2 Fire extinguisher 4.5 kg capacity confirming to IS 15683: 2018 or latest with ISI mark provided with all fittings and accessories. Inspection-Consignee							
95	c	1.00	Numbers	6625.58	6625.58	AT Par	6625.58	Above/ Below/Par
	Description:- Fabrication, supply & wiring, installation of Dual tone buzzer with flasher arrangement 25W horn (Make of any ISI approved firm) working voltage as per circuit design and as per instruction of site Incharge. Make- ACES ENTERPRISE or better							
96	c	1.00	Numbers	5000.00	5000.00	AT Par	5000.00	Above/ Below/Par
	Description:- Supply of Track Feed Charger Monitoring Panel suitable for monitoring of Track feed Battery charger and indicate the failure of the same by an Auto visual alarm on panel as per site requirement and instruction of Site Engineer. Specification: 1) Input voltage : i) 24V DC DC-10%+20%, ii) 110V AC: 10%+20%, 2) Type: Wall mounting type, 3) Component on Front Panel: Buzzer reset push button, 4) Indication: i) Green for "Healthy" , iii) Red for "Trip/fail" in two zone for Up/DN side TFBC's. 5) Termination: i) 2 Terminals for DC Input (24 VDC), ii) 4 Terminals for AC Input (110VAC), 6) Configuration Logic shall be used of TFBC's Potential Free Contact for indication of failure. The configuration of panel should be in two zone UP/DN by connecting/ wiring all TFBC's of UP/DN side separately, 7) Size 400mm X 300mm X 150mm 8)Construction: Metal box duly painted and written SMMP (Signal Maintainer Maintenance Panel). The unit is suitable for Wall mounting type. The input terminals are brought out in Front at the Bottom of the cabinet along with Changeover potential free contactfor sensing the LED indication is provided on Front Panel along with BuzzerReset, 9) All the materials i.e LED, Terminal, Buzzer etc. to be supplied by Contractor. Inspection-Consignee							
97	c	1.00	Job	6500.00	6500.00	AT Par	6500.00	Above/ Below/Par
	Description:- Wiring of all TFBC's with potential free contact in required configuration i.e series/parallel to make indication of failure of TFBC's in Monitoring Panel and Installation, Fixing, wiring, testing & commissioning of Track Feed Charger Monitoring Panel complete in all respect in ESM room as per instruction of site incharge. This includes:- (a) Wiring, soldering, termination of cable etc. complete in all respect of all TFBC's potential free contact of UP/DN side separately. (b)Wiring, soldering, termination of cable etc. complete in all respect on terminal of Monitoring panel as required for connectingthe UP/DN side all TFBCs contacts in two zone on monitoring panel. All required materials like tools, soldering materials etc to be provided/ arranged by Contractor. Note:- Railway will supply the cable/advise the spare cable as available. (Job per station)							
98	c	3.00	Numbers	43445.57	130336.71	AT Par	130336.71	Above/ Below/Par
	Description:- Design, fabrication & supply of fuse Auto Changeover system for 24 Nos. of external Non Deteriorating Type or 'G' Type fuses from 4 Amp to 10 Amp capacity including extender fixing plates of stainless steel of 1.5 mm with suitable fixing holes as per RDSO spec no.-RDSO/SPN/209/2012 rev 2.0 or latest. (Unit should be read as Per Module) Supply- Inspection-RDSO							
99	c	12.00	Numbers	26343.21	316118.52	AT Par	316118.52	Above/ Below/Par
	Description:- Design, fabrication & supply of fuse Autot Changeover system for 32 Nos. of external Non Deterating type or 'G' Type fuses from 0.6 Amp to 4 Amp capacity including Extender fixing plates of stainless steel of 1.5 mm with suitable fixing holes as per RDSO spec no.-RDSO/SPN/209/2012 Rev 2.0 or latest. (Unit should be read as Per Module) Supply- Inspection-RDSO							
100	c	25.00	Numbers	786.41	19660.25	AT Par	19660.25	Above/ Below/Par
	Description:- Installation, wiring, testing and commissioning of Fuse Auto Change over System (FACS). This includes provision of common Buzzer & indication at ASM Room & ESM Duty Room and painting of fuse details. This also includes fabrication of frame for installation of FACS at Station/ IBH/ Relay Hut where installation of relay racks not feasible. (Unit should be read as Per Module) Supply- Inspection-Consignee							
101	c	1.00	Numbers	6000.00	6000.00	AT Par	6000.00	Above/ Below/Par
	Description:- Supply & Installation of MS Stand (Mountable Rack complete with all fitting etc.) of dimensions 80" X 21" with 7MM holes, suitable for Installation & Commissioning of Fuse Auto Changeover System as per RDSO Spec. RDSO/SPN/209/2012 along with necessary accessories like Triangular Base, Insulators, Nuts, Bolts, support angles etc. Supply- Inspection-Consignee							
102	c	1.00	Numbers	1000.00	1000.00	AT Par	1000.00	Above/ Below/Par
	Description:- Fabrication, supply &wiring, installation of remote buzzer for Fuse Alarm Systemas per Tech. Spec.(Common Audio Visual alarm unit for FACS as per RDSO/SPN 2009/2012 rev.1.0 or latest at panel RR/ESM room as per instruction of site Incharge. Supply- Inspection-Consignee							
103	c	2.00	Set	106800.29	213600.58	AT Par	213600.58	Above/ Below/Par
	Description:- Supply of Electrically Operated Lifting Barrier complete set (110V DC/AC with/without hand Generator) complete with GI OCTAGONAL BOOMS (as per RDSO drg No-RDSO/S 11600 and Motorized boom locking/ unlocking arrangement with limit switches with/without hand generator back up as per RDSO Specs No RDSO/SPN/208/2012 ver 2.0 or latest. One set consisting 02 Nos of Barriers of 32 ft long GI sheet Booms along with Control Panel and Boom locking with all accessories needed for installation, Spares & tool kit mentioned in RDSO Spec SPN/208/2012 clause 10.1 & 10.2.- Execution							
104	c	2.00	Set	445339.59	890679.18	AT Par	890679.18	Above/ Below/Par
	Description:- Supply of Electrically Operated Lifting Barrier complete set (110V DC/AC with/without hand Generator) complete with GI OCTAGONAL BOOMS (as per RDSO drg No-RDSO/S 11600 and Motorized boom locking/ unlocking arrangement with limit switches with hand generator back up as per RDSO Specs No RDSO/SPN/208/2012 ver 2.0 or latest. One set consisting 02 Nos of Barriers of 32 ft long GI sheet Booms along with Control Panel and Boom locking with all accessories needed for installation, Spares & tool kit mentioned in RDSO Spec SPN/208/2012 clause 10.1 & 10.2.- Supply Inspection RDSO							
105	c	2.00	Set	245142.42	490284.84	AT Par	490284.84	Above/ Below/Par
	Description:- Supply and Installation of Sliding boom barrier as per signal Workshop Eastern Railway, Howrah drg no- BSA/29/730, BSA/29/731 & BSA/29/737. This includes supply of 8 Nos E-type lock with Key as per IRS spec. no- IRS/S-30/64 with latest amndt. Supply- Inspection- RITES							
106	c	2.00	Set	60389.01	120778.02	AT Par	120778.02	Above/ Below/Par
	Description:- Casting, concreting & Curing of foundatiuon(1:3:6) for sliding Boom as perdrgr no-SGW-SDAH/Sliding gate foundation/ 2012 including supply & fixing of Holding down bolts with washers and nuts , MS plates of size 350MMX350MM X8MM, cement etc 12 foundations in each set.							
107	c	2.00	Per Gate	3996.30	7992.60	AT Par	7992.60	Above/ Below/Par
	Description:- Installation & Commissioning of Sliding Boom gate. This includes levelling, fixing of sliding boom with fixing of E-type lock etc..							
108	c	2.00	Set	1003000.00	2006000.00	AT Par	2006000.00	Above/ Below/Par
	Description:- Supply, installation and commissioning of Block proving by Axle Counter as per RDSO Specification no.- IRS:S 105/2012 (Ver 0) or latest amndt using UFSBI (Universal Fail Safe Block Interface) & Block Panel for double line operation including auto change over card (pallelleing of Relay contact and validation of relays in datalogger is included in installation and commissioning.).Supply- Inspection-RDSO							
	S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount
	Schedule ()	D-Annexure - Z (Schedule-4)						Bidding Unit
	d	1.00	Station	24102414.25	24102414.25	AT Par	24102414.25	Above/ Below/Par

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

1	Description:- Design, manufacture, supply of Hot standby architecture Electronic Interlocking (Centralized EI system) system complete as per RDSO Specification No. RDSO/SPN/192/2019 Ver.2.0 with latest amndt.. (Inspection - RDSO) .EI mainly consisting of microprocessor based CPU card, output card, input card, interfacing equipment and Datalogger protocol converter, interfacing for outdoor function, Rack for EI card, Relay rack, [65" Operator VDU (2Nos) & 65" maintenance VDU (01 Nos) with terminal embeded including furnitures, printer, UPS (Each set having 1 PC with 2 Nos. Monitor)], Racks, Relays, Interlocking cables, Rack fixture mounting arrangements and accessories. PC based Operator's/ maintenance console with complete stand by set, Embedded Industrial grade fanless PCs should be of rugged. All wiring is to be done to make EI operational which includes full power wiring also as per requirement. SM 480 Relay, External SM key Box. Tenderer should submit break up details for interfacing with outdoor signalling gears with rate along with offer for interlocking of each station. - for Bela Station Inspection-RDSO							
2	a	1.00	Station	2364898.90	2364898.90	AT Par	2364898.90	Above/ Below/Par
Description:- Supply of essential spares minimum @ 10% itemwise details to be supplied with unit rate, quantity and brief description of their function should be listed by tenderer. for Bela Station Inspection-RDSO								
3	d	1.00	Station	1611478.25	1611478.25	AT Par	1611478.25	Above/ Below/Par
Description:- Installation, wiring, programming, testing and commissioning of Electronic Interlocking system as per interlocking plan. It includes networking/ centralization of maintenance terminal at divisional HQ. for Bela Station								
4	d	1.00	Station	147589.67	147589.67	AT Par	147589.67	Above/ Below/Par
Description:- Supply of "As made document and manuals" as per the tender condition and specification (all documents & drawings). for Bela Station Inspection-Consignee								
5	d	1.00	Station	682071.63	682071.63	AT Par	682071.63	Above/ Below/Par
Description:- Maintenance and supervision of SSI equipments for one year. for Bela Station								
6	d	1.00	Station	140165.84	140165.84	AT Par	140165.84	Above/ Below/Par
Description:- Training on EI system for Technician, Supervisors & Officers. for Bela Station								
7	d	1.00	Station	1002700.00	1002700.00	AT Par	1002700.00	Above/ Below/Par
Description:- Supply of various sorts of Relays. for Bela Station Inspection-RDSO								
8	d	1.00	Set	734665.98	734665.98	AT Par	734665.98	Above/ Below/Par
Description:- "Supply installation testing and commissioning of Pyrotech work space new modular control desk. Note:- The control shall be made suitable to place two UFSBs on each side of the control desk and installation of VDU mounting wall to accommodate two VDU. for Bela Station Supply Inspection-Consignee"								
9	d	1.00	Set	338764.79	338764.79	AT Par	338764.79	Above/ Below/Par
Description:- EI special earthing (Ring Earthing) of SSI equipments,relay racks,power equipments etc. to be done along with the supply of all requisite stores as per latest Guidelines of RDSO & Railway Board - Bela Station								
10	d	10.00	Numbers	7298.66	72986.60	AT Par	72986.60	Above/ Below/Par
Description:- Supply & installation of 230V AC /110V DC /24V DC Surge protection device. for Bela Station Supply Inspection-Consignee								
11	d	1.00	Numbers	150450.00	150450.00	AT Par	150450.00	Above/ Below/Par
Description:- Protocol Converter for data logger with all accessories for all unit. for Bela Station Supply Inspection-Consignee								
12	d	10.00	Numbers	10500.00	105000.00	AT Par	105000.00	Above/ Below/Par
Description:- Supply of FMX Box/12U RACK Inspection-Consignee								

3. ITEM BREAKUP

Schedule A-Annexure - Z (Schedule-1)						
Item- 1	SOR items					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Excavation of trench in all kinds of soil and refilling of trenches (1.0 Mtr. Depth 300 mm width)-Without bricks	Metre	8000.00	9.00	72000.00
2	2	Excavation of trench in all kinds of soil and refilling of trenches (0.5 Mtr. Depth 300 mm width) - Without bricks	Metre	500.00	8.00	4000.00
3	3	Excavation, trenching, earth work and reinstatement of track while track crossing.	Metre	100.00	35.00	3500.00
4	4	Reinstatement of platform and repairing to original state after cable laying work.	Metre	100.00	100.00	10000.00
5	5	Laying cable of different sizes as per cable route plan approved by Railway and meggering of all main & tail cables as per technical specification of tender.- 2 core to 12 core signalling cable.	Kilometre	80.00	2900.00	232000.00
6	6	Laying cable of different sizes as per cable route plan approved by Railway and meggering of all main & tail cables as per technical specification of tender- Telecom Cable -Quad cable	Kilometre	8.00	3000.00	24000.00
7	7	Supply and fixing of G.I. Pipe with threaded collars of 100 mm nominal bore specn.No.IS 1239 medium grade. Perforated of required length on bridge/below metalised road/L-Xing/Culvert as per technical specification of tender.- Supply portion for the G.I.Pipe & collars. Supply- Inspection-Consignee	Metre	100.00	335.00	33500.00
8	8	Supply and fixing of G.I. Pipe with threaded collars of 100 mm nominal bore specn.No.IS 1239 medium grade. Perforated of required length on bridge/below metalised road/L-Xing/Culvert as per technical specification of tender.- Execution with remaining miscellaneous materials	Metre	100.00	15.00	1500.00
9	9	Supply of CLS Post 4.5 mtr. and Ladder 4.5 Mtr. With bases as per RDSO DRG.No.SA.5533/ADV and RDSO Spec. No.S6-81. Inspection-Consignee	Numbers	7.00	7150.00	50050.00
10	10	Supply of CLS Post 3.5 mtr. and Ladder 3.5 Mtr. With bases as per RDSO DRG.No.SA.5533/ADV and RDSO Spec. No.S6-81. Inspection-Consignee	Numbers	4.00	6050.00	24200.00
11	11	Supply of offset bracket for colour/position light signal (140 mm/90mm outside Dia as per site requirement) post with U- clamps,nuts, washers complete as per RDSO DRG. No.SA 23080/ADV/ ALT-1. Inspection-Consignee	Numbers	7.00	775.00	5425.00
12	12	Casting, concreting and curing of foundation for Main signal and as per DRG.No.SGW/MGS/51/91 including cost of all materials required for casting and concreting and provision of holding down bolts & nuts.	Numbers	11.00	2300.00	25300.00
13	13	Casting,concreting and curing of foundation for Shunt signal and as per DRG.No.SGW/MGS/51/91 including cost of all materials required for casting and concreting and provision of holding down bolts & nuts.	Numbers	5.00	1000.00	5000.00
14	14	Installation,erection and wiring of CLS including laying out of tail cable from location box and earthing of CLS as per technical specn.In the tender. 3 Aspect CLS	Numbers	4.00	850.00	3400.00
15	15	Installation, erection and wiring of CLS including laying out of tail cable from location box and earthing of CLS as per technical specn.In the tender. 2 Aspect CLS	Numbers	7.00	750.00	5250.00
16	16	Installation, Erection and wiring of direction type route indicator. 2 Way	Numbers	1.00	500.00	500.00
17	17	Installation, Erection and wiring of direction type route indicator. 3 Way	Numbers	1.00	700.00	700.00

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

18	18	Installation, Erection laying out of tail cable from Loc. Box and wiring of Shunt Signal as per Technical Specification in the tender.- independent position light shunt signal	Numbers	5.00	200.00	1000.00
19	19	Installation, Erection laying out of tail cable from Loc. Box and wiring of Shunt Signal as per Technical Specification in the tender.- On offset bracket	Numbers	9.00	200.00	1800.00
20	20	Installation,Erection & laying out of tail cable from loc.box and wiring of Calling On signal on same post below main signal as per technical specification in the tender.	Numbers	2.00	200.00	400.00
21	21	Supply of PBT ARA terminal as per IRS SPECN No. IRS:S-75-91- 6 way Supply-Inspection RDSO	Numbers	250.00	220.00	55000.00
22	22	Supply of Bakelite Strip/Sheet of Size (950 x 75 x 12) mm. For fixing 30Nos. ARA terminals/ Fuse base terminals/Fuse base. Inspection-Consignee	Numbers	100.00	160.00	16000.00
23	23	Casting,Concreting and Curing of foundation and erection for full apparatus case (GKP-type)as per DRG No.SGW/MGS/L1/91 includong cost of all materials required for fixing holding down bolts, casting, concreting and fixing of "E" type lock.Note: i)The contractor will provide holding down bolts. ii)Bottom of appratus cases should be filled with sand and the top surface covered with masonry work and neat cementing.	Numbers	70.00	1550.00	108500.00
24	24	Casting,Concreting and Curing of foundation and erection for Half apparatus case(GKP-type) as per DRG No.SGW/MGS/L1/91 including cost of all materials required for fixing holding down bolts,casting concreting and fixing of E type lock. Note: i)The contractor will provide holding down bolts. ii) Bottom of appratus cases should be filled with sand and the top surface covered with masonry work and neat cementing.	Numbers	5.00	1275.00	6375.00
25	25	Casting,Concreting and Curing of foundation and erection for quarter apparatus case(GKP- type) as per DRG No.SGW/MGS/L1/91 including cost of all materials required for fixing holding down bolts,casting concreting and fixing of E type lock. Note: i)The contractor will provide holding down bolts. ii) Bottom of appratus cases should be filled with sand and the top surface covered with masonry work and neat cementing.	Numbers	25.00	1000.00	25000.00
26	26	Fixing,wiring of terminal strips,bakelite strip, transformers, relays fuses with base and supply and fixing of shelves for full appratus case. (All materials except transformers,relay,terminal strips, bakelite strip and fuses with base to be supplied by the contractor.).	Job	70.00	1450.00	101500.00
27	27	Fixing,wiring of terminal strips, bakelite strip, transformers, relays, fuses with base and supply and fixing of shelves for half apparatus case n. (Materials other than transformers, relay, terminal strips, bakelite strip and fuses with base to be supplied by the contractor.)	Job	5.00	850.00	4250.00
28	28	Supply of Bakelite Strip/Sheet of Size (950 x 75 x 12) mm. For fixing 30Nos. ARA terminals/ Fuse base terminals/Fuse base. Inspection-Consignee	Job	10.00	390.00	3900.00
29	29	Supply of track lead junction box complete with bush and ARA terminals conforming to IRS:S-75/ 91. Angle iron of Size (1500 x 50 x 50) mm to hold the junction box and for fixing cable entry pipe (40 x 500) mm. Only DRG.No.SA-20101/M. Note: Angle should be 6 MM thick. Inspection- TLJB Consignee, ARA terminal -RDSO	Numbers	100.00	450.00	45000.00
30	30	Supply of B-Type choke coil having annealed enamelled copper wire for DC track circuit SPECN.No.IRS-S-65/ 83(Latest) Inspection-RDSO	Numbers	32.00	1900.00	60800.00
31	31	Supply of PBT fuse block with inserts cartridge type, to be mounted inside the location Box/ Relay Rack- Fuses (2A,IRS:S-78/92) Inspection-RDSO	Numbers	200.00	27.00	5400.00
32	32	Supply of PBT fuse block with inserts cartridge type, to be mounted inside the location Box/ Relay Rack- Fuse Base (DRG No.SA-23748,IRS:S-75/91) Inspection-RDSO	Numbers	200.00	80.00	16000.00
33	33	Supply of 8 SWG soft drawn GI wire bond pieces (1320x4)mm. Resistance upto 19.5 OHM/MT.To IS-280 & IS - 23. Inspection-Consignee	Numbers	2500.00	4.00	10000.00
34	34	Supply of channel Pin with single groove 7.2 mm Dia for 4 mm Dia bond wire to DRG.No.S-69/M & IRS Specn.IRS:S-S17. Inspection-Consignee	Numbers	5000.00	1.80	9000.00
35	35	Installation wiring,testing and commissioning of Single/Double rail DC track circuit as per approved track circuiting plan.The work includes track battery charging and installation,track bonding (double) with 8 SWG soft GI Wire laying of tail cable with track lead junction box,rail connector with Galvanised iron wire track jumpering with supporting arrangement.- Track Circuit (Beyond 200 Mtrs.)	Numbers	12.00	1100.00	13200.00
36	36	Installation wiring,testing and commissioning of Single/Double rail DC track circuit as per approved track circuiting plan.The work includes track battery charging and installation,track bonding (double) with 8 SWG soft GI Wire laying of tail cable with track lead junction box,rail connector with Galvanised iron wire track jumpering with supporting arrangement.- Short length track circuit upto 200 Mts.	Numbers	9.00	1100.00	9900.00
37	37	Installation wiring,testing and commissioning of track circuit involving points & crossing as per Track circuiting plan.Track Battery charging and installation including drilling 9/32" hole on rails. Installation of bonding,double with 8 SWG soft GI Wire insulation of strecher bars (leading &following) ,guage/crossing tie plates involving cutting & rivetting/welding of angle clit,split stracher bars,fixing of track lead junction boxes.Laying of tail cable	Numbers	11.00	1100.00	12100.00
38	38	Supply of point JB fitted with 18 Nos. 1 way ARA PBT terminal block conforming to IRS - S- 75/91 with 3 Nos. of 40mm Bore. GI pipe 600 mm long as per DRG No.SGW/MGS/PT4/91 fixed on hard wood plank with U-channel (75 x 40 x 1500) mm for fixing. Inspection- Point JB Consignee, ARA terminal -RDSO	Numbers	12.00	1150.00	13800.00
39	39	Supply of complete ground fittings for point machine, including insulated stretcher Bar Switch extension piece etc. and all other accessories required for installation- For IRS point machine Spec IRS-24-90, Turn out [RDSO DRG No- SA- S3261 62 01 Inspection-Consignee	Numbers	12.00	4300.00	51600.00
40	40	Dismantling of existing point fittings and installation of already prepared and matched point fitting sets for point machine of IRS 24/90 type with final testing and commissioning from panel as per technical specification including transportation from railway store.- Turn out (Facing point layout)	Numbers	12.00	3000.00	36000.00
41	41	Charging of lead acid secondary cells of various capacities as per manufactures instruction/railway engineer's instructions acid & distilled water will be supplied by the contractor. - 80 AH (12 Cell)	Set	8.00	1800.00	14400.00
42	42	Supply of CT rack (DRG.NO.S&T/C-19/2001/ER) complete with all fittings including 6 way terminals or wago terminal as per Spec.No.IRS-79/92. Inspection-Consignee	Numbers	3.00	15000.00	45000.00
43	43	Installation of cable termination Rack with scaffolding materials;ladder for supporting outdoor cable;wire guide;complete with other necessary hardwares as per requirements of Rly. & erection materials.(Rate & Staion Wise Qty. to be specified by the tenderer.)- Upto 4 to 5 Line Station	Station	1.00	1500.00	1500.00
44	44	"Preparation of cable route plan,cable core chart ,power supply layout,cable termination chart in relay room and location box.Location wiring plan,cable insulation chart,fuse analysis, equipment disposition plan,track bonding plan, as per railways practice. Note- I) All the above plans for end bungalow also to be submitted.All diagrams/plans to be submitted in polyester film tracing to the railways along with 6 sets of ferro prints of the above. The diagrams/ plans should also be submitted in CD. - upto 4 line station"	Job	1.00	35000.00	35000.00
45	45	Supply of earth electrode.Materials to be procured as per E.Rly Sketch No.SGW/T/3/G/8/89. Inspection-Consignee	Numbers	100.00	500.00	50000.00
46	46	Supply of electrical key transmitter for crank handle interlocking arrangement siding control,LC Gate control. Inspection-RDSO	Numbers	10.00	2500.00	25000.00

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

47	47	Installation of electrical key transmitter on suitable bracket as per inspection of site engineer. ,wiring and testing of electrical key transmitter.	Numbers	10.00	3880.00	38800.00
					Total	1316550.00
Schedule Schedule B-Annexure - Z (Schedule-2)						
Item- 2 Non SOR Items						
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply of E-type lock without key,spec.no.IRS-S-30,Drg. no. S-3376/M key-S-3377/M. Individual number of miniature E locks and Normal size of locks required at site to be decided by the site engineer as per site requirement. Inspection-Consignee	Numbers	100.00	521.52	52152.00
2	2	Key for E type lock supplied above Inspection-Consignee	Numbers	50.00	78.31	3915.50
3	3	Supply of Miniature lock. Inspection-Consignee	Numbers	25.00	419.77	10494.25
4	4	Supply of full size location box as per design of GKP signal workshop Inspection-RITES	Numbers	70.00	9260.23	648216.10
5	5	Supply of half size location box as per design of GKP signal workshop. Inspection-Consignee	Numbers	5.00	7635.46	38177.30
6	6	Supply of quarter size location box as per design of GKP signal workshop. Inspection-Consignee	Numbers	10.00	4639.25	46392.50
7	7	Filling earth around location box/signal post for a width of 0.5 m on all sides, upto a level of 150 mm below the foundation top. This work includes consolidation of earth by watering.	cum	100.00	71.10	7110.00
8	8	Supply of Non deteriorating type low voltage cartridge fuse as per Spec. No. IRS/S/78/92. Round head type. 4 Amp. Capacity. Inspection-RDSO	Numbers	50.00	31.99	1599.50
9	9	Supply of Non deteriorating type low voltage cartridge fuse as per Spec. No. IRS/S/78/92. Round head type.- 6 Amp. Capacity. Inspection-RDSO	Numbers	200.00	36.57	7314.00
10	10	Supply of Non deteriorating type low voltage cartridge fuse as per Spec. No. IRS/S/78/92. Round head type.- 16 Amp. Capacity Inspection-RDSO	Numbers	250.00	30.17	7542.50
11	11	Supply of slotted angle (40 x 40 x 2 mm) Inspection-Consignee	Metre	50.00	93.99	4699.50
12	12	Supply of paper base hylum sheet 12 mm thick. Inspection-Consignee	Sqm	10.00	3153.01	31530.10
13	13	Supply and installation of portable CO2 extinguisher (4.5Kg.) Inspection-Consignee	Numbers	4.00	6280.93	25123.72
14	14	Supply of Chair PCH 7002 Godrej or similar Inspection-Consignee	Numbers	3.00	9533.53	28600.59
15	15	Supply of Chair KES-CH4 Godrej or similar Inspection-Consignee	Numbers	3.00	1715.21	5145.63
16	16	Supply of Table- T-8 Godrej or similar Inspection-Consignee	Numbers	2.00	6883.00	13766.00
17	17	Supply of Slimline store well plain Godrej or similar Inspection-Consignee	Numbers	2.00	9985.98	19971.96
18	18	Painting and numbering of all equipments such as Signals, Shunt Signals/Calling-On Signals,Electric Point machines,Track circuit equipments,Apparatus cases, Rod runs and its accessories, Junction boxes, Track lead junction boxes including existing gears. Painting shall consist of "2 coats" of "primer" and "3 coats" of "final paint". Note:- Paint should be ISI marked (Make Asean Paints or similar). Supply Inspection Consignee - Upto 8 lines stations	Station	1.00	11108.77	11108.77
19	19	Supply of indoor cable as per IRS-S-76/89. [40c x 0.6 mm] Inspection-RDSO	Metre	100.00	77.35	7735.00
20	20	Supply of PVC wire coil of size of colours as per instruction of site engineer in 100 mtr. Coils.Spec.no.IRS-S-76/89 material to be procured from RDSO approved firm only with performance guarantee.- 16/0.2 mm Inspection-RDSO (Unit- Per Coil)	Numbers	250.00	442.63	110657.50
21	21	Supply of PVC wire coil of size of colours as per instruction of site engineer in 100 mtr. Coils.Spec.no.IRS-S-76/89 material to be procured from RDSO approved firm only with performance guarantee.- 3/0.750 mm Inspection- RDSO (Unit Per coil)	Numbers	21.00	905.16	19008.36
22	22	Supply of PVC wire coil of size of colours as per instruction of site engineer in 100 mtr. Coils.Spec.no.IRS-S-76/89 material to be procured from RDSO approved firm only with performance guarantee.-7/0.75 mm Inspection-RDSO (Unit= per coil)	Numbers	10.00	1736.81	17368.10
23	23	Inter connection wiring with ladder arrangement from power supply equipment to relay rack,IPS, Data logger,Control panel,Block instruments,CTR etc.It also includes interconnection wiring with ladder arrangement between relay racks,CTR's, indication board and block instruments.This also includes termination of cables/wires on all the above and dressing,bunching etc.as required at site.Wire shall be 16/0.2mm for relays,3.0737 mm for MCB's and 7/0.75 mm for power wiring. Indoor cable 60 x 0.6 mm/40 x 0.6 mm as per IRS-S-76/89 or Latest for interconnection of indication board. Wires shall be procured from RDSO approved firm and inspected by RDSO.- Upto 4 lines stations	Station	1.00	47236.56	47236.56
24	24	Installation, commissioning & testing of LED signals. (Unit per Aspect)	Numbers	70.00	364.01	25480.70
25	25	Fixing of P/G/C marker with complete fittings as per instruction of site engineer.	Numbers	6.00	103.97	623.82
26	26	Supply of adjustable track feed resistance disc type 30 ohm as per RDSO Drg no. SA-20166/M/66 (adv) with latest amendments (with Phenolic moulded base) Inspection-RDSO	Numbers	32.00	278.40	8908.80
27	27	Releasing of signals and location boxes , other ground gears.	Station	1.00	11725.04	11725.04
28	28	Transportation of released materials except Rail posts, over head alignment to Store of SE/CON and stacking properly as per instruction of site Engineer.	Station	1.00	18227.35	18227.35
29	29	Supply of PVC switch board cable, pair twisted, conductor of size 0.63 mm. dia Annealed copper conforming to IRS-TC-24/91 or ITD 1138.- 10 Pair. Inspection-RDSO	Metre	200.00	36.49	7298.00
30	30	Supply of Thermoshrink jointing kit for 2T joints-6 quad. Inspection-RDSO	Numbers	15.00	1661.22	24918.30
31	31	Installation of Thermoshrink jointing kit	Numbers	15.00	1367.19	20507.85
32	32	Supply of 4 wire way station control equipments DTMF type (3 digit) with telephone, Power supply and battery back-up, Spec-IRS-TC@45<47@93 Inspection-Consignee	Numbers	1.00	4734.90	4734.90
33	33	Supply of cable termination box. Spec.no.IRS-TC-18-75 with locking arrangements and termination of derivation cable as per the technical supplements. -20 pairs Inspection-Consignee	Numbers	10.00	1420.47	14204.70
34	34	Supply of VF transformer Spec.IRS-TC-76-2006 or (latest) Inspection-RDSO	Numbers	15.00	679.24	10188.60
35	35	Supply of 4 wire DTMF way Station Control Telephone. Inspection-Consignee	Numbers	1.00	1506.81	1506.81
36	36	Supply of 4/2 wire control office head quarter equipment DTMF type (3 digit) with microphone, amplifier, loud speaker, head set and head phone. Spec- IRS-TC@45<47@93 Inspection-Consignee	Numbers	1.00	13910.63	13910.63
37	37	Installation & commissioning of way Station Control Equipment, 4 wire type as per arrangement decided by the engineer along with control board of Hylum sheet and wall fixing materials as per technical supplement.	Numbers	1.00	2076.71	2076.71
					Total	1329177.65

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

DANAPUR DIVISION-S AND T/EAST CENTRAL RLY TENDER DOCUMENT

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

1	The tenderer must have minimum average annual contractual turnover of V/N OR 'V' which ever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet	No	No	Allowed (Mandatory)
---	---	----	----	---------------------

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited 1) Three similar works each costing not less than the amount equal to 30% of advertised value of tender, or 2) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or 3) One similar work costing not less than the amount equal to 60% of advertised value of the tender. In case of tenders for composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender. Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. In such cases, what constitutes a component in a composite work shall be clearly pre-defined with estimated tender cost of it, as part of the tender documents without any ambiguity	No	No	Allowed (Mandatory)
2	Similar nature of work- Panel Interlocking/Route Relay Interlocking/Electronic Interlocking/IBH/ Automatic Signalling OR Any [Indoor or (Indoor +Outdoor)] signaling work involving Alteration/Modification in Panel Interlocking/Route Relay Interlocking/Electronic Interlocking/IBH/Automatic signalling Ref: (ECR/HJP letter No- ECR/HQ05nT/1/2020(Computer No- 81849) Dtd. 14.10.2025)	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer whether sole proprietor, a company or a partnership firm / joint venture (JV) / registered society / registered trust etc if they want to act through agent or individual partner(s), should submit along with the tender, a copy of power of attorney duly stamped and authenticated by a Notary Public or by Magistrate in favour of the specific person whether he/they be partner(s) of the firm or any other person specifically authorizing him/them to submit the tender, sign the agreement, receive money, co-ordinate measurements through contractor's authorized engineer, witness measurements, sign measurement books, compromise, settle, relinquish any claim(s) preferred by the firm andThe tenderer whether sole proprietor, a company or a partnership firm / joint venture (JV) / registered society / registered trust etc if they want to act through agent or individual partner(s), should submit along with the tender, a copy of power of attorney duly stamped and authenticated by a Notary Public or by Magistrate in favour of the specific person whether he/they be partner(s) of the firm or any other person specifically authorizing him/them to submit the tender, sign the agreement, receive money, co-ordinate measurements through contractor's authorized engineer, witness measurements, sign measurement books, compromise, settle, relinquish any claim(s) preferred by the firm and sign "No Claim Certificate" and refer all or any disputes to arbitration. sign "No Claim Certificate" and refer all or any disputes to arbitration.	No	No	Allowed (Mandatory)
2	Contractors are allowed to make payments against this tender towards bid security only through only payment modes available on IREPS portal like net banking, debit card, credit card etc. Manual payments through Demand draft, Banker cheque, Deposit receipts, FDR etc. are not allowed. The firm can also submit Bid security in the form of Bank guarantee Bond from a scheduled commercial Bank	No	No	Allowed (Mandatory)
3	If the bidders opt for submission of Bank Guarantee towards Bid security, the original Bank Guarantee should be delivered in person to the official nominated as indicated in the tender document before closing date for submission of bids (i.e. excluding the last date of submission of bids) (As Per Rly. Bds Letter No. 2022/CE- I/CT/GCC-2022/Policy dated 20.10.203, Advance Correction Slip No. 5).	No	No	Allowed (Mandatory)

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

4	The tenderer shall clearly specify whether the tender is submitted on his own (Proprietary Firm) or on behalf of a Partnership Firm / company / Joint Venture (JV) / Registered Society / Registered Trust etc. The tenderer(s) shall enclose the attested copies of the constitution of their concern, and copy of PAN Card along with their tender. Tender Documents in such cases are to be signed by such persons as may be legally competent to sign them on behalf of the firm, company, association, trust or society, as the case may be. (ii) In case tenderer is other than sole proprietorship firm, following documents shall be submitted by the tenderer: (a) Partnership Firm: The tenderer shall submit (i) a notarized copy of Partnership Deed or a copy of partnership deed registered with the registrar. (ii) a copy of Power of Attorney (duly registered as per prevailing law) in favour of an individual to sign the tender documents and create liability against the Firm. (b) Joint Venture (JV): The tenderer shall submit documents as mentioned in Clause 17 of the Tender Form (Second Sheet). (c) Company registered under Companies Act-2013: The tenderer shall submit (i) the copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company; and (ii) A copy of Authorization/Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. (d) LLP (Limited Liability Partnership) Firm: If the tender is submitted on behalf of a LLP Firm registered under LLP Act-2008, the tenderer shall submit alongwith the tender- (i) a copy of LLP Agreement, (ii) a copy of Certificate of Incorporation; and (iii) a copy of Power of Attorney/Authorisation issued by the LLP Firm in favour of the individual to sign the tender on behalf of the LLP Firm and create liability against the Firm. (e) Registered Society & Registered Trust: The tenderer shall submit (i) a copy of the Certificate of Registration, (ii) Deed of Formation; and (iii) a copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust. (iii) If it is NOT mentioned in the submitted tender that tender is being submitted on behalf of a Sole Proprietorship firm / Partnership firm / Joint Venture / Registered Company etc., then the tender shall be treated as having been submitted by the individual who has signed the tender. (iv) After opening of the tender, any document pertaining to the constitution of Sole Proprietorship Firm / Partnership Firm / Registered Company/ Registered Trust / Registered Society etc. shall be neither asked nor considered, if submitted. (v) A tender from JV / Partnership firm etc. shall be considered only where permissible as per the tender conditions. (vi) The Railway will not be bound by any change in the composition of the firm made subsequent to the submission of tender. Railway may, however, recognize such power of attorney and changes after obtaining proper legal advice, the cost of which will be chargeable to the Contractor	No	No	Allowed (Mandatory)
5	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The Tenderers are required to scrutinize carefully all clauses appearing in the Tender documents before uploading their bid	No	No	Not Allowed
2	The Railway reserves the right to verify all statements, information and documents submitted by the bidder in his tender offer, and the bidder shall, when so required by the Railway, make available all such information, evidence and documents as may be necessary for such verification. Any such verification or lack of such verification, by the Railway shall not relieve the bidder of its obligations or liabilities hereunder nor will it affect any rights of the Railway there under	No	No	Not Allowed
3	In case of any information submitted by tenderer is found to be false forged or incorrect after the award of contract, the contract shall be terminated. Performance Guarantee and Security Deposit available with the railway shall be forfeited. In addition, other dues of the contractor, if any, under this contract shall be forfeited and agency shall be banned for doing business for a period of up to two years	No	No	Not Allowed
4	Railways reserves its right to either cancel the tender or reject any or all the tenders without assigning any reasons thereof	No	No	Not Allowed
5	General Conditions of the Contract (GCC), April 2022 with latest amendment/ correction slips is applicable and final authority for this contract in case of any conflict or confusion. The contract shall be governed by the provision of Indian Railways Standard General Conditions of Contract-2022 (Latest) with correction slips up to the date of uploading of tender.	No	No	Not Allowed
6	The firm must entry of details of numbers of engaged labours (skilled or unskilled) , ESIC & PF deduction if applicable) , must be updated on IR- Shramik Kalyan portal at the time of execution of work. Without uploading of these documents running bill of concerned period will not be processed.	No	No	Not Allowed
7	Firm must submit details of Graduate/diploma engineers or equivalent employed by the firm against this work with relevant certificate within two weeks of issue of LOA/before making of agreement Other wise any bill will not be process and LD will be imposed as described in tender Document.	No	No	Not Allowed
8	No payment will be initiated till all the conditions regarding Payment of Wages act & Minimum Wages act in terms of clause 54 and 55 of Indian Railways General Condition of Contract. It shall be mandatory upon the contractor to ensure correct and prompt uploading of all salient details of engaged contractual labour & real payments made thereof after each wage period on Shramik Kalyan portal.	No	No	Not Allowed
9	Tentative Yard plan of BELA station has been attached as tender document Part-II	No	No	Not Allowed
10	Item wise inspection clause has been given in the schedule . However, modification may be done at the time of issue of LOA.	No	No	Not Allowed
11	Bidders should go through Special condition of EI works which has been elaborated in the tender document (Para No- 50 of special condition of Contract)	No	No	Not Allowed
12	The firm must follow the instructions regarding precaution taken during trenching/digging work which is mentioned in the JPO issued dated 21.05.2024. The JPO has been attached in Tender document.	No	No	Not Allowed
13	It is mandatory to followed provisions under Make in India policy 2017 issued by Govt. of India, as amended from time to time.	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The successful bidder shall submit an undertaking from RDSO approved EI OEM, before the supply of material, to confirm compliance with extant RDSO guidelines and to meet contract specific requirements (In terms of Railway Board's letter no. 2013/Sig/01/pt) Dup dated 17.02.2022).	No	No	Not Allowed
2	The undertaking of OEM shall cover the supply of Electronic Interlocking equipment installation, testing & commissioning of Electronic Interlocking including after sale support during the warranty period & beyond the warranty period.	No	No	Not Allowed
3	The successful bidder shall submit Breakup of cards/modules of Electronic Interlocking system & spare parts of schedule of work (i.e. SSI/EI supply items) along with cost of individual items in consultation with/with authorised signature of OEM before supply of materials for payment/Inspection/Call letter purpose only. Spare cards shall be as per standard spare list of OEM as per extant guidelines.	No	No	Not Allowed
4	No materials supply against any schedule of this contract shall be made till submission of MOU.	No	No	Not Allowed
5	The Contractor shall also employ qualified Graduate Engineer or qualified Diploma Engineer, based on value of contract, as may be prescribed by the Ministry of Railways through separate instructions from time to time. In case the Contractor fails to employ the Engineer, he shall be liable to pay penalty at the rates, as may be prescribed by the Ministry of Railways through separate instructions from time to time for the default period for the provisions	No	No	Not Allowed

**DANAPUR DIVISION-S AND T/EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: DNRSandTSig2026-1

Closing Date/Time: 09/02/2026 15:00

6	Contractor is to abide by the provisions of Payment of Wages act & Minimum Wages act in terms of clause 54 and 55 of Indian Railways General Condition of Contract. It shall be mandatory upon the contractor to ensure correct and prompt uploading of all salient details of engaged contractual labour & payments made thereof after each wage period. While processing payment of any 'On Account bill' or 'Final bill' or release of 'Advances' or 'Performance Guarantee / Security deposit', contractor shall submit a certificate to the Engineer or Engineer's representatives that "I have uploaded the correct details of contract labours engaged in connection with this contract and payments made to them during the wage period in Railway's Shramikkalyan portal at 'www.shramikkalyan.indianrailways.gov.in' till ____Month, ____Year	No	No	Not Allowed
---	---	----	----	-------------

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The list of details of personnel including Diploma/Graduate engineer, service workmen etc with certificate / organization in hand and proposed to be engaged for the tendered work.	No	No	Allowed (Mandatory)
2	List of details of Plant & Machinery available in hand and proposed to be inducted and hired for the tendered work	No	No	Allowed (Optional)
3	Certificates and testimonials regarding contracting experience for the type of job (Similar nature of work) for which tender is invited with list of works carried out in the past.	No	No	Allowed (Mandatory)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed
2	I/We have read the various condition of the tender attached hereto and agreed by the said condition.	No	No	Not Allowed
3	I/ We also hereby agreed and abide by the Indian Railway standard general conditions of contract- April 2022 with all correction slips up to date and to carry out the work according to the special conditions of contract and specification of materials and work/services as laid down by railway in the annexed special condition/ specifications, schedule of rates with all correction slips up to date for the present contract	No	No	Not Allowed
4	I/We also agreed to keep this tender open for acceptance for a period of 90 days from the date fixed for opening of the same and in default, I/We will be liable to forfeiture of My Bid Security.	No	No	Not Allowed
5	I will deploy diploma or graduate engineer after issue of LOA as per railway circular otherwise penalty imposed for non deployment of diploma or graduate per month for the period of non deployment will be acceptable.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	DOCSig-2026-1EIBELA.pdf	Tender Document
2	ECRJPOregardingprocedureforundertakingearthworkdiggingworktrenchingworkinthevivityofsignallingtelecomandelectricalcables.pdf	IPO for earth work
3	GCC2022correctionslips.pdf	Correction Slips of GCC 2022
4	SIPBELA.pdf	Tentative SIP of BELA Stn
5	GCC_April-2022_2022__GCC-2022_POLICY_27.04.22.pdf	GCC 2022

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: RAJNISH KUMAR SINGH

Designation : Sr.DSTEDNR