

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

Sr.DSTE acting for and on behalf of The President of India invites E-Tenders against Tender No **KOTA-SNT-SIG-2025-39** Closing Date/Time 09/02/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Provision of Trap/derailing switch to enable stabling on long haul loop line at Thuria, Laban, Chhoti Udai & Piloda stations.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	09/02/2026 15:00	Date Time Of Uploading Tender	10/01/2026 17:46
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	7198771.13	Tendering Section	SIGNAL
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	144000.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	26/01/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () sch-schedule							7198771.13	
1	Please see Item Breakup for details.				4567682.45	AT Par	4567682.45	
	Description:- SCHEDULE-A							
2	Please see Item Breakup for details.				2631088.68	AT Par	2631088.68	
	Description:- SCHEDULE-B							

3. ITEM BREAKUP

Schedule	Schedule sch-schedule					
Item- 1	SHEDULE-A					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	"Supply of Relay AC Immune, Plug-in type, DC Neutral Line 60V 4F/4B, 5F/3B, 6F/2B, front and back contacts metal to metal, conforming to IRS: S-46, S-23, S-34 as applicable and firm's specification. The relay housing shall contain two miniature identical relays in a mini group housing complete with base plate. Note: Base plate inspected by consignee with OEM /Manufacturer testing & guarantee certificate.	Numbers	22.00	10277.51	226105.22

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

2	2	Supply of Plug-in type, two DC neutral line, mechanically interlocked, in mini group housing, complete with base plate each 60V 5F/3B, 4F/4B front and back contacts metal to metal conforming to IRS: S-46, S-23, S-34 as applicable and firm's specification. The relays of various contact configuration shall be given by site incharge as per requirement. Note: Base plate inspected by consignee with OEM /Manufacturer testing & guarantee certificate.	Numbers	22.00	11173.67	245820.74
3	3	Supply of Point Group, RRI, (Ref. IRS: S-46) Siemens Make (No. RSSK 3515/19) or equivalent without base plate along with guide rail conforming to specifications IRS: S-23, S@45"44@ S-46 as applicable & firm's specifications.	Numbers	4.00	115315.11	461260.44
4	4	Supply of Point Chain Group (Ref. IRS: S-46) Siemens make (No. RSSK 3515/3) or equivalent without base plate conforming to specifications IRS: S-23, S@45"44@ S-46 as applicable & firm's specifications.	Numbers	4.00	49926.74	199706.96
5	5	Supply of Signal Group 2- Aspect Siemens Make, type A- RT- RGA066 suitable for LED signal or equivalent without base plate along with guide rail conforming to specifications IRS: S- 23, S- 34, S- 46 as applicable & specifications of firm.	Numbers	4.00	48586.90	194347.60
6	6	Supply of Shunt Signal Group Siemens Make, type A- RT- RG- A065 suitable for LED signal or equivalent without base plate along with guide rail conforming to specifications IRS: S-23, S- 34, S- 46 as applicable & specifications of firm.	Numbers	4.00	70077.69	280310.76
7	7	"Supply of Relay Plug-in type, Style AC- LED All aspects, AC lamp proving relay unit with in- built current transformer type, slow release neutral line relay, 4F/4B contacts, front and back contacts metal to carbon, shall be suitable for working in series with the 110V AC, LED signal lamp rated at 15W confirming to RDSO spec. STS/E/Reelys/AC lit LED signal/ 09- 2002, BRS:941A, IRS: S- 34 & IRS: S- 23 (as applicable). The interlocking code for this unit shall be ABDHK. Note: Base plate shall be inspected by consignee with OEM /Manufacturer testing & guarantee certificate."	Numbers	10.00	8601.77	86017.70
8	8	Supply of Relay, AC Immune, Plug-in type, Style QNA1, DC Neutral line, 24V 8F/8B or 12F/4B contacts, front and back contacts metal to carbon with plug board, retaining clips & connectors conforming to BRS:931A, IRS: S@45<44@ S@45"44@ S-23, Interlocking pincode ABDGH. The relays of various contact configuration shall be given by site incharge as per requirement.	Numbers	16.00	5592.59	89481.44
9	9	Supply of Key Lock Relay AC immunised with different ward combinations (Five extra sets of ward plates to be supplied with each relay). Siemens make working on 60V DC 4F/4B or equivalent (Extra No. of wards to be supplied with the consultation of Engineer in charge of work, as per requirement of site and no additional cost will be paid for extra wards). The ward combination shall be A, B, C, D, E, F , G-----Z.	Numbers	4.00	10148.88	40595.52
10	10	Supply of Base Plate for Point Chain Group or its functional equivalent.	Numbers	4.00	12908.20	51632.80

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

11	11	Supply of powder coated Relay Rack Assembly Complete with scaffolding, fixtures and accessories including MS Bars for fixing of relay plug board, string rods, fuse strips with bracket, 11-Way Bus Bars with cover and mounting brackets, runway for cable/wires, frame base assembly with IDF pillar etc. Siemens type & as per extant practice on W.C. Rly. Typical part list as per Annexure 'J' attached and Rack arrangement as per WCR DRG. No. S&T EQPT. BLDG/2013/Pt. 1/4 and Rack plan as approved by Engineer incharge.	Set	4.00	28590.83	114363.32
12	12	Supply of Tag Blocks 200 way with cover as per specification IRS: S-77/2006 (Rev.1 or with latest amendments). as per drg no SA-24751.	Numbers	3.00	2237.25	6711.75
13	13	(i) Supply of 4 conductor disconnect terminal blocks for test and measurement suitable for at least 2.5 mm ² conductor as per RDSO specification No. RDSO/SPN/189/2004 with latest amdt.	Numbers	604.00	66.79	40341.16
14	14	(ii) Supply of End plate as per RDSO specification No. RDSO/SPN/189/2004 with latest amdt.	Numbers	50.00	12.87	643.50
15	15	(iii) Supply of Din rail of dimension 35mm X 7.5 mm, 1 mm thickness unslopped as per RDSO specification No. RDSO/SPN/189/2004 with latest amdt.	Numbers	6.00	115.99	695.94
16	16	(iv) Supply of End Stop for Din 35 Rail 10 mm wide as per RDSO specification No. RDSO/SPN/189/2004 with latest amdt.	Numbers	109.00	11.37	1239.33
17	17	Supply of PVC indoor cable 1x60x0.6 mm dia colour coding of insulation of inner core shall be in six colour viz. Blue, Red, Green, Grey, Brown & Black conforming to IRS 76/89 or latest.	Kilometre	1.20	190483.65	228580.38
18	18	Supply of PVC indoor cable 1x40x0.6 mm dia colour coding of insulation of inner core shall be in four colour viz. Yellow, Shite, Pink & Violet conforming to IRS 76/89 or latest.	Kilometre	1.10	132805.35	146085.89
19	19	Supply of PVC indoor cable 1x24x1 mm dia colour coding of insulation of inner core shall be in six colour viz. Blue, Red, Green, Grey, Brown & Black conforming to IRS 76/89 or latest.	Kilometre	1.00	191909.14	191909.14
20	20	Supply of flexible multistrand copper wire size 16/0.2 to IS 694 of various colours suitable for wiring of 'Q' series realys. The contractor shall obtain approval for colour wise quanti from executive incharge before placing order for this item.	Kilometre	1.00	8791.40	8791.40
21	21	Supply of Domino units with cover plates as per approved panel diagram, each of size 54 x 34mm completely wired up similar to Siemens make. Each domino unit should have all the 15 contact terminals wired up.	Numbers	76.00	1312.16	99724.16
22	22	Supply of High power main signal with LED aspect integrated type, current Regulator and Health Monitor Alarm Unit as per RDSO Specn. No RDSO/SPN/199/2025 Rev. 1.2 with Amendment 1 or latest-Red	Numbers	4.00	8243.51	32974.04
23	23	Supply of High power main signal with LED aspect integrated type, current Regulator and Health Monitor Alarm Unit as per RDSO Specn. No RDSO/SPN/199/2025 Rev. 1.2 with Amendment 1 or latest-Yellow	Numbers	4.00	8243.51	32974.04
24	24	Supply of calling ON Unit LED integrated type as per RDSO Specn. No RDSO/SPN/153/2023 Rev. 5.0 or latest	Numbers	18.00	5070.97	91277.46

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

25	25	Supply of Main Signal Post 140 mm outer dia 4.6 Mtr Length as per specification No. IRS: S-6 with latest amendment.	Numbers	4.00	8951.24	35804.96
26	26	Supply of Cast iron main signal surface base 140mm as per specification No. IRS: S-10 and Drg No. S-2011/M with latest amendment, with CLS Ladder assembly complete and ladder base for CLS signal 3.6 mtrs/ 4.6 Mtrs./ 5.6 Mtrs. long as per RDSO Drg. No. SA-23150/23153/23156 (Adv.) with latest amendment. This also include, signal front & Back staging complete assembly for CLS unit as per Drg. No. RST/11413.	Numbers	4.00	13922.47	55689.88
27	27	Supply of Non Metallic (FRP) colour light signal housing multi unit type for railway signaling suitable for RE area TWO Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23003A/M Adv. Alt-S and as per SPEC. No. RDSO/SPN/194/2006 (Rev 2.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest.	Numbers	4.00	23636.24	94544.96
28	28	Supply of Off-Set bracket 5-1/2 " for Signals & Routes as per Specification No. IRS: S-10/78 and Drg no. SA-23080(Adv) Alt-1 or with latest amendment.	Numbers	10.00	1317.07	13170.70
29	29	Supply of Shunt Signal Post complete with Base. GI Pipe, 'B' class of 80mm Dia. of min. 1 meter length to be supplied by the contractor.	Numbers	6.00	3564.20	21385.20
30	30	Supply of position light LED based shunt signal unit (as per RDSO Drg. No. SA-23840).	Numbers	6.00	12613.89	75683.34
31	31	Supply of Retro reflective Signal No. plates as per IRSEM Drg No. 19-D10 with clamps, nut, bolts and other accessories required for Fixing.	Numbers	10.00	646.65	6466.50
32	32	Supply of Pad Locks 50 mm with common key make Godrej / Navtal only.	Numbers	20.00	353.02	7060.40
33	33	Supply of Electric Point Machine IRS make 110V DC operation (AC immunity 160V) NONTRAILABLE, complete with lock, detector, cable termination box and slides for lock and detector (Rotary locking) as per specification no. IRS: S-24/2002 amendment-1 or latest, requirement of point machine is 143 mm throw only as per RDSO Drg. No RDSO/S-10800.	Numbers	5.00	72527.41	362637.05
34	34	Supply of Ground Connection complete set suitable for IRS type Point machine for ordinary turnout of 60 Kg rails as per RDSO Drg. RDSO-S-3361.	Numbers	5.00	11205.57	56027.85
35	35	Supply of G. I. Bend pipe, 'B' Class/ Medium Grade, 50 mm Dia & 1.2 M straight length and having fixing plate welded with bent pipe as per Drg. No. Dy.CSTE(Con)/Kota/5 for point machine cable entry.	Numbers	5.00	393.83	1969.15
36	36	Supply of Pre-wired Crank Handle cum Key Lock Relay box (of metal) along with accessories viz. LEDs, with approved type push buttons, terminal strips, string rod, etc. as per Drg. No. Dy.CSTE/C/Kota/6 (A) & (B).	Numbers	5.00	12049.60	60248.00
37	37	"Supply of William stretcher nylon insulation Set suitable for ground connection for motor point operation. Each set comprising of - (RDSO Drg. No.) T-10367-1 no.,T-10368- 2 nos., T-10371- 4 nos. and conforming to the Specification IRS: S-23 & 40/84 with latest Amendment."	Set	15.00	650.91	9763.65

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

38	38	Supply of Gauge Tie plate nylon insulation as per RDSO Drg. No. (T-10372- 1 no., T-10368- 3 nos., T-10371- 6 nos. in each set) and to the Specification IRS: S-23 & 40 with latest Amendment as applicable.	Set	15.00	297.82	4467.30
39	39	Supply of Thermo shrink Jointing Kit for jointing underground 0.9 mm dia. cond. 4/6 quad cables as per specn No. IRS: TC-77/2012 (Rev.3.0) with Amend. 1, 2 & 3 or latest.	Numbers	22.00	3402.91	74864.02
40	40	Supply of Apparatus Case with miniature 'E' type locks with keys (1 key per 5 location boxes) of ward no. 41 (as per Specification No. IRS: S-30/64 & RDSO Drg. No. SA- 3376/M with latest Amendments) on both the doors, duly painted with red oxide.-Single Case as per Drg. No. SK- 783-1/2 & 2/2 with latest alteration.	Numbers	10.00	20558.68	205586.80
41	41	Supply of Apparatus Case with miniature 'E' type locks with keys (1 key per 5 location boxes) of ward no. 41 (as per Specification No. IRS: S-30/64 & RDSO Drg. No. SA- 3376/M with latest Amendments) on both the doors, duly painted with red oxide.-Half Case as per Drg. No. SK- 783-1/2 & 2/2 with latest alteration.	Numbers	10.00	16415.71	164157.10
42	42	Supply of Double Walled Corrugated (DWC) pipe made up of High Density Poly Ethylene (HDPE) of size 103/103.5 mm inner dia and 120 mm outer dia in 6 Mtr straight length as per British Standard No. BSEN 50086-1 and BSEN 50086-2-4 and BIS draft Specification Doc No. ETD 14(5071) and ETD 14(5072) along with one coupler per every 6 meters.	Metre	90.00	543.30	48897.00
43	43	"Supply of GI pipe, inner dia. 100 mm dia., Medium class as per spec. No. IS 1239 PT.1/2004 with socket and fittings.	Metre	90.00	1013.53	91217.70
44	44	Supply of Earth Electrode assembly as per Drg. No. S&T/CON/KOTA/EARTHING/01 ALT - 01. All nut, Bolts & Lugs to be of stainless steel. The earth electrode pipe shall be 'B' Class/ Medium Grade as per Specification No. IS: 1239 Pt. 1/ 2004 of Nominal Inner Dia 50mm, Outside dia (Max 60.8 mm, Min 59.7 mm), Thickness (3.6mm), Tolerance in Thickness ('+' not limited, '-' 12.5 percent).	Numbers	20.00	1313.36	26267.20
45	45	Supply of Track feed Battery chargers, 110V AC as per specification No. IRS: S-89/2013 ver. 1.0 or latest. Chargers shall be of 10 Amp output capacity suitable for charging 80 AH battery and 2/ 3/ 4 no. of cells with potential free contact.	Numbers	10.00	3184.75	31847.50
46	46	Supply of adjustable Track Feed Resistance disc type 30 Ohm as per RDSO Drg. No. SA-20161-66/M (Adv) with latest Amendment with phenolic moulded base.	Numbers	10.00	1783.39	17833.90
47	47	Supply of 'B' type 120 ohms impedance choke to specn. No. IRS.S.65/83 (Amndt-3) or latest.	Numbers	10.00	5074.05	50740.50
48	48	"Supply of Low Maintenance Lead Acid Secondary Cell 2V, 80 AH as per Specification IRS: S-88/2004 with latest amendments. Cells should be supplied with microporous vent plug cum sealed floats, lead coated inter cell connectors, lead coated brass nut bolts & washers in dry and uncharged condition."	Numbers	30.00	2757.90	82737.00

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

49	49	Supply of Relay, AC immune, Plug-in type, style QTA2 relay, DC Neutral track, Relay 9 Ohms, 2F/1B contacts, metal to carbon, complete with plug board, retaining clip and connectors conforming to BRS: 939A, BRS: 966 (Appendix F2) IRS: S-34 & IRS: S-23 as applicable.	Numbers	10.00	6800.31	68003.10
50	50	Supply of Track Lead Junction Box as per Drg. No. JBP/S&T/C/106/I & II made from fiber glass, along with terminal blocks & links. The TLJB should be BLACK in colour.	Numbers	20.00	1451.05	29021.00
					Total	4567682.45
Item- 2	SCHEDULE-B					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Alteration in Existing Panel Interlocking system. This also includes design of circuit alterations and various plans / drawings to suit layout of station sigg. drgs., wiring diagram, contact analysis, fuse board and component details, selection table, locking table, panel tag block analysis, relay rack arrangement, movement locking tables, signalling interlocking plans, route section plan & control panel diagram in AUTO CAD and supplied with Pendrive. The item includes all relevant drawings. The item includes supply of 2 sets of each drg. for approval. Contractor will supply 6 sets of prints on white paper in plastic folder & one print on tracing after final testing and commissioning and 2 sets of Pendrives.	Lot	4.00	61023.15	244092.60
2	2	Installation of Relay Rack Assembly including IDF pillar if any complete with wall supports, scaffolding insulated ladders, runway for cables, Relay/Relay group base plates, fixing of Tag block, Cable Runway PVC channel/trough etc. The work shall be done as per approved plan, extant practice on W.C. Railway & the instructions of Railway Engineer at site with contractor's own materials as per typical rack arrangement WCR DRG. No. S&T EQPT. BLDG/2013/Pt. 1/4.	Set	4.00	1733.51	6934.04
3	3	Termination of cable cores on ARA terminal/ 8-way/ Wago terminals in the cable termination rack. This includes all associated works of pulling out the cable from underground, peeling off insulation, dressing of cable core with lacing thread supported on string rod with contractor's own material. This includes soldering & earthing of armour of cables on CT rack. The work shall be done as per instructions of Railway Engineer at site. The item unit will be Per Rack	Per Unit	4.00	10209.87	40839.48

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

4	4	"Wiring in Relay Room/Auto Hut/ IBS hut/ LC Gate Hut/Adjacent station:- Fixing of Q- series relay base plate/ Metal to Metal relay mini group and major group base plates, laying, lacing, dressing & packeting of 60/40 core PVC indoor cable/ flexible wire and termination of 60/40 core cable/ flexible wire on tag block/ base plate & soldering. Wiring of circuits to be done as per the approved diagram based on relay interlocking system using metal to metal/ metal to carbon type relays and soldering after testing. Contractor will arrange seal tablet & seal wire suitable for k-50 relay for entire relay room. This also includes fuse wiring, function wiring (interconnection between Relay Rack & CT Rack) and paralleling of spare contacts of metal to carbon relays, material required like jumper wire of 0.6mm, 1.0mm and 16/0.02 multi strand flexible etc. Resin core, solder wire, lacing thread, adhesive tapes, lugs resistance, condensers, diodes, of Nippon/ Philips/ Samsung make etc. of various ratings and capacity as per site requirement will be supplied by the contractor free of cost and will be used after approval of Railway Engineer at site.NOTE:- The jumper wire required for carrying out the indoor wiring shall be supplied after RDSO inspection. The quantity required for jumpering shall be assessed jointly with the Engineer in-charge in the beginning itself. The colour wise distribution shall be in proportion of total quantity as under:-Blue- 67%, Grey- 21%, Red- 4%, Black-4%, Yellow- 2%, green- 2%.All type of resistances, capacitors etc. required for commissioning will be supplied & fixed by the contractor. Typical requirement of the jumper wire is approximately 300 meter. The item unit will be per tag block	Per Unit	4.00	939.40	3757.60
5	5	"Wiring in Relay Room/ Auto Hut/ IBS hut/ LC Gate Hut:- Plugging of Q-series relay, Metal to Metal relay/ relay groups. Energisation of the system, making the panel through, functional test as per control table with contractor's own mock panel, break test & wire count test if applicable to be done in presence of Railway Engineers. This will include wiring alterations required if any at that stage, preparation and submission of wire count detail register etc. The work shall be done as per extant practice on W.C. Railway & the instruction of Railway Engineer at site. All type of resistances, capacitors etc. required for commissioning have to be provided by the contractor free of cost & commissioning of system after testing."the item unit will be Per Rack	Per Unit	4.00	2972.97	11891.88
6	6	Excavation, casting (1:3:6) and plastering (1:4, with fine sand) of main signal foundation as per Drg. No. Dy.CSTE/C/Kota/1 ALT 'A' with contractor's own material including ballast, cement, local available sand, PVC pipe & galvanised anchor bolts with nuts & washers, etc. The hole for cable entry should be kept as per site requirement and instruction of Railway Engineer at site. The required Ferma of the size mentioned in the drawing for casting of foundation will have to be brought by the contractor at his own cost. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	4.00	11430.80	45723.20

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

7	7	Erection of Main Signal (CLS) Post with Surface base and signal unit complete on top or on Off-set Bracket, fixing of front and back staging, ladder, guard, signal name plates/board, protective screen, blanking of ladder (0.6mm MS sheet), if any with contractor's own brackets, nuts & bolts & other fixing materials. This also includes erection of auxiliary signals like Calling-ON, Shunt Signal. Wooden white cross-arms (1000mm x 100 mm) to be provided by the contractor till the signals are commissioned with contractor's own material. If the ladder/front/back staging is infringing the SOD, then suitable arrangement of fixing steps for climbing up to signal unit and reducing the size of front/back staging as per instructions of site engineer shall be done. The work shall be done as per instructions of Railway Engineer at site. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	4.00	3946.08	15784.32
8	8	Termination of tail cable on Main & Auxiliary Signal units and wiring with contractor own material, fixing of LED signal units etc. Flexible Single core copper wire 2.5 sq.mm (50/0.25) conforming to IS-694:1990 (as per aspect colour) and lugs etc. will be supplied by the contractor. This includes insertion of tail cables from ground to signal unit, thereafter sealing the opening and testing the signal as per instructions of Railway Engineer at site.	Numbers	4.00	1367.97	5471.88
9	9	Excavation, casting (1:3:6) and plastering (1:4, fine sand) of shunt signal foundation as per Drg. No. Dy.CSTE/C/Kota/1 ALT 'A' with contractor's own material including ballast, cement, local available sand, PVC pipe & galvanised anchor bolts with nuts & washers, etc. The hole for cable entry should be kept as per site requirement and instruction of Rly engineer at site. The required Ferma of the size mentioned in the drawing, for casting of foundation will have to be brought by the contractor at his own cost. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	6.00	3392.40	20354.40
10	10	Erection of Shunt Signal Post with surface base, unit, number plate complete. Wooden white cross-arms (1000mm x 100 mm) to be provided by the contractor till the signals are commissioned with contractor's own material. The work shall be done as per instructions of Railway Engineer at site. All nuts, bolts and washers etc. should be galvanised iron.	Numbers	6.00	546.51	3279.06
11	11	Termination of tail cable on Shunt Signal units and wiring with Contractor's own material, fixing of LED Signal unit etc. Flexible Single core copper wire 2.5 sq.mm (50/0.25) conforming to IS: 694:1990 copper wire as per Railway standard and lugs etc. will be supplied by the contractor. This includes insertion of tail cables from ground to signal unit, thereafter sealing the opening and testing the signal as per instructions of Rly engineer at site.	Numbers	6.00	446.80	2680.80

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

12	12	Excavation and Casting of Apparatus Case Foundation with mixture of Cement:Sand:Stone aggregate/Chip in 1:3:6 ratio and plastering with mixture of Cement:Sand in 1:4 ratio, with contractors own Metal Sheet ferma of the size mentioned in the drawing, cement, anchor bolts, with nuts & washers and other materials. The items also include additional earth work if required as per instruction of Rly. Engineer at site. All nuts, bolts and washers etc. should be galvanised iron. -Single Case as per Drg. No. Dy.CSTE/C/Kota/2	Numbers	10.00	11824.68	118246.80
13	13	Excavation and Casting of Apparatus Case Foundation with mixture of Cement:Sand:Stone aggregate/Chip in 1:3:6 ratio and plastering with mixture of Cement:Sand in 1:4 ratio, with contractors own Metal Sheet ferma of the size mentioned in the drawing, cement, anchor bolts, with nuts & washers and other materials. The items also include additional earth work if required as per instruction of Rly. Engineer at site. All nuts, bolts and washers etc. should be galvanised iron. -Half Case as per Drg. No. Dy.CSTE/C/Kota/3	Numbers	10.00	11396.98	113969.80
14	14	Erection of Apparatus cases. This includes filling of Location Foundations with the sieved sand being used for making the foundation of location boxes and plastering on top of the sand. All nuts, bolts and washers etc. should be galvanised iron. -Single Case	Numbers	10.00	1240.69	12406.90
15	15	Erection of Apparatus cases. This includes filling of Location Foundations with the sieved sand being used for making the foundation of location boxes and plastering on top of the sand. All nuts, bolts and washers etc. should be galvanised iron. -Half Case	Numbers	10.00	948.76	9487.60
16	16	Supply, fabrication and fixing of Phenolic Laminated Sheet Board in Location Box by providing all fixtures, double ended insulators (06 Nos.), PVC coated string rods at the back side for cable support with contractor's own material. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be of 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of the Phenolic Laminated Sheet for Full Case terminal board should be 800mm x 950mm and for half case it should be 800mm x 450mm. In case board size is in variation with the size mentioned as per location details, then proportionate payment on area basis shall be made. This also include, the work to be done in existing Location Boxes (if required) as per instructions of Railway Site Engineer. -Single Case	Numbers	10.00	4877.16	48771.60

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

17	17	Supply, fabrication and fixing of Phenolic Laminated Sheet Board in Location Box by providing all fixtures, double ended insulators (06 Nos.), PVC coated string rods at the back side for cable support with contractor's own material. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be of 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of the Phenolic Laminated Sheet for Full Case terminal board should be 800mm x 950mm and for half case it should be 800mm x 450mm. In case board size is in variation with the size mentioned as per location details, then proportionate payment on area basis shall be made. This also include, the work to be done in existing Location Boxes (if required) as per instructions of Railway Site Engineer. -Half Case	Numbers	10.00	2999.11	29991.10
18	18	Supply, fabrication and fixing of Phenolic Laminated Sheet for Shelf of equipments/batteries with contractor's own fixing material, angle frames, additional in-between supporting angle for the Shelf, etc. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of Shelf for Single Case Apparatus/Location Box shall be 500mm x 950mm and for Half Case Location Box it shall be 500mm x 450mm. In case board size is in variation with the size mentioned as per Location details, then proportionate payment on area basis shall be made. Galvanised nut & bolts to be used for fixing of Phenolic Laminated Sheets.-Single Case	Numbers	10.00	3105.23	31052.30
19	19	Supply, fabrication and fixing of Phenolic Laminated Sheet for Shelf of equipments/batteries with contractor's own fixing material, angle frames, additional in-between supporting angle for the Shelf, etc. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of Shelf for Single Case Apparatus/Location Box shall be 500mm x 950mm and for Half Case Location Box it shall be 500mm x 450mm. In case board size is in variation with the size mentioned as per Location details, then proportionate payment on area basis shall be made. Galvanised nut & bolts to be used for fixing of Phenolic Laminated Sheets.-Half Case	Numbers	10.00	1934.94	19349.40

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

20	20	Supply, fabrication and fixing of Phenolic Laminated Sheet for Shelf of equipments/batteries with contractor's own fixing material, angle frames, additional in-between supporting angle for the Shelf, etc. The work shall be done as per Drg. No. SK 783-1/2 with latest alterations & as per instructions of Railway Engineer at site. The Phenolic Laminated Sheets should be 10mm thick, grade P3 as per specification No. IS: 2036 of 1995 or latest. The size of Shelf for Single Case Apparatus/Location Box shall be 500mm x 950mm and for Half Case Location Box it shall be 500mm x 450mm. In case board size is in variation with the size mentioned as per Location details, then proportionate payment on area basis shall be made. Galvanised nut & bolts to be used for fixing of Phenolic Laminated Sheets.-Half Case	Numbers	10.00	2083.19	20831.90
21	21	"Installation of Equipments (Relays, Resistance, chargers, Choke, batteries, LV box, KLCR, PPTC fuses & track feed charger alarm unit, etc. as applicable) with contractor's own wiring material, MS frame, copper lugs etc. & wiring of the same in Apparatus Cases as per Location Diagrams, paralleling of spare contacts of Metal to Carbon Relays and wiring of potential free contact of track feed charger and testing of track circuits as per instruction of Railway's Site Incharge and standard practice. This also includes supply of Multi-strand Flexible Single Core Copper Wire 2.5 sq.mm (50/0.25) except for relay wiring which will be done with 16/0.2 mm flexible multi-strand wire conforming to IS: 694:1990 with suitable lugs. All wires to be duly manufactured by RDSO approved firms (16/0.2 mm flexible multi-strand wire inspected by RDSO). Note: PPTC fuses shall be provided as per fixing arrangement of PPTC as advised by HQ's policy guideline issued vide letter no. WCR/N-HQ/110/Signal Policy/Sig-32 Pt-VII, dtd. 07.11.2013 i.e. PPTC fuse are to be connected with crimped ring type lugs and crimped area is also to be filled with solder. PPTC lead to be provided with ferrules for volt & current rating of PPTC.-Half Case"	Numbers	10.00	1449.44	14494.40
22	22	Fixing of ARA/cage type disconnect terminals and fuse blocks with provision of holes on Phenolic Laminated Sheets and fixing with galvanised nuts & bolts in Location Boxes and elsewhere. This includes provision of additional holes on the Phenolic Laminated Board on either side for cable conductor entry. The work shall be done as per the instructions of Railway Engineer at site.	Numbers	600.00	30.07	18042.00

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

23	23	Termination of cable cores on ARA Terminals/cage type disconnect terminals, fuse blocks, 8-way terminals blocks, telecom terminals in new/existing apparatus cases, existing MCTB/existing telecom cable termination racks. This includes all associated works of pulling out the cable from underground, dressing of cable, making wiring tree with contractor lacing & threading material etc. Both ends of a cable core shall be counted as per conductor. This includes soldering of armour tree/ring of cables and connecting to copper plate through GI wire bus bar in location boxes. The work shall be done as per instructions of Railway Engineer at site.	Per Conductor	600.00	22.56	13536.00
24	24	Supply & Fixing of lamp holders (two pin) with switches (ISI mark) of reputed make for location boxes. This also includes supply of LED bulb of reputed make.	Numbers	20.00	119.77	2395.40
25	25	Installation of earth electrode assembly as per Drg. No. S&T/CON/Kota/Earthing/01 ALT-1 and connecting through stainless steel wire 8 SWG supported on MS flat of size 5mm x 40mm to earth electrode as per Drg. No. T/2014/1 for signals and T 2014/5 for Location Boxes/Apparatus Cases. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Railway Supervisors. It should be documented and painted on earth enclosure made of concrete. Only earth electrode will be supplied by Railway. All other material required for provision of earthing will be brought by the contractor. This earth can be provided for DPs, block instruments & ELD etc. also, so as to achieve the desired earth resistance value. Earth enclosure to be manufactured & supplied by contractors own material of ratio 1:3:6, without cover. Additional connection of Earth pipe including parallel connection with other earth pipes with the function shall be done using left over pieces of signalling cable. Laying of cable pieces shall be covered in laying of cable item and cable shall be supplied by Railways.	Numbers	20.00	2426.89	48537.80

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

26	26	"Fixing/ Refixing of electrical point machine on existing layout, ground connection during phase working (NI/ Pre-NI) after removing the electrical point detector, FPL assembly and mechanical or any other fittings including existing Point Machine fitting if any, adjustment if necessary, wiring of point machine testing and commissioning of electrically operated point, fixing and connecting point indicator on derail switch if necessary. This will include fabrication and fixing of GI bend pipes as per Drg. No. Dy.CSTE(Con)/Kota/5 of S-shape of 1.2 meter length & 50mm dia with welded frame for cable entry to the point machine and termination of tail cable in point machine and wiring servicing of point machine & supply and filling of SAE-30 lubrication oil . This also includes installation of William stretcher nylon insulation set (complete), Tongue attachment nylon insulation set and Gauge Tie plate nylon insulation set as per RDSO specification. The work shall be done as per extant practice on W.C. Railway and the instructions of Railway Engineer at site. Internal wiring of Point machine & cable termination suitable for EI/PI/RR1 installation, 2.5 sq.mm (50/0.25) conforming to IS: 694:1990 flexible copper wire of different colours & lug will be supplied by contractor. Point Machine, ground connection, insulation sets will be supplied by Railways. This includes drilling of holes in tongue rail, provision of high di-electric varnish on contact assembly and wiring during NI period. This also include rewiring of point machine if required as per type of point machine & circuit (independent detection) & as per instruction of site engineer. To reduce the no. of days of NI, the existing point machines may be replaced with new point machines and operated from existing panel. During pre-NI / NI, rewiring at MCTB/location box/point machine shall be carried out as per the requirement without any additional cost. the item unit will be Per point	Per Unit	5.00	8952.48	44762.40
27	27	Fixing of KLCR in KLCR boxes as per Drg No. Dy.CSTE/C/Kota/6 (A) & (B). Item includes supply of bracket, nuts, bolts & holes drilling MS angles, MS plates & Phenolic laminated sheet of 10 mm etc. (KLCR relays will be supplied by Rlailway).	Numbers	4.00	1520.94	6083.76

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

28	28	Erection, Fitting and Rail connection of Track Lead Junction Box (TLJB) on two vertical support (M.S. angle) with contractor's own fixing material including 7mm single groove galvanized channel pins for track lead connections as per Drg. No. JBP/S&T/C/106/II. This include drilling of holes (04 Nos., 8.2 mm dia) in rails for track connections as per instructions of Railway Engineer at site.Note: Jacketted galvanized steel wire rope of 6mm dia., PVC sheathed of 2mm thickness for connection between the TLJB and the rails to be used and to be supplied by the contractor. Double wire ropes to be connected between each rail and TLJB (using lugs) i.e. with each TLJB, 04 Nos. of wire ropes to be fixed, at locations having positive & negative connections and at other TLJBs i.e. for jumpering only 02 wire ropes are required to be fixed (jacketted galvanised steel wire rope of 6mm dia, PVC sheathed of 2mm thickness inspected by consignee).	Numbers	20.00	1905.29	38105.80
29	29	Provision of bonding with GI wire 4mm dia (8 SWG) for fish plate joints bonds, crossing bond etc. This will include drilling of 7.2 mm dia. holes in rails (4 Nos.) and provision of two jumpers for each bond, etc. with contractor's own tools as per instruction of Railway Engineer at site. (Channel pin, bonding wire (8 SWG) will be supplied by contractor). Z-bonding will be done using left over cable pieces (two pieces per bond) with 08 holes per bond, these cables will be supplied by the railways (GI wire 4mm dia, 8SWG for bonding inspected by consignee). NOTE: Two jumpers will constitute one unit of this item.	Numbers	25.00	219.08	5477.00
30	30	Charging of 2V lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in group & their connection & wiring. The work shall be done as per extant practice of W.C. Railway & instruction of Engineer in-charge. the item unit will be per 100 VAH	Per Unit	48.00	100.73	4835.04
31	31	Excavation of trench 1.2 mtr deep, 300mm wide at the bottom along main line in normal soil, including clearing of bushes, trees etc and refilling of the trench by excavated soil and ramming after laying of the required quantity of cables as per instructions of Engineer at site. The work also includes excavation of trenches in the beds of culverts. Whenever the dimensions of cable Trenches as mentioned in the Tender Schedule are not easily achievable due to terrain conditions, then payments will be made on a pro-rata basis, for the dimensions achieved.The specific approval of the Engineer in charge of the work (not below the rank of Sr. Scale officer), will be required for such dispensation.	Kilometre	3.90	61080.98	238215.82

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

32	32	Excavation of cable trench 300mm wide at the bottom and 1.2 meter deep in hard soil mixed with boulders / hard murum soil including clearing of trees, bushes and refilling of cable trench by excavated soil, murum, boulders etc. Care should be taken while refilling the cable trench such that the murum / boulders etc. does not damage the cable. Ramming after laying of cable (a) 6- quad (b) jelly filled & power cables etc. Whenever the dimensions of cable Trenches as mentioned in the Tender Schedule are not easily achievable due to terrain conditions, then payments will be made on a pro-rata basis, for the dimensions achieved. The specific approval of the Engineer in charge of the work (not below the rank of Sr. Scale officer), will be required for such dispensation.	Kilometre	0.80	90506.12	72404.90
33	33	Excavation of cable trench 1.0m deep from the rail flange and 300mm wide across the track, for track crossing and refilling after laying of GI pipes and restore the track to its original condition. The work shall be done as per extant practice on W.C. Rly & instruction of Rly engineer at site. Cable trench as per Drg. No.TS/Cable laying/12/03/03. For achieving 1.0 m depth for the bottom most cable, the contractor shall dig the trenches to a depth, slightly more than 1.0 m to take care of practical problems.	Metre	50.00	139.48	6974.00
34	34	Cutting of all types of Roads (1 Mtr X300 mm)/ platforms (300mm X 300mm) preparatory to trenching, excavation and refilling after laying of RCC/ GI/ DWC pipe & restoring them to original condition. Generally there shall be no proportionate payment for cable at depth lesser than that specified in the tender schedule. If it is not possible to reach the required depth at any location, then the contractor shall obtain prior approval of Railway Site Engineer, who shall get the dispensation, from JAG vide Rly. Board's letter No. 2013/Sig/SEM Pt.-II/Misc., dated 12.06.2014 before commencement of cable laying process and only then shall the proportionate payment be made to the contractor. This also includes laying of any No. of DWC/RCC/GI pipes, as per requirement. The work shall be done as per extant practice on W.C. Rly & instructions of Railway Engineer at site. The DWC/RCC/GI pipes will be supplied by Railway. Laying of RCC/GI/DWC pipe is covered in separate item.	Metre	80.00	248.64	19891.20
35	35	All work pertaining to Horizontal Directional Drilling (HDD)/Boring and trenchless cabling. It includes supply, transportation and insertion of self lubricated HDPE Pipe and laying of cables in boring under the track/road/platform/circulating area by using different sizes of pipes depending on total number of cables will be crossed. The depth of horizontal boring should be minimum 1 mtr upto 3 mtr, from rail flange/ road level/ground level as per site requirement and as per instructions of Railway Engineer incharge. This item will be used for track crossing of running lines, road crossing & circulating area. By using self lubricated HDPE Pipe of 120mm outer dia and 103.5mm inner dia in the bore and laying of cables in the bore under the track/road/circulating area.	Metre	80.00	1001.39	80111.20

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

36	36	Supply & laying of well burnt bricks of size 200mm x 90mm x 65mm inside the trench (with the brick length being perpendicular to cable route) after laying of cable & covering of cables laid in trenches by loose excavated soil for a layer of 50mm thickness approximately, in station area from Outermost to Outermost signal or at any other location as per instruction of Site Engineer. Note:- Size of bricks to be got approved by Railway Site Engineer. In case brick size is in variance with the size given in the tender schedule then proportionate payment on volumetric basis shall be paid to contractor subject to a maximum limit of schedule rate.	Numbers	47000.00	3.89	182830.00
37	37	Laying of All types of Signal/ Telecom/ Power Cable of various cores/ sizes in excavated trenches. The work shall be done as per extant practice followed on W.C. Railway and as per the instructions of Railway Engineer at site.	Kilometre	72.00	13375.32	963023.04
38	38	Supply, fixing, painting and installation of RCC/Stone cable route markers as per drawing No. DRM/KOTA/MISC-87 or WCR/Sig/ST.RT.MARKER/201401. Placing and securing of cable route markers in trenches at the specified interval and diversions, joints etc along the cable route. The work shall be done as per extant practice on W. C. Rly & the instructions of Rly engineer at site. Sample to be approved by engineer in-charge of the Railways before supply, after the testing prescribed in drawing. This includes supply of Paints of different colours as per drawing. The paint shall be either from Asian or Shalimar / Apcolite / Berger having ISI mark.	Numbers	162.00	229.23	37135.26
39	39	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish.-Apparatus case full size"	Numbers	10.00	554.81	5548.10
40	40	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good smooth & lasting finish.-Apparatus case half size"	Numbers	10.00	563.27	5632.70

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

41	41	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good somooth & lasting finish.-Point machine with ground connection complete. (Point machine with black enamel only outside and ground connection with Red Oxide)"	Numbers	5.00	194.81	974.05
42	42	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good somooth & lasting finish.-Main Signal post with main & auxilliary signal unit, surface base and complete fittings as per W.C. Railway's Standard practice."	Numbers	4.00	940.23	3760.92
43	43	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good somooth & lasting finish.-Shunt Signal post with signal unit, surface base as per W.C. Railway's Standard practice."	Numbers	6.00	224.46	1346.76
44	44	"Painting two coats of Enamel Paint over one coat of Red Oxide primer on the following items after scrapping and cleaning of the surface wherever necessary. Primer and Paints with ISI mark is to be supplied by the Contractor. The work shall be done as per instructions of Railway Engineer at site and extant practice on W.C. Railway. Note: Second coat shall be made after completely drying up of first coat of paint, to give good somooth & lasting finish.-Track lead junction box."	Numbers	20.00	128.75	2575.00
45	45	Lettering, numbering of point machine, track lead junction boxes, block joint, glued joints, , batteries, apparatus cases etc. (outside) (each item to be taken as one unit)	Numbers	51.00	74.77	3813.27
46	46	Lettering & numbering of termination particulars, equipments names etc. legibly and neatly inside Location Boxes as per standard practice of W.C. Railway & instructions of Railway Engineer at Site.-Single case	Numbers	10.00	336.70	3367.00
47	47	Lettering & numbering of termination particulars, equipments names etc. legibly and neatly inside Location Boxes as per standard practice of W.C. Railway & instructions of Railway Engineer at Site.-Half case	Numbers	10.00	229.92	2299.20
					Total	2631088.68

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Financial Eligibility Criteria: The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where: V= Advertised value of the tender in Crores of Rupees. N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover.	No	No	Allowed (Mandatory)
1.1	The Tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: 1Three similar works each costing not less than the amount equal to 30% of advertised value of the tender OR 2Two similar works each costing not less than the amount equal to 40% of advertised value of the tender OR 3One similar work costing not less than the amount equal to 60% of advertised value of the tender	No	No	Allowed (Mandatory)
1.1	UPLOADING OF THE CERTIFICATE:-The tenderers shall submit a copy of certificate stating that all their statements/documents submitted along with bid are true and factual. Standard format of certificate to be submitted by the bidder is enclosed as Annexure-V. In addition to Annexure-V, in case of other than Company/Proprietary firm. Annexure-V(A) shall also be submitted by the each member of a Partnership Firm/ Joint Venture (JV) / Hindu Undivided Family (HUF / Limited Liability Partnership (LLP)etc., as the case may be. Non submission of above certificate(s) by the bidder shall result in summarily rejection of his/their bid. It shall be mandatorily incumbent upon the tenderer to identify, state and submit the supporting documents duly self-attested/digitally signed by which they/he is qualifying the Qualifying Criteria mentioned in the Tender Document.	No	No	Allowed (Mandatory)
1.1.1	DEFINATION OF SIMILIAR NATURE OF WORK:-Any Signaling Work of EI/PI/RR/IBH/ABH/LC Gate Interlocking Track circuit works /Axle counter works etc.	No	No	Allowed (Optional)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	All payment and other conditions are attached with tender document.	No	No	Not Allowed
1.1	Although year of specification is given in the schedule, last amendment, if any, shall apply.	No	No	Not Allowed
1.2	All tenderer must have valid GSTN number and rates must be inclusive of GST Act and its amendment.	No	No	Not Allowed
1.3	Compliance of GST act/rules & correction/modification issue by railway board with regard to GST act shall be binding on contractor & railway.	No	No	Not Allowed

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

1.4	Genral instruction :- 1 The offer will be evaluated based on certificates enclosed with the original offer only. The Railways will not enter into any correspondence to get these certificates subsequently and the offer shall be evaluated based on the documents submitted along with the offer. 2 Tenderer may please note that meeting of eligibility criteria is strictly based on completion certificates issued by the executive in charge of work and not linked with mere list of works claimed to have been executed by the tenderer or a copy of work order from Railways. 3 Tenderer may please note that fulfilling of eligibility clause shall be ascertained only from the completion certificates issued by the executive-in-charge of work and mere list of works claimed to have been executed by the tenderer or a copy of work order from Railways shall not be enough. It may also be noted that cognizance of those works, which are nearing completion or have been almost completed, shall not be taken only those completion certificates, wherein successful commissioning satisfactory performance of work have been clearly unambiguously acknowledged by Executive-in-charge of any Railway Unit or any Govt. Dept./Undertaking for any similar work shall be considered for this purpose. 4 Any variation to quantities in any item and its associated wiring material account of supply and installation will have to be born by the tenderer. Railway Engineer's decision in this regard shall be final. 5 All drawings related with the work can be obtained from the office of DRM Kota on any working day during office hours.	No	No	Not Allowed
-----	---	----	----	-------------

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenders whether being submitted on behalf of Sole Proprietorship Firm /HUF / Partnership Firm / Joint Venture (JV) / Companies Registered Under Companies Act, 2013/LLP (Limited Liability Partnership) / Registered Society or Registered Trust are required to UPLOAD an UNDERTAKING that - They are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of opening of bids, either in individual capacity or as a member of the partnership firm or JV in which the tenderer was / is a partner/member. Concealment / wrong information in regard to above shall make the contract liable for determination under Clause 62 of the General Conditions of Contract.	No	No	Allowed (Mandatory)

**KOTA DIVISION-SIGNALLING AND TELECOMMUNICATION/WEST CENTRAL
TENDER DOCUMENT**

Tender No: KOTA-SNT-SIG-2025-39

Closing Date/Time: 09/02/2026 15:00

1.1	The tenderers shall UPLOAD VALID DOCUMENTS pertaining to prove the constitution of their firm - 1.In case tenderer is Sole proprietorship firm The tenderer shall submit Valid documents or Notarized Affidavit (As per prevailing law) (Annexure E) of Tender document. 2. In case of HUF: A copy of notarized affidavit on Stamp Paper declaring that he who is submitting the tender on behalf of HUF is in the position of 'Karta' of Hindu Undivided Family(HUF) and he has the authority, power and consent given by other members to act on behalf of HUF. 3.In case of Partnership Firm: The tenderer shall submit :(i) A copy of Partnership Deed and (ii) a copy of Power of Attorney)(Annexure D) of Tender document (duly registered /Notarized as perprevailing law) in favour of an individual to sign the tender documents and create liability against the Firm. 4.Joint Venture (JV): The tenderer shall submit documents as mentioned in Clause 17 of the Tender document (Second Sheet). 5.Company registered under Companies Act-2013: The tenderer shall submit (i) the copies of MOA (Memorandum of Association) / AOA (Articles of Association) of the company; and (ii) A copy of Authorization/Power of Attorney issued by the Company (backed by the resolution of Board of Directors) in favour of the individual to sign the tender on behalf of the company and create liability against the company. 6.LLP (Limited Liability Partnership) Firm: If the tender is submitted on behalf of a LLP Firm registered under LLP Act-2008,the tenderer shall submit alongwith the tender- (i) a copy of LLP Agreement,(ii) a copy of Certificate of Incorporation; and (iii) a copy of Power of Attorney/Authorisation issued by the LLP Firm in favour of the individual to sign the tender on behalf of the LLP Firm and create liability against the Firm.7.Registered Society & Registered Trust: The tenderer shall submit (i) a copy of the Certificate of Registration, (ii) Deed of Formation; and (iii) a copy of Power of Attorney in favour of the individual to sign the tender documents and create liability against the Society/Trust. If the above required documents are not uploaded along with the tender, to prove the STATUS of firm that thetender was submitted on behalf of a Sole Proprietorship firm /HUF/ Partnership firm / Joint Venture / Company registered under Companies Act-2013/ LLP(Limited Liability Partnership) Firm: / Registered Society & Registered Trust: etc., then the tender shall be treated as having been submitted by the individual who has signed the tender and the offer will be dealt accordingly.	No	No	Allowed (Mandatory)
-----	--	----	----	------------------------

6. Documents attached with tender

S.No.	Document Name	Document Description
1	TD-SIG-2025-39-u.pdf	TD SIG 2025 39
2	COO-SIP.pdf	COO SIP
3	PDZ-SIP.pdf	PDZ SIP

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: VARSHA . SHARMA

Designation : DSTE SIG N WORKS