

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

Dy.CSTE C BSL acting for and on behalf of The President of India invites E-Tenders against Tender No **SUR-NC-CR-SNT-C-S-01-2026** Closing Date/Time 03/02/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Supply, Installation, Testing & commissioning of Indoor & Outdoor equipment's and Provision of Electronic Interlocking at Sainagar Shirdi Station in connection with provision of 5 stabling line in Pune Division of Central Railway.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Two Packet System
Tender Closing Date Time	03/02/2026 15:00	Date Time Of Uploading Tender	10/01/2026 17:43
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	138915238.08	Tendering Section	TENDER
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	844600.00	Validity of Offer (Days)	90
Tender Doc. Cost (Rs.)	0.00	Period of Completion	8 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	20/01/2026		
Are JV allowed to bid	Yes	Number of JV Member Allowed	3
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Supply, Installation, Testing & commissioning of Indoor & Outdoor equipment's and Provision of Electronic Interlocking at Sainagar Shirdi Station in connection with provision of 5 stabling line in Pune Division of Central Railway.							112723617.02	Above/ Below/Par
1		115.00	Per Route	520441.00	59850715.00	18.00	70623843.70	
Description:- Design, manufacture and supply of Electronic Interlocking (EI) system (Hot Standby) architecture complete as per RDSO specification No.RDSO/SPN/192/2019 Ver. 2.0 / RDSO/SPN/203/2011 ver. 1.0 with latest amendment or latest version or latest specifications. RDSO Technical Advisory Note No.STS/E/TAN/3012 Ver. 4.0 dated 23.07.2025 or latest regarding Technical system Application Approval for Electronic Interlocking (EI) installations, STS/SSI/General dated 07.12.2018 TSAA as per the technical requirements and tentative approved Signaling Plans & Diagrams with OEMs specifications. Electronic Interlocking (EI) system mainly consisting of Central Processing Equipment, Interface Equipments and all types of required Relays, EI racks etc. as per requirements, dual operator Industrial Grade Embedded PC (as per CI 5.3.2 of RDSO specification or latest) with VDU panel (52" LED 2 nos. or bigger) with Redundancy as per the RDSO technical advisory Note No.STS/E/TAN/3007 Version 1 dt. 02.11.12 or latest (Hot standby dual VDU Normally one system will be online and other system will be in standby mode), All types of required relays suitable for EI, interconnecting cables and jumper wires. It also includes provision of Industrial grade maintenance Terminals (as per CI 5.3.2 and 7.2 of RDSO specification or latest) (42" LED or Bigger with UPS minimum 2 hr back up), required power supply DC-DC converters for EI equipments, Housing for EI equipments and enclosures, fuses, screw less disconnecting type terminals, fixture mounting arrangements and accessories necessary make the EI system functional as per approved signaling plan."It does not include supply of Data logger , however Protocol Converter for Data logger to be supplied. The tenderer should furnish complete details of cards/modules/sub-modules connectors, relays etc, for each station. For System ""A & B"" segregation between theDC-DC convereters should be made so that in case of failure only one system is affected. The system design shall incorporate details of approved SIP and its subsequent alteration/modification till its commissioning. It included supply of essential spares of the EI modules at 10% - Essential spares of the EI equipments subject to minimum one of each type mainly consisting of processor, cards/module, interface relays, etc. Item wise detailed break up with unit and quantity to be provided in separate annexure. FOR ----- STATION." A) 20 TO 50 ROUTES. (Inspection by RDSO)								

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

2							
	2	1.00	Set	106064.00	106064.00	18.00	125155.52
	Description:- Supply of tool kit- required for Trouble Shooting and repair of hardware and software for EI system should be supplied for stations as per schedule item 1 above. (This includes tools required for EI maintenance sorts of crimping, insertion, removal, general purpose tools like screw drivers, spanners, PCB extractor, temp. controlled soldering iron, wire cutter, nose plier etc. & measuring instruments with carrying case/ holders/cabinet for technicians/ J.E. or testing, Maintenance and repair at site). Each set comprises of the following (a) Crimping tools for all types of special cable assembly used in EI system. (b) Insertion tool for all types of special cable assembly used in EI system. (c) Removal tools for all types of special cable assembly used in EI (d) Digital multimeter (Tektronics/Fluke/MEGGER/RISHAV or better) system. (e) Steel cabinet / Almira (Godrej/Durian/Transteel) of good quality to store tool, spare cards and documents. (f) Clamp Earth Tester. (Fluke 287/MEGGER/RISHAV or better) (g) Clamp Current Meter. (Fluke 287/MEGGER/RISHAV or better) (h) 6 nos. Electrostatic Discharge Wrist Band for cards modules protection. (Inspection by consignee)						
	3	1.00	Set	134635.00	134635.00	18.00	158869.30
3	Description:- Supply of as made documents (Manuals for Installation, Testing, and maintenance of the system) (One set consists of 6 set of following drawings per station). (i) Manual for installation, Testing, Commissioning and maintenance of the system for Technicians/Jr. Engineers. (Installation and maintenance level) (ii) Functioning and system overview (Higher Management Level) (iii) Completion documents as per special conditions of contract. (iv) Design & supply of circuits and plans to suit layout given in the signaling plan for Hot Standby Architecture Electronic Interlocking (EI) system. All plan and wiring diagram shall be prepared on AutoCAD Drawing and supplied with CD. This will include supply of Control-cum-Indication Panel/VDU diagram, Square sheet, wiring diagrams (Application Logic and Interface circuit), Fuse Analysis, Contact Analysis, Tag Block Analysis, Power supply Distribution / Power Equipment arrangement (with program switch) Diagram, Auto change over diagram (if supplied by the contractor), and all other relevant drawings. NOTE : The contractor shall initially supply 1 set of documents (Paper Prints) for approval of Railways. He shall ensure that each sheet has a block for signature of Railway official as well as a block for signature of firm, duly signed by the authorized signatory of the firm. The name of the work as given by Railways shall be written on every sheet under the work column. All the drawing shall be supplied in a good quality folder for each station. After approval of comments by Railways, the Contractor will make copies of the approved documents and return the approved documents to Railways. The contractor will then make necessary correction to Application Logic Software duly incorporating Railways' alterations/corrections/comments, if any. After complete testing/ commissioning of the station, tracings of completion documents as mentioned above will be submitted to Railways for approval. Along with the completion application logic, difference report (showing addition & deletion in different colors) as compared to earlier approved application logic should also be submitted. After approval of completion application logic by Railways, 5 sets of copies of duly approved completion tracings will be submitted to Railways. (Inspection by consignee)						
	4	1.00	Set	146679.00	146679.00	18.00	173081.22

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

4	Description:- Supply of Portable work station for Data input & configuration with necessary software/AutoCAD latest version programmes/Accessories, simulation and functional Testing, diagnostics and trouble shooting and commissioning of EI system. Suitable Table & Chair or reputed make shall be supplied by the contractor. The specifications of the PC / Laptop should be got approved from the Engineer in charge before supply. Note : Portable work station should strictly adhere to specification as per annexure. (Inspection by consignee)						
5	5	1.00	Per Alteration	2223143.00	2223143.00	18.00	2623308.74
	Description:- Modification in existing EI system as per latest TAN, it includes:- Design and modification in existing interface and interlocking circuit of EI system, including modification in VDU,CCIP, MT, Data logger, EI, Relay rack complete wiring conforming to RDSO specification, as per technical requirement & tentative approved signaling plan/diagrams. Required hardware will be provided by railways except the wiring, material (i.e. connectors, interconnecting cable/wires, fuses etc.) The work includes supply of modified ST/LT, interface and logic circuit, CCIP/VDU diagram etc. to suit the approved interlocking plan. It also includes modification in data logger/MT, carrying out FAT, SAT jointly with railways and satisfactory commissioning of the modified EI with full complements as per approved IP and central railway practices. All plans and wiring diagrams shall be prepared on AUTOCAD and supplied in both soft copy and hard copies (6 sets.)NOTE : If the alteration involves modification of routes up to 10, fixed cost as per the Rate mentioned in (i) above shall be paid. If the alteration involves modification of routes are more than 10 up to 20 routes, then, fixed cost as per the Rate mentioned in (ii) above shall be paid. i) Alteration involving modification in more than 11 and up to 20 routes (Inspection by RDSO)						
6	6	4.00	Set	30325.00	121300.00	18.00	143134.00
	Description:- Supply of Relay rack assembly complete with scaffolding, fixtures and accessories including MS Bars for fixing of relay plug board, string rods, fuse strips with bracket, 11 way Bus bars with cover and mounting brackets, runway for cable/wires, frame, base assembly etc. Siemens type & as per extant practice on C.Rly. Typical part list as per Annexure and Rack arrangement as per sketch no SK-727 and Rack plan as approved by Engineer in charge.(Inspection by consignee)						
7	7	5.00	Set	26006.00	130030.00	18.00	153435.40
	Description:- Supply of Main cable Termination rack complete with scaffolding, fixtures & accessories including square bars for mounting 8-way terminal blocks, ladder, string rods, frame, base assembly, insulators, J bolt , nut/bolts & fasteners, backelite sheet, etc. Siemens type and as per extant practice of Central Railway. Typical part list as per Annexure and rack arrangement shall be as per sketch No.SK-727 with latest alterations.(Inspection by consignee)						
8	8	1.00	Set	822218.00	822218.00	18.00	970217.24
	Description:- Supply of Data logger for monitoring status of important relays, complete with processor Module to monitor following inputs as per spec. RDSO/SPN/99/2006 Spec. No: IRS:S-99/2006 (Amdt-3) with latest amendments including power supply of adequate capacity, battery and fault diagnostic software for failure analysis. Complete data logger & Processor Module (computer) as per Annexure shall be placed in President rack of suitable size to be supplied. This also includes supply of one no. composite computer & printer table (work station table-Godrej/Durian/Transteele) for keeping processor module and one no. Godrej/Durian/Transteele make operator chair. i) 2560 digital and 32 analog inputs.(Inspection by RDSO)						
9	9	1.00	Set	197487.00	197487.00	18.00	233034.66
	Description:- Multi port front end processor with two nos. of dual card modems with and 230/12V charger and 24V, 42AH maintenance free battery. SPN NO.Spc. No.: IRS:S-99/2006 (Amdt-3) or latest (Inspection by RDSO)						
10	10	1.00	Set	36562.00	36562.00	18.00	43143.16
	Description:- Failure analysis software for 1024 digital and below (Inspection by RDSO)						
11	11	1.00	Kilometre	39345.00	39345.00	18.00	46427.10
	Description:- Supply of PVC flexible copper cable single core, multistrand 1x2.5 Sq.mm (50 conductor each diameter 0.25 +/- 0.01) as per IS 694/2010. with latest amendment if any with insulation thickness of 0.70 mm nominal conductor resistance 7.98 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3)or latest.(Inspection by consignee)						
12	12	1.00	Kilometre	76141.00	76141.00	18.00	89846.38
	Description:- Supply of PVC flexible copper cable single core, multistrand 1x6 Sq.mm (84 conductor each diameter 0.30 +/- 0.01) as per IS 694/2010. with latest amendment if any with insulation thickness of 0.80 mm nominal conductor resistance 3.30 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3)or latest .Inspection by consignee)						
13	13	2.00	Kilometre	119222.00	238444.00	18.00	281363.92
	Description:- Supply of PVC flexible copper cable single core, multistrand 1x10 Sq.mm (80 conductor each diameter 0.40 +/- 0.01) as per IS 694/2010. with latest amendment if any with insulation thickness of 1.0 mm nominal conductor resistance 1.91 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3)or latest. (Inspection by consignee)						
	14	2.00	Kilometre	177112.00	354224.00	18.00	417984.32

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

14	Description:- Supply of PVC flexible copper cable single core, multistrand 1x16 Sq.mm (126 conductor each diameter 0.40 +/- 0.01) as per IS 2465/1984 & IS: 694/2010. with latest amendment if any with insulation thickness of 1.0mm nominal conductor resistance 1.121 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3) or latest. Inspection by consignee)						
15	15	2.00	Kilometre	279653.00	559306.00	18.00	659981.08
15	Description:- Supply of PVC flexible copper cable single core, multistrand 1x25 Sq.mm (196 conductor each diameter 0.40 +/- 0.01) as per IS 2465/1984 & IS: 694/2010. with latest amendment if any with insulation thickness of 1.2mm nominal conductor resistance 0.780 ohms/km and test parameters are as per IRS (S) 76/89 (Amd.3) or latest. Inspection by consignee)						
16	16	20.00	Kilometre	5605.00	112100.00	18.00	132278.00
16	Description:- Supply of wire 16/0.2 (Blue, Red, Grey, yellow, Brown, Black, White as per site engineer instruction) finolex/polycab/delton make. IRS:S-76/89 (Amd.3), BS: 4808 Part-2. Wire to be procured from RDSO approved vender. Inspection by consignee)						
17	17	160.00	Numbers	1645.00	263200.00	18.00	310576.00
17	Description:- Supply of low maintenance Lead Acid secondary cells 2V 80AH as per spec. IRS 88/2004 version 1.0 with latest amendments. (Inspection by RITES)						
18	18	60.00	Numbers	3755.00	225300.00	18.00	265854.00
18	Description:- Sealed maintenance free VRLA Battery/Cell 2 volt, 300AH IRS: S-93/96 (A) (Amd.1) or latest.(Inspection by RITES)						
19	19	10.00	Numbers	6323.00	63230.00	18.00	74611.40
19	Description:- Supply of Program switches with acrylic cover, snap action, base mounting type along with cover and mounting bracket 25A-7 pole 3 position Siemens (3 LAO-25/7Y)/ L&T/HEVELS type. Drg. No.RST.C.106.(Inspection by consignee)						
20	20	10.00	Numbers	6595.00	65950.00	18.00	77821.00
20	Description:- Supply of Program switches, snap action, base mounting type along with cover and mounting bracket 63A-7 pole 3 position Siemens (3 LAO-63/7Y)/L&T/HEVELS type Drg.No.RST.C.106. (Inspection by consignee)						
21	21	1.00	Numbers	76605.00	76605.00	18.00	90393.90
21	Description:- Supply of Battery charger self regulating floor mounting type with 230 V AC single phase input and output 110 V DC, 40 A as per spec.IRS.S.86/2000 (Amd.4) with latest amendments. (Inspection by RDSO)						
22	22	3.00	Numbers	53789.00	161367.00	18.00	190413.06
22	Description:- Supply of Battery charger self regulating floor mounting type with 230 V AC single phase input and output 24 V DC,30 A to spec.IRS.S.86/2000 (Amndt-1) with latest amendment for Axle counter application (Amd.4) (Inspection by RDSO)						
23	23	300.00	Kg	112.00	33600.00	18.00	39648.00
23	Description:- Supply of Rubber Mat 5mm thick for use in signaling installation..(Inspection by consignee)						
24	24	30.00	Numbers	7948.00	238440.00	18.00	281359.20
24	Description:- Supply of Key Lock Relay with different ward combinations (Three extra set of ward plate for point Machine to be supplied with each relay). Siemens make working on 60V DC/24 DC or functional equivalent without base plates. RDSO/SPN/219/2016 version 1.0 with Amendment No.1 or latest.(Inspection by RDSO)						
25	25	40.00	Numbers	3359.00	134360.00	18.00	158544.80
25	Description:- Supply of QNA1 AC immunized relay, 8F-8B, 24 VDC along with plug, board, retaining clip and connectors conforming to BRS:931A,IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1(Inspection by RDSO)						
26	26	20.00	Numbers	3507.00	70140.00	18.00	82765.20
26	Description:- Supply of QN1 Non AC immunized neutral relay, 8F-8B, 24 VDC along with plug, board, retaining clip and connectors conforming to BRS:930, IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1(Inspection by RDSO)						
27	27	10.00	Numbers	3876.00	38760.00	18.00	45736.80
27	Description:- Supply of QN1 Non AC immunized neutral relay, 12F-4B, 24 VDC along with plug, board, retaining clip and connectors conforming to BRS:930,IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1(Inspection by RDSO)						
28	28	50.00	Numbers	3241.00	162050.00	18.00	191219.00
28	Description:- Supply of QTA2 AC immunized track relay, 9 Ohm, 2F.1B, along with plug, board, retaining clip and connectors conforming to BRS:939A, 966 & Appendix F2, IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1)(Inspection by RDSO)						
29	29	10.00	Numbers	5531.00	55310.00	18.00	65265.80
29	Description:- Supply of QBAT track Relay, AC immunized, 2F-2B, contacts, 9 ohms. Complete with plug, board, retaining clip and connectors as per RDSO/SPN/84 Ver. 2.0 with Amendment No.1 or latest.(Inspection by RDSO)						

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

30	30	10.00	Numbers	3317.00	33170.00	18.00	39140.60	
	Description:- Supply of Universal LED Lamp proving relay QECX61 relay, 4F-4B, AC conforming to BRS:941A STS/E/RELAYS/AC LIT LED SIGNAL/09-2002, Amdt.-1 (FOR ALL ASPECT ECR FOR AC LED SIGNAL)(Inspection by RDSO)							
31	31	10.00	Numbers	4062.00	40620.00	18.00	47931.60	
	Description:- Supply of QBCA1 AC immunized relay, 2FHD 4F-4B, 24VDC along with plug board, retaining clip and connectors conforming to BRS:943 POINT CONTACTOR RELAY. And RS S46/74 with Amendment No.1 & firms specification(Inspection by RDSO).							
32	32	10.00	Numbers	4006.00	40060.00	18.00	47270.80	
	Description:- Supply of QL1 LATCH relay, 11F-4B or 8F-6B along with plug board, retaining clip and connectors conforming to BRB:935A.(Inspection by RDSO)							
33	33	50.00	Numbers	3415.00	170750.00	18.00	201485.00	
	Description:- Supply of QNA1K relay 1000 ohm, 6F/6B 24V DC as per BRS :931A, IRS:S60, IRSS354 & IRS:S23 and RDSO Spec. STS/E/Relays/UEA (PI) dtd.30.05.1997 Annexure II (IRS:S60/78 with Amendment no.1 , IRS:S34/68 with Amendment no.6 & IRS:S23/88 with Amendment no.1)(Inspection by RDSO)							
34	34	10.00	Numbers	2501.00	25010.00	18.00	29511.80	
	Description:- Supply of Desk type Electronic Magneto Telephone as per spec No. IRS TC-79/2000 (Amd.4) with Amendment No.02 or with latest amendments.(Inspection by consignee)							
35	35	1.00	Numbers	9504.00	9504.00	18.00	11214.72	
	Description:- Supply of Test Board & circuit progress board for relay room as per Drg No RST/C/105 A&B(Inspection by consignee)							
36	36	2.00	Numbers	30024.00	60048.00	18.00	70856.64	
	Description:- Supply of Automatic media changeover of Modems working on redundant channels for data transmission on OFC/Quad/Microwave Radio.(Inspection by consignee)							
37	37	2.00	Numbers	55906.00	111812.00	18.00	131938.16	
	Description:- Supply of Modems for UFSBI (For use with secondary media and OFC/Quad.) (Inspection by consignee)							
38	38	2.00	Set	61649.00	123298.00	18.00	145491.64	
	Description:- Supply of MODEM compatible with existing UFSBI system to work on back up media (either VF channel on OFC P/Mux or 2 Mbps E1 channel from STM or direct dark single mode optic fibre cable upto 30 km distance.(Inspection by consignee)							
39	39	200.00	Numbers	8.00	1600.00	18.00	1888.00	
	Description:- Supply of PPTC Fuse GP 60-185 UL-94 certification (1.6 Amps) for internal / external current. Make: LITTLEFUSE, FUZETEC, TYCO, BOURN, RAYCHEM etc..(Inspection by RDSO)							
40	40	200.00	Numbers	7.00	1400.00	18.00	1652.00	
	Description:- Supply of PPTC Fuse GP 60-400 UL-94 certification (12V/4A) TF, TR Circuit. Make: LITTLEFUSE, FUZETEC, TYCO, BOURN, RAYCHEM etc..(Inspection by RDSO)							
41	41	200.00	Numbers	7.00	1400.00	18.00	1652.00	
	Description:- Supply of PPTC Fuse GP 30-100 (24V/1.4A) TPR Circuit. Make: LITTLEFUSE, FUZETEC, TYCO, BOURN, RAYCHEM etc..(Inspection by RDSO)							
42	42	200.00	Numbers	7.00	1400.00	18.00	1652.00	
	Description:- Supply of PPTC Fuse GP 250-185 UL-94 certification (24V/4A)110V AC for track chargers. Make: LITTLEFUSE, FUZETEC, TYCO, BOURN, RAYCHEM etc..(Inspection by RDSO)							
43	43	30.00	Kg	1078.00	32340.00	18.00	38161.20	
	Description:- Resin cored wire as per specification No.IS:1921-1975 with Alloying element percentage as 63% SN (Tin) nd / 37% Pb (Lead) with percentage of various impurities not exceeding the values Sb (Antimony 0.2% maximum, Cu (Copper) 0.1% maximum, As (Arsenic) 0.05% maximum, Fe (Iron) 0.02% maximum & other impurities mainly Al, Zn & Cd shall be limited. The flux shall be free from corrosive action as per clause 5.2 & flux percentage may be used as per requirement.(Inspection by consignee)							
44	44	150.00	Numbers	57.00	8550.00	18.00	10089.00	
	Description:- Lacing thread rolls, black, wax coated (100 mtrs)(Inspection by consignee)							
45	45	30.00	Each Module	23147.00	694410.00	18.00	819403.80	
	Description:- Design, fabrication and supply of fuse Auto changeover system for 32 Nos external non deteriorating type fuses or 'G' type fuses from 0.6A Amp to 4A Amp capacities used in signaling circuits. System shall have 8 cards with monitoring arrangement of 4 fuses in one card. As per RDSO spec. RDSO/SPN/209/2012 Ver.2.0 or latest amendment if any.(Inspection by RDSO)							
	46	6.00	Each Module	33712.00	202272.00	18.00	238680.96	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

46	Description:- Design, fabrication and supply of fuse Auto changeover system for 24 Nos external non detorating type fuses or 'G' type fuses from 4 A to 10 Amp capacities generally used for point operation circuits. System shall have 6 cards with monitoring arrangement of 4 fuses in one card. As per RDSO spec. RDSO/SPN/209/2012 Ver.2.0 or latest amendment if any.(Inspection by RDSO)						
47	47	15.00	Numbers	5979.00	89685.00	18.00	105828.30
	Description:- Supply of Main signal post 140 mm outer dia 4.6 Mtr Length as per spec No.IRS S 6/81 with latest amendments.(Inspection by consignee)						
48	48	5.00	Numbers	8119.00	40595.00	18.00	47902.10
	Description:- Supply of Main signal post 140 mm outer dia 5.6 Mtr Length as per spec No.IRS S 6/81 with latest amendments.(Inspection by consignee)						
49	49	20.00	Numbers	2650.00	53000.00	18.00	62540.00
	Description:- Supply of Shunt signal post with Base (GI Pipe of 80 mm Dia of min. 1 meter length.) (Inspection by consignee)						
50	50	20.00	Numbers	7944.00	158880.00	18.00	187478.40
	Description:- Supply of Cast Iron Main signal surface base 140mm as per spec No IRS: S-10 and Drg No 2011/M with latest amendments, with CLS Ladder assembly complete for CLS signal 5.5/4.5/3.5 mtrs long as per RDSO Drg no. SA 23156 (Adv), SA 23153 (Adv) & SA 23150 (Adv) Alt.1 respectively with Latest Amendment as the case may be for CLS unit & signal back staging as per extant C.Rly practice.(Inspection by consignee)						
51	51	20.00	Numbers	1752.00	35040.00	18.00	41347.20
	Description:- Supply of Cast Iron Shunt signal surface base 80 mm as per spec No IRS: S-10 and Drg No 2011/M with latest amendments, as per RDSO Drg. No.SA- 23156/ Drg. No.RST/11413 as per extant C. Rly practice. (Inspection by consignee)						
52	52	50.00	Numbers	447.00	22350.00	18.00	26373.00
	Description:- Supply of Signal No.Plates as per Drg No RST-11393/ SK-842(Inspection by consignee)						
53	53	5.00	Numbers	821.00	4105.00	18.00	4843.90
	Description:- OFF set bracket 5-1/2" to suit 140 mm dia CLS Post with two no. of "U" Bolts with nut & washer complete as per RDSO Drg No SA-23080 for signals & Routes.(Inspection by consignee)						
54	54	5.00	Numbers	4129.00	20645.00	18.00	24361.10
	Description:- OFF set bracket 3-1/2' for signals & Routes. Drawing No.SA23840(Adv) Alt-2 as per extant C.Rly practice.(Inspection by consignee)						
55	55	20.00	Numbers	476.00	9520.00	18.00	11233.60
	Description:- Supply of A/AG/C/P/G/IB Board as per Drg. RST-11444/1(A), RDSO Drg No SA-23460(AG), SA-23461(C) , RST-11445, SA 23456(P), SA 23477(G) & SA 23476-77 (IB) as applicable respectively with Latest Amendment.(Inspection by consignee)						
56	56	8.00	Numbers	2763.00	22104.00	18.00	26082.72
	Description:- Supply of Stop Board / IB Board as per RST-11791 (STOP BOARD)/ RDSO Drg No 7235/B as per extant C.Rly practice.(Inspection by consignee)						
57	57	10.00	Numbers	2795.00	27950.00	18.00	32981.00
	Description:- Supply of different warning Board as per Goods warning Board (SK-784) RDSO Drg No. SA 2380 (Adv), SA 2370/M-, Block section limit Board RDSO Drg No. SA 2373 - Paint and retroreflective arrangement as per Railways drawing.(Inspection by consignee)						
58	58	200.00	Numbers	245.00	49000.00	18.00	57820.00
	Description:- Supply of Hand Cuff Locks / Godrej Navtal lock with Three common keys.(Inspection by consignee)						
59	59	15.00	Numbers	25824.00	387360.00	18.00	457084.80
	Description:- Supply of "2 aspect" Signal Unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev.2.0 or latest complete and to suit LED signal Lamps and suitable for 140 mm dia post saves pigment finish on the back side of the and inside. white pigment finish inside the 2 aspect unit to avoid any extra paint cost(Inspection by RDSO)						
60	60	5.00	Numbers	26638.00	133190.00	18.00	157164.20
	Description:- Supply of "3 aspect" Signal Unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev.2.0 or latest complete and to suit LED signal Lamps and suitable for 140 mm dia post saves pigment finish on the back side of the and inside. white pigment finish inside the 4 aspect unit to avoid any extra paint cost(Inspection by RDSO)						
61	61	20.00	Numbers	11731.00	234620.00	18.00	276851.60
	Description:- Supply of Shunt Signal Position Light Type FRP complete as per RDSO Specification RDSO/SPN/194/2006/Rev.2.0 or latest with Off set bracket 3-1/2" to be fitted on 140 mm post drawing No.SA23840(Adv) Alt-2 for dependent type complete with signal unit bracket, terminals etc without lenses, lamp, lamp holder, and to suit LED signal lamps.(Inspection by RDSO)						
	62	2.00	Numbers	36469.00	72938.00	18.00	86066.84

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

62	Description:- Supply of 2 way junction Route Indicator in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev. 2.0 or latest complete and to suit LED signal Lamps(Inspection by RDSO)						
63	63	3.00	Numbers	7154.00	21462.00	18.00	25325.16
63	Description:- Supply of "Calling On" Signal Unit in FRP body without lenses and transformers as per RDSO Specification RDSO/SPN/194/2006/Rev. 2.0 or latest complete and to suit LED signal Lamps(Inspection by RDSO)						
64	64	6.00	Numbers	4381.00	26286.00	18.00	31017.48
64	Description:- Supply and Fixing of RE Protective Screens of expanded metal 12 SWG of size 1200 x 1500 mm on signals as per extent practice & as per instruction of Rly engineer at site DRG - No.SK-844(Inspection by consignee)						
65	65	20000.00	Numbers	65.00	1300000.00	18.00	1534000.00
65	Description:- Supply of ARA Terminal blocks with links made of PBT Specn No.IRS/75/2006 (Rev - 2) with latest amendments and RDSO Drg.No.SA-23741A Alt.4., SA-23745 Alt.5, SA-23746, SA-23748 Alt.4, & SA-23756 Alt.3.(Inspection by RITES)						
66	66	300.00	Numbers	144.00	43200.00	18.00	50976.00
66	Description:- Supply of cartridge fuse block made of PBT as per RDSO Drg No SA-23748 Alt 4, SA-23749 & Spec No.IRS S 75/2006 Rev.02 with latest amendment. Fuse block shall be suitable for round head type voltage fuses.(Inspection by RITES)						
67	67	70.00	Numbers	30.00	2100.00	18.00	2478.00
67	Description:- Supply of Tik-tak, piano type switches, 5 A (as per IS Specification).(Inspection by consignee)						
68	68	70.00	Numbers	205.00	14350.00	18.00	16933.00
68	Description:- Supply of three pole plug and socket 5 Amp (as per IS Specification).(Inspection by consignee)						
69	69	80.00	Numbers	20.00	1600.00	18.00	1888.00
69	Description:- Supply of Lamp 110V / 24W, 2 pin for Loc.(Inspection by consignee)						
70	70	50.00	Numbers	14252.00	712600.00	18.00	840868.00
70	Description:- Supply of Apparatus case with godown locks with detachable handle on both the doors.a) Single Case as per Drg No SK 783-1 & 2. with latest alteration.(Inspection by RITES)						
71	71	20.00	Numbers	11287.00	225740.00	18.00	266373.20
71	Description:- Supply of Apparatus case with godown locks with detachable handle on both the doors. b) Half Case as per Drg No SK 783-1 & 2. with latest alteration.(Inspection by RITES)						
72	72	80.00	Numbers	951.00	76080.00	18.00	89774.40
72	Description:- Supply of earth electrode assembly as per Drg.No. CR/S&T/SK-815 (Inspection by consignee)						
73	73	1.00	Set	51446.00	51446.00	18.00	60706.28
73	Description:- A CLASS EARTHING - Supply of ESR ALTEC TERRA STREAMER Lightning Arrestr with SS adaptor (TSP30, 50 Mtr. Radius) SPN : NFC-17-102-2011.(Inspection by RITES)						
74	74	1.00	Numbers	12067.00	12067.00	18.00	14239.06
74	Description:- Supply of Lightning strike recorder LSC 6 digit shall be weather proof type. It should have 6 digit event count & the capacity to count smallest strike (3KA). It should be voltage sensing type counter. So that it will register nearby strikes & static discharge due to induction effect. as per IS 2309:1989..(Inspection by RITES)						
75	75	500.00	Metre	365.00	182500.00	18.00	215350.00
75	Description:- Supply of 35 Sq. mm. multistrand single core PVC insulated copper for connecting earth bus bar to earth electrode.Inspection by consignee)						
76	76	100.00	Metre	711.00	71100.00	18.00	83898.00
76	Description:- Supply of copper Tape 25x6 mm (Bonding ring conductor) mounted on insulated standoff (1 round).Inspection by consignee)						
77	77	2.00	Numbers	1181.00	2362.00	18.00	2787.16
77	Description:- Supply of 300x25x6 mm Cu equipotential Bus Bar.Inspection by consignee)						
78	78	5.00	Numbers	118645.00	593225.00	18.00	700005.50
78	Description:- Supply of Microprocessor based universal earth resistance sensing unit 12 channel AC/DC. As per RDSO/SPN/256/2002 with latest amendments.Inspection by RDSO)						
79	79	120.00	Numbers	878.00	105360.00	18.00	124324.80
79	Description:- Supply of Track Lead junction Boxes as per C.Rly Drg.No.RST 11509 made from fiber glass alongwith terminal blocks.Inspection by consignee)						
80	80	70.00	Numbers	3099.00	216930.00	18.00	255977.40
80	Description:- Supply of B type choke to specn.No.IRS.S.65/83 (Amd.3) with latest amendments.Inspection by consignee)						

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

81	81	60.00	Numbers	1089.00	65340.00	18.00	77101.20	
	Description:- Supply of adjustable Track Feed Resistance disc type 7.5/15/30 ohms as per RDSO Drg. No. SA 20161-66/M (Adv) with latest amendments (with phenolic moulded base).Inspection by consignee)							
82	82	70.00	Numbers	2001.00	140070.00	18.00	165282.60	
	Description:- Supply of Track feed battery chargers, 110V AC input 2, 4 to 6 V DC Output to Specn. No.IRS.89/2013 Ver.1.0 with latest amendments. Charger shall be suitable for charging 80 AH battery.Inspection by RITES)							
83	83	10000.00	Numbers	2.00	20000.00	18.00	23600.00	
	Description:- Supply of Channel Pins single groove, galvanised, 7 mm suitable for 4mm dia bonding wire as per spec No. IRS: S 17-75 Revision 3.Inspection by consignee)							
84	84	6000.00	Metre	46.00	276000.00	18.00	325680.00	
	Description:- Supply of PVC jacketed wire rope for Track lead connections. PVC jacketed wire rope should be of Galvanised steel wire rope 6mm dia (6x19 stranded wire with steel core of 6 mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10 mm. PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as per IS: 2266:2019. Reclaimed for recycled material should not be used.Inspection by consignee)							
85	85	500.00	Kg	75.00	37500.00	18.00	44250.00	
	Description:- Supply of 8 SWG GI wire (4mm dia) suitable for track circuit rail bonding. As per IRS Specification S:13@45>46@Inspection by consignee)							
86	86	30.00	Numbers	242.00	7260.00	18.00	8566.80	
	Description:- Supply of Hydrometer, Exide make similar for measuring specific gravity of Battery Graded acid with mounting stand in location Boxes. Consignee inspection under manufacturer certificate.Inspection by consignee)							
87	87	60.00	Numbers	1407.00	84420.00	18.00	99615.60	
	Description:- Supply, Installation, testing and commissioning of track battery charger monitoring system for 2V/4V/6V/8V batteries with accessories at nominated stations. General scheme to be approved by Engineer-in-charge.Inspection by consignee)							
88	88	2.00	Numbers	984.00	1968.00	18.00	2322.24	
	Description:- Supply, installation, testing and commissioning of remote indication unit along with all accessories for above item.Inspection by consignee)							
89	89	3.00	Numbers	393822.00	1181466.00	18.00	1394129.88	
	Description:- Supply of single section Digital Axle Counter (SSDAC) with two detection point with reset arrangement and vital relay box as per RDSO/SPN/177/2012 Ver.03 or Latest. Each set consist of following:- a) High frequency TX coil and RX coil (Each set consist of web mounting type TX coils-2 Nos. RX coils-2 Nos along with 10 mtr cable-2 sets),b)Track side digital axle counter unit.-2 nos. c) 24V 6F/4B, 1000 ohm "Q" type relay Box duly wired - 2 Nos. d) Clamp with detector plates and hardware etc-4 Nos e) Reset Box 2 Nos ii) Mushroom/Location Box suitable for housing Track side equipment (2 Nos.) 2) Transportation, Installation testing & commissioning:- Transportation, Installation testing & commissioning of equipment field training (one man day per set) at site or as desired by site Engineer. These includes:- a) Foundation & erection of Track side Equipment i.e. Mushroom/ Location Box (If required). This includes supply of all associated materials., b) Individual Earthing of all detection Point for the OEM recommended earth value certified by OEM site engineer. This includes supply & installation of maintenance free earth materials and exothermic bonding and other connecting cable etc as per Railway practice (As per RDSO Spec.no: RDSO/SPN/197/2008 or latest. Resetting equipment to the connected to the EI Ring earth. c) Installation to be carried out by OEM certified Engineer. 3) Tool Kit consisting of :-a) Digital True RMS multi meter of suitable make for above Digital Axle counter system with probe set- 1nob) Train Simulator (High frequency)-1 no c) Extender Card - 1 no d) Dummy wheel-1 no e) Different type of spanners suitable for above Digital Axle counter - 1 set f) Torque wrenches suitable for the aboe-1 no g) Screw driver set suitable for the above - 1 set. h) Carrying Bag for Tools - 1 no i) 6 nos Electrostatic Discharge Wrist Band for cards/ modules protection. (Inspection by RDSO)							
90	90	30.00	Per Detection Point (DP)	288366.00	8650980.00	18.00	10208156.40	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

90	Description:- Supply of Digital Axle counter Multi section type complete system including the central Evaluator and final track clearance relay for each section, Reset boxes, LV boxes, All track side units with detection point complete assembly & fixing arrangement for each detection point, clamps deflector for either side of each detection points, monitoring console for monitoring all the DPs at a time installed at a station/RH/IBH etc. with all other accessories fully wired and fully equipped as per RDSO specification No.RDSO/SPN/176/2013 (ver.3) or latest and manufacturers specification. The equipment must also include the following: a) System must have remote monitoring and health diagnostics feature as per RDSO specification. b) Surge protection device, c) 20% spare slots for the both detection heads and track section in the evaluator for future and emergency provision. Each set also consisting of a) Double rail contact of standard length of cable as per site requirement and mounting accessories - Equal to no. of DP. b) Deflectors to safe guard Rail contact will be TWICE the no. of DPs. c) Protecting tube from DP to railhead as per requirement. d) Diagnostic PC as per specification and other accessories (as per Annexure) e) Pre-wired cabinet/rack - No. as per site requirement. f) 6 nos. Electrostatic Discharge Wrist Band for cards/modules protection. (Inspection by RDSO)						
91	91	4.00	Numbers	2387.00	9548.00	18.00	11266.64
	Description:- SUPPLY of Electronic timers for DAC reset arrangement 3 sec to 30 sec with 2NO/2NC contact working voltage 24V/60V DC. Siemens/ABB/L&T or SELEC(642X A programmable electronic timer switch) make. (Inspection by CONSIGNEE)						
92	92	500.00	Metre	12606.00	6303000.00	18.00	7437540.00
	Description:- Supply of Multi strand twin twisted core shielded cable of 28 - 30/0.2 mm for Axle counter as per IRS spec. 76/89 with Amendment No.03 or latest amendments, if any. (Inspection by RITES) (Unit Meter = Per 100 Meter)						
93	93	5.00	Numbers	8891.00	44455.00	18.00	52456.90
	Description:- Supply of Pre-wired Crank Handle cum key lock relay box (of metal) alongwith LEDs, with approved type push buttons, 8-way terminal strips, string rod, etc. as per Drawing No.RST.C.114 (Inspection by CONSIGNEE)						
94	94	50.00	Set	452.00	22600.00	18.00	26668.00
	Description:- Supply of William stretcher nylon insulation set suitable for ground connection as per RDSO drg No T-10367, T-10368, T-10384 as applicable and to the spec IRS S 23/88 with Amendment No.01 & 40/84 with Amendment No.01 or latest amendments. (Inspection by RITES)						
95	95	50.00	Set	287.00	14350.00	18.00	16933.00
	Description:- Supply of Tongue attachment nylon insulation set consisting of one insulating plate as per Drg no: RST-106961 & 3 nos of Ferrules with collars to suite rodding supplied as per RDSO spec & Drg.no: RST-10692 (Inspection by RITES)						
96	96	50.00	Set	207.00	10350.00	18.00	12213.00
	Description:- Supply of Gauge Tie Plate nylon insulation as per RDSO drg No: T-10372 Alt2, T-10368, T-10371 Alt2, T-15083/88/Alt2 & T-11690/Alt2 and to the spec IRS S 23/88 with Amendment No.01 & 40/84 with Amendment No.01 or latest amendments. (Inspection by RITES)						
97	97	25.00	Set	7018.00	175450.00	18.00	207031.00
	Description:- Supply of Ground connections, complete set suitable for IRS type/appd. Point Machine for ordinary turnout with tongue attachment insulation and other insulation as per RDSO Drg.S/3361@47>47?40@for IRS type point machine) or RDSO Drg No.SA-9151/52 (for Siemens point machine) with latest amendments. However the ground connection shall be procured only after confirmation from Railway engineer as per site condition /type of machine/turnout. (Inspection by RITES)						
98	98	10.00	Set	5707.00	57070.00	18.00	67342.60
	Description:- Supply of Ground connections, complete set suitable for IRS type/appd. Point Machine for derail switch with tongue attachment insulation as per RDSO Drg.S/3361@47>47?40@for IRS type point machine) or RDSO Drg No.SA-9151/52 with latest amendments. However the ground connection shall be procured only after confirmation from Railway engineer as per site condition /type of machine/turnout. (Inspection by RITES)						
99	99	50.00	Numbers	211.00	10550.00	18.00	12449.00
	Description:- Supply of GI bend pipe, B class, 50mm dia for cable entry in point machine alongwith required fixing arrangements as per standard practice on Central Railway. As per Drg No. RST.11835. (Inspection by CONSIGNEE)						
100	100	300.00	Metre	908.00	272400.00	18.00	321432.00
	Description:- Supply of GI pipe, inner dia. 100mm dia. B-class as per spec. No.IS 1239 PT. 1/2004 or latest with sockets and fittings. TATA/JINDAL/ZENITH BIRLA make. (Inspection by RITES)						
101	101	2000.00	Metre	288.00	576000.00	18.00	679680.00
	Description:- Supply of DWC HDPE pipe with one snap fit coupler and 'O' ring fire resistant, anti rodent, in 6 meter length of size 120 mm outer dia as per RDSO/SPN/204/2011 Ver 1.1 with Amd.1 or latest. (Inspection by RITES)						
102	102	6000.00	Numbers	365.00	2190000.00	18.00	2584200.00
102							

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

	Description:- Supply of RCC pipes half round of size 300 mm dia outer and 250 mm dia internal 1 mtr long matching to IS No.458/2003 amendment-1 with Rev.4..Inspection by CONSIGNEE)						
103	103	3000.00	Numbers	100.00	300000.00	18.00	354000.00
	Description:- Supply of Modular terminal block of 2.5 sq.mm 2 in 2 out type disconnect type terminal along with as per RDSO/SPN/189/2004 Rev 3.0. The current capacity of 16 Amps and more. The terminal should have marking at centre to view description from front. Material to be procured from RDSO approved firms only..Inspection by RITES)						
104	104	300.00	Numbers	187.00	56100.00	18.00	66198.00
	Description:- Supply of DIN Channel for the terminals 1 Mtrs eachInspection by CONSIGNEE)						
105	105	300.00	Numbers	20.00	6000.00	18.00	7080.00
	Description:- Supply of End plates for modular terminal block Inspection by CONSIGNEE)						
106	106	600.00	Numbers	15.00	9000.00	18.00	10620.00
	Description:- Supply of End Clamp for modular terminal block Inspection by CONSIGNEE)						
107	107	2.00	Numbers	7266.00	14532.00	18.00	17147.76
	Description:- Operating tool (operating tool, screw driver & stripper) as per Annexure. Inspection by CONSIGNEE)						
108	108	2.00	Set	42990.00	85980.00	18.00	101456.40
	Description:- Tool bag complete with Megger as per Annexure. ADD AC / DC clamp meter, with Hand Held Tool Bag. Inspection by CONSIGNEE)						
109	109	1.00	Numbers	3856.00	3856.00	18.00	4550.08
	Description:- Supply of Digital measuring wheel for measuring cable trench/route make: Stanley or Freemans make or similar reputed make. Inspection by CONSIGNEE)						
110	110	2.00	Numbers	123508.00	247016.00	18.00	291478.88
	Description:- CABLE ROUTE TRACER for tracing existing cable route and depth make: Stanley/MEGGER/Rycom. Inspection by CONSIGNEE)						
111	111	100.00	Numbers	28.00	2800.00	18.00	3304.00
	Description:- Supply of Adhesive Tapes rolls, PVC (18mm x 25 Mtr) Steel Grip/SCOTCH/ANCHOR. Inspection by CONSIGNEE)						
112	112	20.00	Numbers	4321.00	86420.00	18.00	101975.60
	Description:- Supply of 4.5 kg CPO2 type fire extinguisher along with all accesories, extinguisher testing certificate has to be supplied along with - Supply of ISI marked Carbon Dioxide type (BC) fire extinguisher of 4.5 Kg capacity confirming to IS 2878: 2004 from seamless cylinder, with ISI marked control value, high pressure mtr., Long discharge hose and horn complete with initial gas charged with carrying handle and wall mounting braket etc. as required by site Engineer.Inspection by CONSIGNEE)						
113	113	1.00	Numbers	55467.00	55467.00	18.00	65451.06
	Description:- Supply, Installation, Testing & Commissioning of Microprocessor based intelligent, addressable, Fire Alarm control Panel with LCD display complying to RDSO/SPN/217/2025 Ver 3.1 or latest modular, 1 loop (minimum 125 detector/devices per loop-expandable to 2 loops) with 320 Character with soft keys for displaying alarm, events and operating functions, Day/Night operation function, Remote maintenance service feature etc. The panel should be multi-protocol i.e. able to support at least 2 different makes of addressable detectors. The panel should have minimum two relay outputs & 1 Monitored Sounder Output. It should have provision to be connected to repeater panels in future. The panel shall capable to operate on 230 volts AC power supply, automatic battery charger, 24 volts, sealed lead acid maintenance free batteries sufficient for 24 hours normal working and then be capable of operating the system for 30 minutes during emergency condition. Panel should be Vds Certified. (Inspection by RDSO)						
114	114	60.00	Numbers	2748.00	164880.00	18.00	194558.40
	Description:- Suply, Installation, Testing & Commissioning of Analogue Addressable Multisensor Detector complying to RDSO/SPN/217/2025 Ver 3.1 or latest. As per latest VDS approved/Listed. (Inspection by RDSO)						
115	115	2.00	Numbers	4313.00	8626.00	18.00	10178.68
	Description:- Suply, Installation, Testing & Commissioning of Manual call points, complying to RDSO/SPN/217/2025 Ver 3.1 or latest. As per latest VDS approved/Listed.(Inspection by RDSO)						
116	116	400.00	Metre	1167.00	466800.00	18.00	550824.00
	Description:- Suply, Installation, Testing & Commissioning of Resettable, Analogue Type Liner Heat Sensing (LHS) Cable complying to RDSO/SPN/217/2025 Ver 3.1 or latest. As per latest VDS approved/Listed.(Inspection by RDSO)						
117	117	1.00	Numbers	110725.00	110725.00	18.00	130655.50
	Description:- Suply, Installation, Testing & Commissioning of LHS Interface Module with all accessories for single stretch, complying to RDSO/SPN/217/2025 Ver 3.1 or latest. As per latest VDS approved/Listed.(Inspection by RDSO)						

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

118	118	1.00	Numbers	222716.00	222716.00	18.00	262804.88	
	Description:- Suply, Installation, Testing & Commissioning of Aspiration (Air Sampling Type) Detection unit complying to RDSO/SPN/217/2025 Ver 3.1 or latest. As per latest VDS approved/Listed.(Inspection by RDSO)							
119	119	100.00	Metre	1320.00	132000.00	18.00	155760.00	
	Description:- Suply, Installation, Testing & Commissioning of CPVC pipe for Aspiration Detection system complying toRDSO/SPN/217/2025 Ver 3.1 or latest. As per latest VDS approved/Listed /approved by UL or FM or VDS or LPCB or tested with appropriate equivalant standard. (Inspection by RDSO)							
120	120	3.00	Numbers	7151.00	21453.00	18.00	25314.54	
	Description:- Suply, Installation, Testing & Commissioning of Analogue Addressable loop powered Monitor Module with inbuilt isolator complying to RDSO/SPN/217/2025 Ver 3.1 or latest. As per latest VDS approved/Listed.(Inspection by RDSO)							
121	121	3.00	Numbers	7151.00	21453.00	18.00	25314.54	
	Description:- Suply, Installation, Testing & Commissioning of Analogue Addressable loop powered Control Module complying to RDSO/SPN/217/2025 Ver 3.1 or latest. (Inspection by RDSO)							
122	122	1.00	Numbers	6394.00	6394.00	18.00	7544.92	
	Description:- Suply, Testing & Commissioning of Hooter cum strobe complying to RDSO/SPN/217/2025 Ver 3.1 or latest..(Inspection by RDSO)							
123	123	300.00	Metre	94.00	28200.00	18.00	33276.00	
	Description:- Suply, Testing & Commissioning of 2C 1.5 sq mm twisted shielded armoured copper cable (Per Meter) with accessories complying to the RDSO/SPN/217/2025 Ver 3.1 or latest.. (Inspection by RDSO)							
124	124	2.00	Numbers	3071.00	6142.00	18.00	7247.56	
	Description:- Suply, Testing & Commissioning of Isolator Device to isolate the circuit in case of short circuit, complying to the RDSO/SPN/217/2025 Ver 3.1 or latest.(Inspection by RDSO)							
125	125	1.00	Numbers	7413.00	7413.00	18.00	8747.34	
	Description:- Suply, Testing & Commissioning of Auto Telephone Dialler (GSM) to send the pre-recorded message to multiple mobile numbers, programmed earlier, complying to the RDSO/SPN/217/2025 Ver 3.1 or latest.(Inspection by RDSO)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-Supply, Installation, Testing & commissioning of Indoor & Outdoor equipment's and Provision of Electronic Interlocking at Sainagar Shirdi Station in connection with provision of 5 stabling line in Pune Division of Central Railway.							13387606.22	Above/ Below/Par
1	1	1.00	Station	416994.00	416994.00	18.00	492052.92	
	Description:- Installation, testing & commissioning of EI system complying to RDSO Technical Advisory Note No STS/E/TAN/3012 Ver 2.0 dated 10.08.2016 and Supply, Installation, testing & commissioning of earthing arrangment for EI as per RDSO/SPN/197/2008 at locations/Gumtis/Cabins/EI Huts/Auto Hut of the yard, Earthing of EI equipment, relay racks and power equipment etc to be done with Class A protection, Earthing shall be in the form of perimetric/Ring Earth conforming to RDSO specification and RDSO technical advisory note for earthing and bonding scheme of EI No.STS/E/TAN/3006 Ver.1 Dt. 02.11.2012 or latest, with earth resistance less than 1 ohm.							
2	2	24.00	Man-Month	66458.00	1594992.00	18.00	1882090.56	
	Description:- Training of Technician / Engineers/ Senior Engineer in installation, for trouble shooting & repairing, commissioning, Testing, Repairs Troubleshooting. (Hard copies of training material/ course modules to be given to each participant).							
3	3	4.00	Numbers	1258.00	5032.00	18.00	5937.76	
	Description:- Installation of Relay Rack Assembly including IDF pillars if any complete with wall supports, scaffolding, ladders, runway for cables, Relay/Relay group base plates, fixing of Tag blocks etc. The work shall be done as per approved plan, extant practice on C.Railways & the instructions of Rly engineer at site.							
4	4	5.00	Numbers	1024.00	5120.00	18.00	6041.60	
	Description:- Installation of Cable Termination Rack Assembly complete including wall supports, scaffolding, Disconnecting links/ARA terminal, 96 way tag block with tag block cover & other necessary accessories etc. The work shall be done as per approved plan, extant practice on C.Railways & the instructions of Rly engineer at site.							
5	5	3750.00	Numbers	9.00	33750.00	18.00	39825.00	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

	Description:- Termination of cable cores on ARA terminal/disconnecting links in the cable termination rack. This includes all associated works of pulling out the cable from under ground, peeling off insulation, dressing of Cable core supported on sting rods with contractors own material. The work shall be done as per instructions of Rly engineer at site.						
6	6	1.00	Set	38566.00	38566.00	18.00	45507.88
	Description:- Installation, wiring, testing and commissioning of Data logger complete along with accessories with contractors own wiring & fixing material as per following configuration. (It includes loading of NETWORKING software and networking of data logger. The requisite communication cable/channel for networking will be arranged by Railway. i) 2560 digital and 32 analog inputs.						
7	7	256.00	Numbers	58.00	14848.00	18.00	17520.64
	Description:- Charging of 2V Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice of C.Rly & instruction of Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by contractor & Rly's site-in-charge. (Unit Numbers = Per 100 VAH)						
8	8	1.00	Numbers	8531.00	8531.00	18.00	10066.58
	Description:- Installation of control and other communication equipment like control phone/magneto phones/auto phones etc in panel Room as per instructions of engineer-in-charge.						
9	9	2.00	Lot	24836.00	49672.00	18.00	58612.96
	Description:- Wiring and Charging of Integrated power supply to signalling installation. This includes connection of MF Earth of 1 ohm earth resistance for IPS and power distribution connection to bus bars and relay racks in the room with contractor's own wiring materials and fabrication and fixing of AC/DC power distribution board made on 10mm thick phenolic hylam sheets or any standard make with connections suitable for 63 A. Wiring to be done considering site requirement, depending upon the load with suitable wires, lugs & glands as per instructions of Engineer-in-charge. This item also includes supply & fixing of ladder along the wall for carrying power supply wires/cables from IPS room to Relay room/power room and potential free contact wiring at Datalogger IDF etc.						
10	10	20.00	Each Module	537.00	10740.00	18.00	12673.20
	Description:- Wiring, fixing & commissioning of modules of fuse 0.6 to 4 Amp rating alarm system having change over arrangement and potential free contact wiring at Datalogger IDF. Etc as per instructions of Railway Engineer. (Module of 32 nos fuses)						
11	11	5.00	Each Module	523.00	2615.00	18.00	3085.70
	Description:- Wiring, fixing & commissioning of modules of fuse 4 to 10 Amp rating alarm system having change over arrangement and potential free contact wiring at Datalogger IDF. Etc as per instructions of Railway Engineer. (Module of 24 nos fuses)						
12	12	9.00	Rack	290.00	2610.00	18.00	3079.80
	Description:- Lettering & Numbering of detail and description writing of particulars of terminations & equipments on relay rack, relays, cable termination rack, battery & power equipment, IPS, operating panel, axle counter etc constituting entire system with contractor's own paint and writing material ("Asian/Dulux" make enamel paints to be used). The work shall be done as per extant practice on C.Rly & instruction of Rly engineer at site.						
13	13	1.00	Lot	49786.00	49786.00	18.00	58747.48
	Description:- Preparation of cable route plan, cable coreage plan, location particulars, cable termination rack particulars, cable meggering report, earth resistance particulars, Traction bonding diagram, 1/2 wire count sheet and any other drawing in Autocad in A3/A4 size. The contractor shall initially supply 3 sets of circuits complete for approval of Railways. Railways will return one set to the contractor duly approved with alteration/corrections if any. The contractor shall incorporate Railways alterations/corrections in the tracings without any deviation and submit all tracings complete in all respects to the Railways. This includes submission of final cable route plan as per laid cable duly measured at every 30m clearly indicating distance of laid cable from fixed point of reference & indicating all track crossings and tail cables. This also include designing of cable coreage plan based upon I.P. in consultation with engineer-in-charge. i) For big yards (>100 routes)						
14	14	1.00	Lot	17505.00	17505.00	18.00	20655.90
	Description:- Preparation of final ammonia prints of diagrams in A-3 size after tracings are approved by Railways, in four sets for final submission with one set of diagrams in transparent polythene bag/lamination. (only two sheets shall be placed on one polythene bag/laminated each). Every set shall be set in a plastic folder of A3 size and of good quality. The final approved tracings will be handed over to contractor by railway for this purpose and contractor will return back the same after taking out the prints for stations having less than 20 routes. i) for stations having 101 - 200 routes						
--	15	20.00	Numbers	7537.00	150740.00	18.00	177873.20

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

15				Description:- Excavation and Casting of main signal foundation as per Drg No SK 801 with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for casting of foundation will have to be brought by the contractor at his own cost.			
	16	20.00	Numbers	2043.00	40860.00	18.00	48214.80
16				Description:- Excavation and Casting of Shunt signal foundation as per Drg No SK 802 with contractor's own materials including cement and anchor bolts of standard size. The required scaffolding Ferma etc for casting of foundation will have to be brought by the contractor at his own cost.			
	17	20.00	Numbers	2841.00	56820.00	18.00	67047.60
17				Description:- Erection of CLS post with surface base and signal unit on top or on OFF set Bracket, fixing of front and back staging, ladder and guards, signal name plates/boards if any with contractors own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site.			
	18	20.00	Numbers	371.00	7420.00	18.00	8755.60
18				Description:- Erection of shunt signal with surface base, post, signal unit and fixing of No. plates. The work shall be done as per instructions of Rly engineer at site.			
	19	2.00	Numbers	608.00	1216.00	18.00	1434.88
19				Description:- Fixing of Jn. Route Indication 1-way/2-way/3-way on the top of the signal post.			
	20	5.00	Numbers	435.00	2175.00	18.00	2566.50
20				Description:- Fixing of stop Board, Block section limit Board, goods warning board with contractors own material. The work shall be done as per instruction of Rly engineer at site.			
	21	20.00	Numbers	900.00	18000.00	18.00	21240.00
21				Description:- Termination of tail cable on Main signal units and wiring with contractor own material etc. The work shall be done as per instruction of Rly engineer at site.			
	22	20.00	Numbers	273.00	5460.00	18.00	6442.80
22				Description:- Termination of tail cable on Shunt signal units and wiring with contractor own material etc. The work shall be done as per instruction of Rly engineer at site.			
	23	40.00	Numbers	406.00	16240.00	18.00	19163.20
23				Description:- Installation on ON/OFF aspect LED's in signal including termination of tail cable on signal, wiring fixing of LED units and testing. The work shall be done as per instruction of Railway engineer at site.			
	24	50.00	Numbers	1942.00	97100.00	18.00	114578.00
24				Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783- 1& 2. with latest alterations & as per instructions of Rly engineer at site. a) Single Case			
	25	20.00	Numbers	1647.00	32940.00	18.00	38869.20
25				Description:- Fabrication and fixing of phenolic laminated/Fibre glass sheet in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated/with PVC pipe covered string rods at the back side for cable support with contractor's own materials. The work shall be done as per drg and arrangement similar to SK 783- 1& 2. with latest alterations & as per instructions of Rly engineer at site.b) Half Case			
	26	50.00	Numbers	462.00	23100.00	18.00	27258.00
26				Description:- Fixing of cutting in relay bases & wiring of relays with Contractors own material obtained from approved sources in location box as per the instructions of Engineer in charge.			
	27	20000.00	Per Conductor	12.00	240000.00	18.00	283200.00
27				Description:- Fixing of ARA Terminals and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry.			
	28	40000.00	Per Conductor	9.00	360000.00	18.00	424800.00
28				Description:- Termination of cable cores on ARA terminal/fuse blocks in the apparatus cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site.			
	29	45.00	Numbers	8500.00	382500.00	18.00	451350.00
29				Description:- Excavation and Casting of Apparatus case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding ferma etc for Casting of foundation will have to be brought by the contractor at his own cost. a) Single Case as per Drg No SK-803			
	30	20.00	Numbers	8024.00	160480.00	18.00	189366.40

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

30				Description:- Excavation and Casting of Apparatus case foundation with contractors Anchor bolts, cement, ballast and other materials. The required scaffolding ferma etc for Casting of foundation will have to be brought by the contractor at his own cost.b) Half Case as per Drg No SK-804				
31	31	50.00	Numbers	945.00	47250.00	18.00	55755.00	
				Description:- Erection of Apparatus cases. This includes filling of location foundations and plastering.a) Single Case				
32	32	20.00	Numbers	703.00	14060.00	18.00	16590.80	
				Description:- Erection of Apparatus cases. This includes filling of location foundations and plastering. b) Half Case				
33	33	20.00	Numbers	1266.00	25320.00	18.00	29877.60	
				Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc. as applicable) & wiring of the same in apparatus cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice.a) Single Case				
34	34	80.00	Numbers	2088.00	167040.00	18.00	197107.20	
				Description:- Installation of earth electrode assembly as per Drg.No.RE/S&T/SIG/Tender/SK726/85 including earth wire connected through GI wire 8 SWG supported on M.S. flat of size 6mm x 40 mm to earth electrode as per drg. No.CR/S&T/SK-815 for sigg. Equipment such as lever frames, apparatus case, signals, relay racks, block instruments, and etc. as per RE manual. The earth value should be less than 10 Ohms including the lead wire. The value should be measured in presence of Rly. supervisor. It should be documented and painted on earth enclosure made of concrete.(only earth electrode will be supplied by Railway). All other material required for provision of earthing will be brought by the contractor.				
35	35	1.00	Station	14463.00	14463.00	18.00	17066.34	
				Description:- Installation & commissioning A-Class Lighting protection complete include base plate with base mast & accessories SPN: NFC-17-102-2011 and as per IS 2309:1989.				
36	36	20.00	Set	4382.00	87640.00	18.00	103415.20	
				Description:- Installation of unit earth as per RDSO/SPN/197/ver I or latest, to construct earthing of </=1 Ohm consisting of a digging the earth to required depth, insertion of electrode, filling of earth enhancing compound & construction of chamber, measurement of earth value and all other work of earthing as per code of practice. All the consumables for mounting the copper tape inside the relay room, Exothermic weld materials and tools & fixtures for the welding copper tapes nd Electrodes etc shall be arranged by the contractor.				
37	37	20.00	Numbers	5783.00	115660.00	18.00	136478.80	
				Description:- Installation, wiring, testing and commissioning of Microprocessor based universal earth leakage detector unit 12 channel AC/DC.				
38	38	120.00	Numbers	1012.00	121440.00	18.00	143299.20	
				Description:- Erection, Fitting and Rail connection of Track Lead junction Box on two supports (M.S.angle) with contractor's fixing material and PVC jacketed wire for track lead connection including angles of size 40x40x5mm 1200mm length. This will include drilling of holes for track lead/side connections of rail. The work shall be carried out as per Drg. No.SK-845 or / & instructions of Rly engineer at site.				
39	39	200.00	Numbers	134.00	26800.00	18.00	31624.00	
				Description:- Provision of bounding with contractor's PVC jacketed wire rope for Track Lead connections. PVC jacketed wire rope should be of Galvanised steel wire rope 6 mm dia (6x19 stranded wire with steel core of 6mm dia) sheathed with PVC 2mm wall thickness, overall thickness being 10 mm. PVC sheath should be made of type 6 compound as per IS 5831 of 1984 Reaffirmed 2001 and steel wire rope as Per IS:2266:2019. Reclaimed or recycled material should not be used. This will include drilling of 7.1mm dia holes in rails (4 Nos) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own materials and tools as per instruction of Rly engineer at site.				
40	40	200.00	Numbers	122.00	24400.00	18.00	28792.00	
				Description:- Provision of bounding with GI wire 4mm dia (8 SWG) for track jumper & fish plate joints bonds. This will include drilling of 7.1mm dia holes in rails (4 Nos) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own tools as per instruction of Rly engieer at site.				
41	41	2.00	Set	19374.00	38748.00	18.00	45722.64	
				Description:- Installation of Axle counter (Digital)/Central Evaluator,wiring from CT rack to central evaluator, installation and wiring of indoor & outdoor reset box and wiring the power supply including supply of 2 core shielded cable of required size copper conductor as per IRS S 76/89 or IS694/1977 as applicable with other accessories. NOTE: Installation/programming/configuration/commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railway/RDSO preferably by Authorised representative of OEM.				
	42	4.00	Set	10841.00	43364.00	18.00	51169.52	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

42	Description:- Installation of EJB and Track devices of Digital Axle counter including digging of trench, drilling of holes, if required on rail, laying of Doubled walled antirodent corrugated pipe, Medium class from track device to location box and making its terminations. (DWC pipe made up of High density polyethylene of 60mm outer dia of suitable length and all other accessories as per site requirement to be supplied by firm.) NOTE: Installation/programming/configuration/commissioning of Axle counter equipment to be carried out in accordance with latest guidelines issued by Railway/RDSO preferably by Authorised representative of OEM.						
43	43	1.00	Set	9250.00	9250.00	18.00	10915.00
	Description:- Fixing of track devices (Transmitter coil and receiver coil) to the rails, fixing of EJB in the location connection of track device to EJB using DWC pipe of suitable length and wiring of EJB, testing and adjustment of transmitter and receiver to obtained required channel level as per standard practices on C.rly and instruction of Rly Engineer on site.						
44	44	30.00	Per Detection Point (DP)	2269.00	68070.00	18.00	80322.60
	Description:- Installation, wiring & /commissioning of Multi section Digital Axle counters's central unit/Evaluator/Processor for the section/at station including its associated all indoor equipments, Indication panel, monitoring console/interface computer and wiring the same to integrate with the relay circuits including supply required power cable of multistrand 10 sq.mm or more from power room to central evaluator, 2 core shielded cable of required size copper conductor as per as per IRS (S)76/89(Amd.3). or IS 694/2010. with latest amendment as applicable with other accessories as per the instruction of Rly engineer at site and earthing as per OEM's technical requirement and specifications. This also includes laying & termination of cable, if any from panel Room to Axle counter room/Relay room in DWC pipe with contractor's material/existing ladder.						
45	45	30.00	Station	5895.00	176850.00	18.00	208683.00
	Description:- Installation, wiring & Testing / commissioning of Axle counters Reset Box of all types in Cabin/Panel Room and wiring the same to integrate with the axle counter as per instructions of Railway Engineer at site. This includes laying & termination of cable, if any from Panel Room/Axle counter room/ Relay Room to Reset Box in DWC pipe/existing ladder.						
46	46	12.00	Numbers	12253.00	147036.00	18.00	173502.48
	Description:- Installation, fixing and wiring of Track side Electronic Equipment of Axle counters including its battery & charger (if required), foundation and earthing as per OEM's technical requirement and specification associated Relays in apparatus cases, location huts, relay rooms etc., with contractor's wiring material, termination of tail cables on terminals/fuse blocks, Supply and making Axle counter parameter history cards, all activites as per standard practice and technical specifications.						
47	47	45.00	Numbers	9428.00	424260.00	18.00	500626.80
	Description:- Installation of complete assembly of track device/double rail Contact unit for entry or exit with conductors all material including drilling of required sizes holes on rails for fixing these, taking the cable lead through anti-rodent, anti-oxidant & non-flame propagating type Double walled corrugated (DWC) pipe as per RDSO/SPN/204/2011 Ver 1.1 with Amd.1 or latest from track device to location box and terminating it on terminals including digging of trench under track and up to location/Track side unit and all other accessories as per site requirement for laying of transmitter and receiver cable with suitable wire embeded rubber pipe with clamp for protecting these cables at DP end. (Unit Numbers = Per track device/double rail contact)						
48	48	45.00	Per Detection Point (DP)	731.00	32895.00	18.00	38816.10
	Description:- Installation of complete assembly of deflectors on either side of Track Device/Double Rail Contact Unit including drilling of required sizes holes on rails for fixing these.						
49	49	1.00	Station	36538.00	36538.00	18.00	43114.84
	Description:- Supply, fixing & Wiring of mismatch panel depicting Indication panel/VDU layout with contractors own material like LEDs for each track section, flexible wire, connecting terminals, buzzer etc. The work shall be done as per extant practice on C.Rly & the instruction of Rly engineer at site.Inspection by consignee)						
50	50	5.00	Turn-out	3862.00	19310.00	18.00	22785.80
	Description:- Refixing of electrical point machine, ground connection during phase working (Non interlocked working) after removing the existing fitting if any, adjustment if necessary, cable termination, wiring, testing and commissioning of electrically operated point, fixing and connecting point indicator on derail switch if necessary. The work shall be done as per extant practice on C.Rly & the instuction of Rly engineer at site.						
	51	30.00	Turn-out	2709.00	81270.00	18.00	95898.60

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

51	Description:- Fixing of point machine on newly laid turnout on Wooden/MBC sleepers, fixing of ground connections, adjustment and testing with crank handle operations, Removal of ground connection & point machines duly numbered. This will include fixing of bend pipes with welded frame for cable entry to machine. This will also includes necessary adjustment and smithy work, drilling of holes to tounge rails, fitting of insulation for tounge attachment, gauge plate & stretcher bars, cable termination & wiring if required. The work shall be done as per extant practice on C.Rly & the instuction of Rly engineer at site.						
52	52	5.00	Numbers	2451.00	12255.00	18.00	14460.90
	Description:- Installation, fixing and wiring of Boxes for key Lock Relays with contractor's wiring & fixing material. The work shall be done as per extant practice on C.Rly & the instruction of site engineer.						
53	53	2000.00	cum	291.00	582000.00	18.00	686760.00
	Description:- Excavation of cable trench as per cable route plan, 1.0 mt. deep and 300mm wide along side the track in normal soil/strata, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid to trench by loose soil for a layer of 50mm thickness after clearing of route, bushes etc. It shall be ensured that top of the cables laid is at a depth of 0.8 m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions, proportionate payment will be made as per procedure. The work shall be done as per extant practice on C.Rly & the instruction of Railway engineer at site. Drg No SK 805						
54	54	200.00	cum	491.00	98200.00	18.00	115876.00
	Description:- Excavation of cable trench as per cable route plan, 1.0 mt. deep and 300mm wide along side the track in hard soil, conforming to distances as per cable route plan and refilling after cable laying. This work includes covering of cable laid to trench by loose soil for a layer of 50mm thickness afer clearing of route, bushes etc. It shall be ensured that top of the cables laid is at a depth of 0.8 m or more. If it is less, then the width and depth shall be suitably increased and accordingly proportionate payment shall be made. In case depth of trench is not achievable due to site conditions, proportionate payment will be made as per procedure. The work shall be done as per extant practice on C.Rly & the instruction of Railway engineer at site. Drg No SK 805						
55	55	100.00	cum	2438.00	243800.00	18.00	287684.00
	Description:- Cutting of all types of Roads/platforms (except concrete type) for trenching and excavation to depth of 300mmx300mm wide approx. and refilling after laying of RCC/GI/DWC pipe & to restore them to original condition. The work shall be done as per extant practice on C.Rly & the instruction of Railway engineer at site. Drg No SK 807						
56	56	300.00	Metre	60.00	18000.00	18.00	21240.00
	Description:- Fixing of GI pipes for crossing the culverts, bridges etc. and concreting of ends with brick masonry at both ends as per the instruction of Rly engineer at site.						
57	57	120.00	cum	504.00	60480.00	18.00	71366.40
	Description:- Digging of trench 1.0 M deep from rail flange/road level (for LC) and, 0.3 Mtr to 0.6 Mtrs wide and back filling after placing of DWC/RCC/GI pipe. (Placing of DWC/RCC/GI pipe covered separately). The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. Drg No SK 806						
58	58	6000.00	Metre	49.00	294000.00	18.00	346920.00
	Description:- Laying of DWC/RCC pipes alongwith collars / RCC Half round pipes in trenches at places of track and road crossings, platform cutting etc.						
59	59	400.00	Kilometre	4542.00	1816800.00	18.00	2143824.00
	Description:- Laying of signalling/Power/Telecom cable of various cores/sizes in trenches.						
60	60	10.00	Numbers	3005.00	30050.00	18.00	35459.00
	Description:- Jointing of 4 / 6 quad cable with Heat shrinkable straight through jointing kit for 4/6 quad cable.						
61	61	30.00	Metre	1703.00	51090.00	18.00	60286.20
	Description:- Provision of brick masonry duct as per Rly.Drg.No.PA/N/CN/STD/19 (modified) after cutting of platform/excavating the earth for the duct with contractor's own materials and restoring the excavated earth to its original condition.						
62	62	30.00	cum	4419.00	132570.00	18.00	156432.60
	Description:- "Where ever depth of 0.5 m cable trench is not feasible, cable shall be protected as under:- Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench."						
63	63	2000.00	Numbers	16.00	32000.00	18.00	37760.00
	Description:- Fixing of modular termianal/fuse blocks alongwith all accessories with provision of fixing holes on hylam sheets/side angles of Loc Box and fixing by galvanised nuts & bolts. This includes fixing on DIN channel alongwith PVC Comb type 'C' channel (size 2 inch x 2 inch) for cable termination of modular terminal. The PVC channel with cover to be supplied by firm as required. The work shall be done as per the instruction of Rly engineer at site.						

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

64	64	2000.00	Numbers	6.00	12000.00	18.00	14160.00	
	Description:- Termination of cable cores on ARA terminal/Disconnecting link/fuse blocks, in the apparatus Cases/ cable termination rack. This includes all associated works of pulling out the cable from underground. The work shall be done as per location plans and instructions of Rly engineer at site.							
65	65	300.00	Metre	116.00	34800.00	18.00	41064.00	
	Description:- Laying of GI pipes in on bridges/culverts/concrete drain/ mountain ridges etc. with suitable GI bend shall be provided where there is turning of pipe as per instructions of the site engineer. GI Clamps at every 2 m as shown in the drawing to be fixed. Suitable holes to be made in the pipe before laying as per instructions of the site engineer. 100 mm dia. Drg No SK 808							
66	66	4.00	Location Box	1668.00	6672.00	18.00	7872.96	
	Description:- Releasing of cables from old location boxes and taking it into new location boxes. This includes excavating the earth to release the cables. From old location box for taking it into new location. This also includes releasing the old location box and bringing it to nearest station/central cabin. Location (old) will be released only after ensuring all working cables have been shifted in New location.							
67	67	100.00	Numbers	102.00	10200.00	18.00	12036.00	
	Description:- REMOVAL OF PSC/Wooden SLEEPERS coming in the way of/route of cable trenching, signal/Location foundation/Track Crossing etc. These obstruction will be removed by contractor for ensuring proper execution of related works.							
68	68	100.00	Numbers	102.00	10200.00	18.00	12036.00	
	Description:- REMOVAL OF Redundant/Old Rails coming in the way of/route of cable trenching, signal/Location foundation/Track Crossing etc. These obstruction will be removed by contractor for ensuring proper execution of related works.							
69	69	30.00	Numbers	271.00	8130.00	18.00	9593.40	
	Description:- FIXING OF "C" Channel Clamps on Girders along with proper coupling of GI/DWC pipes. The work will be executed as per instruction of site incharge and site incharge may take decision as per site condition. All the fixtures, nut bolts, tolls required to fix the channel will be provided by Contractor. Proper safety equipment like Helmet, Retroreflective jacket and whistle, flag is to be made available during execution of work.							
70	70	4.00	Numbers	379.00	1516.00	18.00	1788.88	
	Description:- Making an entrance for new cable in old existing location, Casting concreting and curing of foundation and restoring it to old position by perfect masonry/concreting work. Contractor will ensure that cable entered in Location Box is properly protected.							
71	71	460.00	Metre	2175.00	1000500.00	18.00	1180590.00	
	Description:- Horizontal boring of cable duct of minimum 2.0 Mtr depth along with laying of 120mm HDPE pipe for track crossing with minimum depth reckoned from bottom of the rail/Road crossing with minimum depth reckoned from ground level. The work shall be done as per extant practice & instructions of site engineer. Preparation of site for Horizontal Boring shall be carried out in presence of Railway Representative. HDPE will be supplied by Contractor at his own cost. Note:- Contractor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable.							
72	72	100.00	Metre	1497.00	149700.00	18.00	176646.00	
	Description:- Horizontal boring of cable duct of minimum 2.0 Mtr depth along with laying of 120mm HDPE pipe for Other location with minimum depth reckoned from the ground level. The work shall be done as per extant practice & instructions of site engineer. Preparation of site for Horizontal Boring shall be carried out in presence of Railway Representative. HDPE will be supplied by Contractor at his own cost. Note:- Contractor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable - BORING upto the length of 150 mtrs. Preparation of site for Horizontal Boring shall be carried out in presence of Railway Representative.							
73	73	200.00	Metre	1905.00	381000.00	18.00	449580.00	
	Description:- Horizontal boring of cable duct of minimum 2.0 Mtr depth along with laying of 120mm HDPE pipe for Other location with minimum depth reckoned from the ground level. The work shall be done as per extant practice & instructions of site engineer. Preparation of site for Horizontal Boring shall be carried out in presence of Railway Representative. HDPE will be supplied by Contractor at his own cost. Note:- Contractor shall provide all material required for boring and adequate nos. of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable - BORING beyond of 150mtrs. Preparation of site for Horizontal Boring shall be carried out in presence of Railway Representative.							
	74	30.00	Numbers	290.00	8700.00	18.00	10266.00	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

74	Description:- Termination of Tail cable inside the point machine through bend pipe this includes preparatory work of pulling the cables, and peeling out the insulation, dressing and lacing after termination etc., pulling of tail cable as per circuit requirement inside point machine through bend pipe, termination of cables on terminal blocks as per instruction of site supervisor the cable shall be entered in such a way that, armouring shall protect the cable near sharp edge of entry point and armouring shall be clamped between pipe fixing bracket and boy of point machine.						
75	75	10.00	Numbers	4102.00	41020.00	18.00	48403.60
	Description:- Shifting of existing full location boxes coming in the alignment of doubling. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location box horizontally opposite to railway track up to 0.5 to 1.0 mtr. This includes losing of existing cable coils without any damage. The excavated soil shall be back filled after shifting of Location Boxes. Location box along with its foundation shall be shifted by push method with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge at site. Any minor repairs in foundation due to patching shall also be carried out by contractor as per instruction of Engineer incharge. The work may affect train working hence the work shall be done as per margin only or during traffic block only.						
76	76	5.00	Numbers	3304.00	16520.00	18.00	19493.60
	Description:- Shifting of existing Half location boxes coming in the alignment of doubling. The work includes losing & removal of soil around location boxes by excavating soil around foundation, making of pit for shifting of location box horizontally opposite to railway track up to 0.5 to 1.0 mtr. This includes losing of existing cable coils without any damage. The excavated soil shall be back filled after shifting of Location Boxes. Location box along with its foundation shall be shifted by push method with the help of jacks or by crane by contractors own expenditure under instructions of engineer in-charge at site. Any minor repairs in foundation due to patching shall also be carried out by contractor as per instruction of Engineer incharge. The work may affect train working hence the work shall be done as per margin only or during traffic block only.						
77	77	10.00	Numbers	357.00	3570.00	18.00	4212.60
	Description:- "Transferring of signalling/Telecom cables from existing location box to New location box. The work include breaking/dismantling of existing foundation of locations, excavating and removing / segregating coils of this cables which may be of about 10 mtr in length. These cables are then to be disconnected and removed from the existing locations one by one as per the instructions and under the supervision of railway staff present at site. The cable is then to be inserted and terminated in new location box. The item includes neatly dressing of cables marking wiring tree etc. The material required for dressing / lacing will be arranged by contractor at its own cost. The work is required to be done systematically and with due precaution during the night block of 2.00 - 2.30 hrs each or within the time that may be allowed. The excavation work to be done carefully without damaging the cables to avoid undue failures. (Termination charges will be given separately) Note: Proportionate payment will be made if cable is of other length. 2/6/12/19/24/30 core signalling cable/4 or 6 Quad/PIJF/Any signalling/Telecom Cable (One no. unit = One cable of 10 m length) "						
78	78	6000.00	Metre	29.00	174000.00	18.00	205320.00
	Description:- Laying of RCC half round cement pipe of approximate size (150/300 mm dia X 2 Meter length) inside the trench after laying of cable. Pipes shall be placed as per directives of engineer.						
79	79	1.00	Lot	37275.00	37275.00	18.00	43984.50
	Description:- Painting two coats of synthetic enamel paint over one coat of Red Oxide primer after scrapping and cleaning of the surface wherever necessary with contractor own supply of primer and paints over all outdoor gears including lifting barrier, axlecounter, ground frame, point machine, location boxes, signal post, unit, track circuits etc The work shall be done as per extant practice on C Rly & the instructions of Rly engineer at site. (Paints to be used shall conform to relevant IS spec.). This includes lettering / Numbering Termination particulars, equipment names etc. legibly and neatly inside and outside surface of units, boxes etc.- for Big stations.						
80	80	50.00	Numbers	360.00	18000.00	18.00	21240.00
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. i) Apparatus Cases Full size.						
81	81	20.00	Numbers	265.00	5300.00	18.00	6254.00
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.ii) Apparatus Cases Half size.						

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

82	82	20.00	Numbers	594.00	11880.00	18.00	14018.40	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. iii) Main signal post with signal Units, Surface base and complete fittings as per Centre Railways standard practice.							
83	83	20.00	Numbers	141.00	2820.00	18.00	3327.60	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. iv) Shunt signal post with signal unit, surface base as per central Railway's Standard Practice.							
84	84	120.00	Numbers	69.00	8280.00	18.00	9770.40	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. v) Track lead Junction Box. (Black enamel outside only)							
85	85	30.00	Numbers	122.00	3660.00	18.00	4318.80	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer.vi) Point Machine with ground connections complete vi) (Point Machine with Black enamel only outside and ground connections with Red Oxide)							
86	86	6.00	Numbers	87.00	522.00	18.00	615.96	
	Description:- Painting two coats of synthetic enamel paint over one coat of primer on the following after scrapping and cleaning of the surface wherever necessary with contractor own supply of paints. Wherever required contractor shall apply coating of epoxy paint also as per instructions of site-in-charge. Epoxy will be supplied by Railways. NOTE:- The paint and primer should be from M/s Asian paints Co. Ltd.,. The paints will be primer (IS 5660 of 1970) the Aluminium synthetic black enamel (IS 2932 of 1974) brilliant white and yellow Painting two coats of enamel paint over one coat of primer. vii) Axle counter devices.							
87	87	500.00	Numbers	47.00	23500.00	18.00	27730.00	
	Description:- Lettering / Numbering of Signals, Point Machine, Track Lead junction Boxes, Block joints, Apparatus Cases etc.(each item to be taken as One Unit) This work will be carried out as per the standard practice being followed in Central Railway.							
88	88	50.00	Numbers	220.00	11000.00	18.00	12980.00	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. a) Full Case.							
89	89	20.00	Numbers	121.00	2420.00	18.00	2855.60	
	Description:- Lettering / Numbering Termination particulars, equipments names etc., legibly and neatly inside location boxes. b) Half Case.							
90	90	1.00	Lot	25736.00	25736.00	18.00	30368.48	
	Description:- Installation Testing and Commissioning of Fire Detection, Aspiration including flame sensor, LHS Cable flame sensor aspiration type smoke sensor as per RDSO SPN No.RDSO/SPN/217/2018 Version No.: 2.0. This includes Control module for the Control Unit, Monitor Module for the Control Unit. LHS Interface should be a microprocessor based start point device that communicates between LHS Cable and Control Unit should be an intelligent device that will monitor LHS cable for continuity and over temperature fire signatures. This also includes supply, Installation, Testing and Commissioning of Integrated Remote Monitoring System Software for complete as per specifications, for integrating, Fire Alarm System, VESDA System for monitoring at Division head quarter.							
91	91	1.00	Lot	49866.00	49866.00	18.00	58841.88	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

91	Description:- Releasing of lever frame, old location boxes, signal posts, equipment inside the location boxes, lifting barrier, rodding run, cranks, compensators, relays and relay racks, power equipments etc as applicable including breaking of foundation etc as per the instruction of Rly engineer at site & their transportation to SSE incharge at nominated depot.							
92	92	1.00	Numbers	1181.00	1181.00	18.00	1393.58	
92	Description:- Dismantling/Releasing of the existing outdoor signalling items such as CLS unit with posts alongwith base, lever frames (5 levers set), battery box with equipments, location box with equipments, block instruments, point machines, mechanical point, AFTC/DAC, Relay rack, CT Rack alongwith Relay rack. IDF with all accessories. All these unit will be counted as one no. along with their accessories. This includes the cost of transportation of released material from site to Railway scrap Depot. (Unit Numbers = Per Signal/Point/Loc. Box/ Relay Rack)							
93	93	10.00	Location Box	1406.00	14060.00	18.00	16590.80	
93	Description:- Releasing of cables from old location boxes and taking it into new location boxes. This includes excavating the earth to release the cables. From old location box for taking it into new location. This also includes releasing the old location box and bringing it to nearest station/ central cabin.							
94	94	20.00	Goomti days	319.00	6380.00	18.00	7528.40	
94	Description:- Provision of temporary Goomty of 3X3X2.5 mtr on hire for NI working made up of waterproof tent with provision of 1 table, 1 chair and two incandescent lamps. (Electrical connection will be provided by Rlys.)							
95	95	6000.00	Numbers	49.00	294000.00	18.00	346920.00	
95	Description:- Transportation of signaling material/equipments including loading and unloading in 10MT vehicle, anywhere to anywhere, and stacking at destination as per instructions of SSE in-charge as per inventory. For carrying heavy materials like cable drums, DG set, Electrical lifting barrier pedestal, IPS, Batteries, Point machine etc. (Unit Numbers = Per Ton/ Per KM)							
96	96	6000.00	Numbers	4.00	24000.00	18.00	28320.00	
96	Description:- Loading, un-loading & transportation of material from the stores of SSE(SIG) depot or any other nominated place & vice-versa. (Unit Numbers = Per Ton/ Per KM)							
97	97	10.00	Numbers	830.00	8300.00	18.00	9794.00	
97	Description:- Installation of Eqpt. (Relays, resistance, chargers batteries etc. as applicable) & wiring of the same in apparatus cases as per location diagrams & circuit diagrams, as per Instruction of site incharge and practice. Half Case							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () C-Supply, Installation, Testing & commissioning of Indoor & Outdoor equipment's and Provision of Electronic Interlocking at Sainagar Shirdi Station in connection with provision of 5 stabling line in Pune Division of Central Railway.							3693954.47	Above/ Below/Par
1	1	2.00	Numbers	1642226.17	3284452.34	AT Par	3284452.34	
1	Description:- SMPS based integrated Power Supply system confirming to RDSO Spec. No. RDSO/SPN/165/2012 with latest amendment for Panel Interlocking Fig. JN STN . As per C. Rly. Drg. No. SK/793 with latest correction if any.Inspection by RDSO)							
2	2	1.00	Numbers	25024.85	25024.85	AT Par	25024.85	
2	Description:- Laserz printer HP A3 size model no Pro MEP-M435NW or latest model of HP Inspection by consignee)							
3	3	1.00	Numbers	147868.77	147868.77	AT Par	147868.77	
3	Description:- Supply of design set for circuits as per annexure.V Inspection by consignee)							
4	4	365.00	Man-Days	622.47	227201.55	AT Par	227201.55	
4	Description:- Provision of man power in connection of transporting of materials in emergency during execution of work ,Phase working during Pre NI and NI							
5	5	1.00	Numbers	9406.96	9406.96	AT Par	9406.96	
5	Description:- Supply of Digital Multimeter Model No DM 4750D of FLUKE or similar make Inspection by consignee)							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () D1-Supply, Installation, Testing & commissioning of Indoor & Outdoor equipment's and Provision of Electronic Interlocking at Sainagar Shirdi Station in connection with provision of 5 stabling line in Pune Division of Central Railway.							1374165.46	Above/ Below/Par
	1	1.00	Set	11963.00	11963.00	18.00	14116.34	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

1								
	Description:-	Supply and Installation of Lightening & Surge protection device, Single phase + neutral (housed in a suitable impact resistance box) for providing B class protection as per RDSO spec No. RDSO/SPN/165/2012 (Ver 3.0)Inspection by RDSO)						
2		1.00	Set	9200.00	9200.00	18.00	10856.00	
	Description:-	Supply and Installation of Lightening & Surge protection device, Single phase + neutral (housed in a suitable impact resistance box) for providing C class protection as per RDSO spec No. RDSO/SPN/165/2012 (Ver 3.0)Inspection by RDSO)						
3		5.00	Set	15671.00	78355.00	18.00	92458.90	
	Description:-	Maintenance Free Earth as per RDSO/SPN/197/2008 or latest consisting of : 1) Copper bond steel electrode 3 Mtr long 17mm dia with copper bonding thickness of min. 250micron & UL listed & marked-01 No. (2) Earth enhancement compound RDSO Approved in sealed bag of 10 kgs - 03 No. (3) Copper strip 150 x 25 x 6mm - 02 No (4) Copper Strip 300 x 25 x 6mm- 01 No (5) 35 Sqmm Copper Cable to connect earth electrode to MEEB - 15Mtr Approx. Inspection by RDSO)						
4		10.00	Numbers	2710.00	27100.00	18.00	31978.00	
	Description:-	Supply of Thermo-Shrink cable joining kit (Reinforced) TSF-2 type generally confirming to RDSO specification RDSO/SPN/TC/57/2015 Rev 1 with modified kit contents as per CSTE's Specification No.:CR/SPN/TC/57 (A)/2015 Dt: 06.01.2015 (Table-A) to be suitable for jointing both 10/20/50 pair PIJF and 4/6 Quad cables alongwith sub-kit (Table-B) for armour continuity.Inspection by RDSO)						
5		1.00	Set	20249.00	20249.00	18.00	23893.82	
	Description:-	Supply of VHF 25W transreceiver (synthesised) set complete consisting of Analog set as per CR specification.Inspection by RDSO)						
6		10.00	Kilometre	63534.00	635340.00	18.00	749701.20	
	Description:-	Supply of Permanently Lubricated HDPE Telecom duct of size 50/42 mm and accessories as per latest Specification TEC GR No. GR/TX/CDS-008/03March 11 with latest amendment" for OFC cable of size 24 fibre armoured in length of 1000 mtr/roll. Duct to be supplied from TEC approved sources.Inspection by CONSIGNEE)						
7		10.00	Numbers	3113.00	31130.00	18.00	36733.40	
	Description:-	"Supply of 24 fibre straight joint closure (SJC) complete with all accessories as per RDSO Spec. No. RDSO/SPN/TC/68/2014 Revision 1.0 and as per or TEC Spec. G/OJC/02/02 Sept 2003 or latest of Raychem make model FOSC 400 B4 24F or TVS ICS make model 1500-L1 83-XX or Birla VXL make model VT-200 or 3M make model 2179 CD.Inspection by RDSO)"						
8		5.00	Numbers	2803.00	14015.00	18.00	16537.70	
	Description:-	Supply and installation of 20 pair CT box . (Inspection by Consignee)						
9		10.00	Numbers	1281.00	12810.00	18.00	15115.80	
	Description:-	Making of thermoshrink straight through/derivation/ transformer /PIJF cable joint for underground jelly filled cable 6 quad/4 quad/20 pair 10 pair etc. PIJF cable as per the instruction of Rly engineer at site.						
10		100.00	Hour	1191.00	119100.00	18.00	140538.00	
	Description:-	Providing Road Breaker/concrete breaker/boulder or rock breaker with compressor & Jack Hammer for Railway work such as cutting & dismantling of road concrete/Brick pucca structure (RCC/Steel section) including contractors fuel, driver and all other charges completed as directed by Engineer in charge						
11		1.00	Numbers	7155.00	7155.00	18.00	8442.90	
	Description:-	Instillation testing & commissioning of the 25 W VHF system including the erection of mast, antenna, charging of the battery with all contractor's materials.						
12		10.00	Kilometre	5462.00	54620.00	18.00	64451.60	
	Description:-	Laying of HDPE duct in trench and its protective work as per direction of site engineer.						
13		10.00	Kilometre	11607.00	116070.00	18.00	136962.60	
	Description:-	Blowing/Drawing of OFC cable in HDPE/DWC duct and protective work, as per direction of site engineer.						
14		5.00	Numbers	5488.00	27440.00	18.00	32379.20	
	Description:-	Splicing (Jointing 2X24 F OFC) and testing of 24 fibre OF Cable and making the splice joint as per direction of site engineer with contractors own splicing machine & tools. Splice loss of each fibre should be less than or equal to 0.05db splice reflectance should be better than 60 db.						
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () D2-Supply, Installation, Testing & commissioning of Indoor & Outdoor equipment's and Provision of Electronic Interlocking at Sainagar Shirdi Station in connection with provision of 5 stabling line in Pune Division of Central Railway.							7735894.91	Above/ Below/P ar
	1	2.00	Numbers	24152.46	48304.92	AT Par	48304.92	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

1	Description:- Installation of IP MPLS Router and swithes with power distribution panel and all accessories in the Rack (19" 42 U), DDF, aluminium runway ladder, patchcord etc and their testing and commissioning . This includes termination of all E1's on DDF, connection of pigtails, optical patch cords and 48V bus to the IP-MPLS equipment including supply of wires and connectors. It also include propermounting of rack, provision of Aluminium runway ladder, casing and capping and conduit pipe as per requirement at each station, other materials from stores supplied by railways for installation. (Conduit pipe/casing and capping, aluminium runway ladder and all other miscellaneous materials should be supplied by the contractor.							
2	2	1.00	Numbers	16409.34	16409.34	AT Par	16409.34	
	Description:- Installation, wiring and testing of battery sets and battery chargers for optic fiber circuits. This includes installation of AC and DC power supply distribution board with MCB's of suitable rating, cable ladder, wiring of external alarm contacts, fixing arrangements for battery and charger in the equipment room with 25 sq. mm multistarnd core copper cable PVC insulated from battery charger to battery with suitable copper lugs crimped /soldered to it, 16 sq. mm multistarnd single core copper cable PVC insulated from battery cahrger to power distribution panelin the rack with suitable copper lugs crimped /soldered to it. Connection from battery charger body and battery +ve terminal to earth terminal by 16 sq. mm multistrand single core copper cable PVC insulated seperately with suitable copper lugs crimped /soldered to it and extension of AC 230 V power supply wiring through PVC pipe with 6 sq mm cu.wire for phase & neutral and 1 sqmm cu. wire for earth to the 19" rack (Copper cables , 20A metal clad with MCB for AC supply to fix in the wall, conduits and other miscellaneous materials required for the work should be supplied by the contractor. This work alsoincludes transportation of materials from stores/supplied by railways for installation.							
3	3	1.00	Station	166267.15	166267.15	AT Par	166267.15	
	Description:- Installation, testing and Final commissioning of equipments at each station for all the equipments conforming with approved system design including end to end testing for realization optical fiber system. This also includes supply of all as made documents for the entiresection(six copies) plus technical , maintenance and installation manuals for IPMPLS, NMS, charger and power suply unit with OEM certificate. Station=per staion.							
4	4	2.00	Man-Week	18114.34	36228.68	AT Par	36228.68	
	Description:- Training of Railway staff and officer on IPMPLS at the factory premises/ railway site of manufacturer of IPMPLS equipment (or) at a reputed training institution as approved by railway executive incharge. (Travel expenses will be borne by the railways).							
5	5	5.00	Numbers	157.36	786.80	AT Par	786.80	
	Description:- Fixing of Krone DPs & termination of PIJF cable in Krone DP duly mounted on good quality Teakwood/Hylum board and GI / good quality PVC pipe at the entry of Krone DP as decided by site incharge.							
6	6	1.00	Job	1995.65	1995.65	AT Par	1995.65	
	Description:- Installation, wiring, testing & commissioning of lightening current arrestor (Class B & C) as mentioned above or as per instruction of Railway Engineer .							
7	7	3.00	Numbers	116979.62	350938.86	AT Par	350938.86	
	Description:- Supply & installation of Fiber Distribution management system as per RDSO Specification No.RDSO/SPN/TC- 37-2000(Ver.3) with latest Amendments as on the date of opening of tender. (It includes the supply of 19" rack with mounting arrangement)(Inspection by RDSO)							
8	8	10.00	Numbers	3481.24	34812.40	AT Par	34812.40	
	Description:- "Supply of Thermo shrink 2T jointing kits for jointing underground 0.9 mm dia. conductor 6 quad cable as per specification IRS:TC 77-2012 Rev.3, Amd.3 or latest. With RDSO inspection. With RDSO approved firms. (Inspection by RDSO)"							
9	9	10.00	Pair	923.09	9230.90	AT Par	9230.90	
	Description:- Supply of 1 T VF Transformer 470:1120 ohms.(Inspection by Consignee)							
10	10	20.00	Numbers	497.81	9956.20	AT Par	9956.20	
	Description:- Supply of Push button telephone sutiable for connecting with way side equipment and the system above as per TEC specification no.GR/TEL-02/04 sept.and from DOT/TECH approved firms. 2002 with latest ammendements model Binatone concept 700/Beetel/Panasonic.(Inspection by Consignee)							
11	11	2.00	Numbers	5721.82	11443.64	AT Par	11443.64	
	Description:- Supply of Fixed Wireless Telephone supporting - band GSM, 2G, 3G, 4G Volte with 2 way speaker consisting of LCD screen, High - performance detachable 'TNC' Antenna, Speed Dial, Supports 4G Volte calls, and FM radio, Direct Memory Keys (M1, M2, M3, M4) with 08 Programmable speed dial keys, rechargeable battery, Adaptor with Surge Protection Make- Betel or Similar.Inspection by CONSIGNEE)							
12	12	200.00	Metre	54.45	10890.00	AT Par	10890.00	
	Description:- Supply of paramite Battery wire, 51 strands each strand size of 0.75 mm dia in RED,BLACK & GREEN Colour. i) RED (Inspection by Consignee)							
13	13	200.00	Metre	54.45	10890.00	AT Par	10890.00	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

14	14	200.00	Metre	54.45	10890.00	AT Par	10890.00	
	Description:- Supply of paramite Battery wire, 51 strands each strand size of 0.75 mm dia in RED,BLACK & GREEN Colour.ii) Black (Inspection by Consignee)							
15	15	2400.00	Metre	19.52	46848.00	AT Par	46848.00	
	Description:- Supply of paramite Battery wire, 51 strands each strand size of 0.75 mm dia in RED,BLACK & GREEN Colour.iii) GREEN (Inspection by Consignee)							
16	16	10.00	Numbers	1603.14	16031.40	AT Par	16031.40	
	Description:- Supply of CAT 6 Cable with identifications marking on cable at regular interval of make: Molex or D-Link ,network, krone or similar. (Inspection by Consignee)							
17	17	2.00	Numbers	1005.19	2010.38	AT Par	2010.38	
	Description:- Supply of KRONE DP 10 pairs in metal box with locking arrangement as per tender document. Conforming to Tender Document Chapter VI. (Inspection by Consignee)							
18	18	100.00	Metre	37.99	3799.00	AT Par	3799.00	
	Description:- Supply and fixing of 25 mm dia. PVC channel, with cover and running switch board cable through them. make Precision or Presto plat or presto teak or similar. (Inspection by Consignee)							
19	19	2.00	Numbers	1353.96	2707.92	AT Par	2707.92	
	Description:- Supply of KRONE DP 20 pairs in metal box with locking arrangement & krone module for 20 pair (Spec no. G/CTN-10/03 june 2005) as per tender document. Conforming to Tender Document Chapter VI. (Inspection by Consignee)							
20	20	100.00	Metre	129.11	12911.00	AT Par	12911.00	
	Description:- Supply & fixing size 50 x 50 mm of PVC Casing capping on wall with all accessories . This includes laying of telecom cables inside the installed PVC casing of ISI make or approved. (Inspection by Consignee)							
21	21	2.00	Numbers	7089.75	14179.50	AT Par	14179.50	
	Description:- Supply, fixing & cable termination of 100 pair Krone DP box suitable for external/Internal use conforming to tender document Chapter VI. (Inspection by Consignee)							
22	22	2.00	Numbers	50188.66	100377.32	AT Par	100377.32	
	Description:- Supply of covered 19" racks of size 2200mm X 600mm X600mm (WQ/VERO President /RITTAL/APC make.) compleate with all fittings including DC fans (48V) -2Nos. , Seperator sheet /Plate to keep testing equipments-1 no and AC power distribution pannel (horizontal fitting) with power socket with fuse/MCB protection (minimum 6 nos. of 230V-15A/5A combined) and compatibility with all equipment conforming to Din-41494 or equivalent EIA/ISO/EN standard manufacturer must certify that products are complied with DIN-41494 or equivalent EIA/ISO/EN/CEA/UL standards. (Inspection by Consignee)							
23	23	3.00	Numbers	13067.57	39202.71	AT Par	39202.71	
	Description:- Supply of Composite rack 19" standard reputed make with fixing arrangement for mounting 2 wire DTMF way side equipment. (Inspection by Consignee)							
24	24	2.00	Pair	7074.10	14148.20	AT Par	14148.20	
	Description:- SUPPLY of LAN extender as per RDSO specification no. RDSO/SPN /TC/82/2020 rev2.0 similar to make CYGNUS/TEAM Engineer/NOMUS. (Inspection by Consignee)							
25	25	1.00	Numbers	122570.93	122570.93	AT Par	122570.93	
	Description:- Supply of SMPS based 48V (2+1) FR/FC module , 25 AMP single phase 230V, AC oprrated battery charger for telecom use as per RDSO/SPN /TC/102/2013 ver 0.0 with latest amendment, in 12.5 Amp with Automatic switching between the module suitable for set. It shall be equiped with surge and lightning protection of class B and Class C alongwith inspectio and service manual. (Inspection by RDSO)							
26	26	1.00	Set	105836.54	105836.54	AT Par	105836.54	
	Description:- Supply of Maintenance free VRLA Batteries sets of 48 Volt 200 AH Capacity as per RDSO Specs IRS:S.93/96(A) with amendment .01 or later . Each battery set shall be of 24 Batteries of 2 Volt 200 AH Capacity .Make : Exide, Amaron, Okaya, Luminous, Mrotek, , Quanta, Amar Raja,Su-Kam,SF Sonic. (Inspection by RITES)							
	27	4.00	Pair	153400.00	613600.00	AT Par	613600.00	

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

27	Description:- Supply and Installation of CYGNUS 845-4P MULTIPLE MEDIA AUTO CHANGEOVER CONVERTER-4 PORT, for simultaneously interconnecting Digital Axle Converter, UFSBI, Block Phone etc. across a Block Section/ IBs over multiple media. Product has the following features: a)Two 120 ohm E1 Main Links with RJ45 connector, having (1+1) hot standby facility b)Two optical Main Links with (1+1) hot standby dual core path and single core path) having 20 Km driving distance. c)Four V.21N.23 (E&M) 2-wire/4-wire user interface with auto changeover to Quad links in case of failure of all Main Links. Each user port is configurable as 2W or 4W without any restriction. d)Unit supports power OFF fail safe mechanism. In case the unit is switched OFF, all analog user devices are bypassed to the Quad link automatically. - e)Unit supports four numbers of Potential free contacts which can be linked with data logger/RTU for E1 Status, Optical status & Power Supply status. ' f)Unit supports front panel resettable audible buzzer in case of mainlink fails (optical or E1). g)Unit supports front panel LED indicators for Quad health status, E1 dual, Optical dual path. h)Unit %B7 has dual hot standby DC power supply having 24VDC/48VDC i)"Unit is 1U height with 19 inch rack mountable-facility j)Unit supports operating temperature from -5 degree Celsius to +55 degree Celsius. Accepted Make/Brand:-CYGNUS or Team-Link or Similar. (Inspection by Consignee)							
28	28	1.00	Set	434266.27	434266.27	AT Par	434266.27	Description:- Supply of Standard 19" Rack Mountable LER(Label Edge Router) , IP- MPLS Router with Redundant DC power feed -48V DC nominal, equipped with interfaces: 2 x 10G (optical) SFP+ Ports along with 2 Nos of 40 Kms 10G SFP+ LC Modules, 4 x 1GbE (Optical) interface along with 4 Nos of 1GbE Single Mode Bi-directional SFP (10KMs) Modules and 4 x 1GbE (Copper) interfaces & Modules and slot for 16 x E1 (G.703), Mounting kit with all necessary accessories & Software, Perpetual Licenses. With options of either upgrading to have a total of 32xE1 (G.703) ports by way of adding / replacing interface cards or should be possible to add 2xSTM-1 (channelized, optical) ports. As Per RDSO Document No. STT/TAN/IP-MPLS/2020 Version 01 or latest. Inspection : RDSO
29	29	2.00	Numbers	66484.59	132969.18	AT Par	132969.18	Description:- Supply of 2 x 10G Adapter Interface without 10G SFP + Modules for LER Routers. (Inspection by RDSO)
30	30	2.00	Numbers	69808.83	139617.66	AT Par	139617.66	Description:- Supply of 8 x 1G Adapter Interface (any combination: one nos of 8 x 1G or two nos of 4 x 1G) without SFP for LER Routers. Inspection RDSO.
31	31	2.00	Numbers	1385.10	2770.20	AT Par	2770.20	Description:- 1G SFP Module with 10 Km range for above Routers. Inspection RDSO.
32	32	2.00	Numbers	119118.24	238236.48	AT Par	238236.48	Description:- "Supply and installation of 16 port E1 Card along with Patch panel/Krone Module and wiring for Routers with all accessories etc. Inspection RDSO."
33	33	6.00	Numbers	115021.13	690126.78	AT Par	690126.78	Description:- 10G SFP+ Module with 40 Km range for above Routers. Inspection RDSO.
34	34	1.00	Set	1967626.01	1967626.01	AT Par	1967626.01	Description:- Supply of Standard 19" Rack Mountable Modular Chassis LSR (Label Switch Router) IP- MPLS Router with Redundant DC power feed -48V DC nominal Redundant Controller Card, equipped with interfaces: 8 x 10G (optical) SFP+ Ports along with 8 Nos of 40 Kms 10 G SFP+ Modules, Mounting Kit with all necessary accessories & Software, Perpetual Licenses. The system should have all the functional & technical requirements of LSR including General specification architecture protocol supported, quality of service, security, performance, certificates & environment of standards of RDSO TAN document No. STT/TAN/IPMPLS/2020. As Per RDSO Document No. STT/TAN/IP-MPLS/2020 Version 01 or latest. - Inspection RDSO.
35	35	1.00	Set	523414.89	523414.89	AT Par	523414.89	Description:- "Supply and Installation of 10 KVA UPS, 02 Module (N+1) with a total of 2 hrs back UP . (Battery to be supplied by firm) .(Detailed technical specification as per chapter III). Make - APC, Microtek, Luminous, Liebert, Numeric or similar. (Inspection by Rites)"
36	36	40.00	Number-Month	44840.00	1793600.00	AT Par	1793600.00	Description:- Supply, installation, testing and commissioning of GPS digital clocks as per RDSO/SPN/TC@47>47@2008 Inspection by RDSO)

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Important : All documents uploaded and remarks / confirmation entered by the bidders against any eligibility condition shall be opened as part of technical bid only
--

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Financial Eligibility Criteria: Financial Eligibility Criteria: Shall be as per Para 10.2 of Advance Correction Slip No. 1 dtd 14-07-2022 of GCC April - 2022. The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderer shall submit requisite information as per Annexure - VIB, along with copies of Audited Balance Sheet duly certified by the Chartered Accountant / Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Technical Eligibility Criteria - Shall be as per Para 10.1 of GCC April - 2022. a)The tenderer must have successfully completed or substantially completed any of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, OR Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, OR One similar work each costing not less than the amount equal to 60% of advertised value of the tender. b)In case of composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges - substructure, superstructure etc.), tenderer must have successfully completedor substantially completedany of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, OR Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, OR One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender. Note for b(i) : Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. (b) (ii) In such cases, what constitutes a component in a composite work shall be clearly predefined with estimated tender cost of it, as part of the tender documents without any ambiguity. (b) (iii) To evaluate the technical eligibility of tenderer, only components of work as stipulated in tender documents for evaluation of technical eligibility, shall be considered. The scope of work covered in other remaining components shall be either executed by tenderer himself if he has work experience as mentioned in clause 7 (a) (ii) of Part-II of GCC or through subcontractor fulfilling the requirements as per clause 7 of Part-II of GCC or jointly i.e., partly himself and remaining through subcontractor, with prior approval of Chief Engineer in writing	No	No	Allowed (Mandatory)

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

2	However, if required in tender documents by way of Special Conditions, a formal agreement duly notarised, legally enforceable in the court of law, shall be executed by the main contractor with the subcontractor for the component(s) of work proposed to be executed by the subcontractor(s), and shall be submitted along with the offer for considering subletting of that scope of work towards fulfilment of technical eligibility. Such subcontractor must fulfill technical eligibility criteria as follows: The subcontractor shall have successfully completed at least one work similar to work proposed for subcontract, costing not less than 35% value of work to be subletted, in last 5 years, ending last day of month previous to the one in which tender is invited through a works contract. In case after award of contract or during execution of work it becomes necessary for contractor to change subcontractor, the same shall be done with subcontractor(s) fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract, with prior approval of Chief Engineer in writing. Note for Item 1.1: Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organization, work experience certificate issued by Public listed company having average annual turnover of Rs. 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate. NOTE: The definition of "Similar Nature of Work" for this work is as under:- "Any Indoor or combined Indoor & Outdoor Signalling work including Design, Supply, Installation testing and commissioning of Electronic interlocking system for passenger carrying lines." OR "Any Indoor or combined Indoor & Outdoor Signaling work including Supply, Installation testing and commissioning of relay interlocking (RRI/PI) system/ABS/IBS for passenger carrying lines."	No	No	Allowed (Mandatory)
---	---	----	----	------------------------

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

3	•Works executed for Central /State Govt. /Semi Govt. organizations Authorities, PSUs and Govt. of India Undertaking, will be considered for assessing the suitability of tenderers. Authentic certificates from the concerned Government authorities shall be produced by the tenderer(s) to this effect, along with the tender offer. •The subcontractor engaged by main contractor / concessionaires / SPVs who executed work for a Central /State Govt. /Semi Govt. Organization /Authorities /PSUs and Govt. of India undertakings will be considered for assessing the suitability, provided authentic certificate is issued by the concerned Government Authorities., subject to followings : (i)For Sub -Contractor of Concessionaires /SPV's, the similar work given by the Concessionaires /SPV's to the Sub-contractor will be considered as completed single similar work for eligibility. (ii) For all other Sub-Contractors: (a)For linear works of Railways, Roads, Canals and Dams only, similar work given to the subcontractor will be considered as completed single similar work for eligibility. (b)For all other contractors, works given to the subcontractor will be considered for eligibility only if the entire work awarded to the main contractor is physically completed and subcontractor completes the similar work allotted to him. •Total value of similar nature of work completed during the qualifying period, and not the payments received within the qualifying period alone, shall be considered. •In case, the final bill of the similar nature of work has not been passed and final measurement has not been recorded, the paid amount including statutory deductions will be considered. If the final measurements have been recorded and work has been completed with negative variation then also the paid amount including statutory deductions will be considered. However, if final measurements have been recorded and work has been completed with positive variation but variation has not been sanctioned, original agreement value or last sanctioned agreement value, whichever is lower shall be considered for judging eligibility. •Value of a completed work done by a member in all earlier Partnership firm or JV firm shall be reckoned only to the extent of the concerned member's share in that Partnership firm /JV firm for the purpose of satisfying his compliance of the above mentioned condition, in the tender consideration. •Tenderers should submit clear certificate(s) giving name of the contractor, PAN No., description of work, organization for whom executed agreement no. & date, approximate value of contract at the time of award, date of schedule completion of work, date of actual start, date of actual completion (as recorded in MB), date of final measurement, date of final bill and final value of contract & working report issued by an officer of rank not below JAG in - charge of work, separate certificate should be submitted for every single similar work. Certificates must also contain name, postal address & telephone / FAX No. of issuing authority.	No	No	Allowed (Mandatory)
---	--	----	----	------------------------

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Important All documents uploaded and remarks / confirmation entered by the bidders against any : compliance condition shall be opened as part of technical bid only.

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender Document.	No	No	Allowed (Mandatory)
2	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender Document.	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	As per Tender Document.	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	01-2026Tenderdocument.pdf	Tender Document
2	GCC_April-2022_2022_CE-I_CT_GCC-2022_POLICY.pdf	GCC April 2022
3	AdvanceCorrectionSlipNo1ofGCCApril2022.pdf	GCC Correction Slip No 1
4	2022_12_13ACSN0_2GCC.pdf	GCC Correction Slip No 2
5	2023_04_26ACS-3GCC.pdf	GCC Correction Slip No 3
6	2023_04_26ACS-4GCC.pdf	GCC Correction Slip No 4
7	2023_10_20ACS-5GCC.pdf	GCC Correction Slip No 5
8	2023_12_21ACS-6GCC.pdf	GCC Correction Slip No 6
9	2024_09_25ACS-7GCC.pdf	GCC Correction Slip No 7
10	2022-CE-I-CT-GCC-2022-POLICY8dated.20.12.2024.pdf	GCC Correction Slip No 8
11	GCCACS9.pdf	GCC Correction Slip No 9

**DSTE-C-BSL-S AND T/CENTRAL RLY
TENDER DOCUMENT**

Tender No: SUR-NC-CR-SNT-C-S-01-2026

Closing Date/Time: 03/02/2026 15:00

12	CorrectionSlipGCC10OK.pdf	GCC Correction Slip No 10
13	SAINAGARSHIRDIUPDATEDADVANCESIPPRINT.pdf	Tentative SIP
14	KAVACHpolicyLetter.pdf	Kavach Policy Letter
15	ExemptionfromPVC.pdf	Exemption from PVC

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: SUDHANSHU MITTAL

Designation : Dy.CSTE/C/BSL