

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

Sr DSTE/AII acting for and on behalf of The President of India invites E-Tenders against Tender No **SNT-AII-33-2025-26Re-tend** Closing Date/Time 17/02/2026 15:30 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Ajmer Division:- Provision of S&T Associated work in C/W provision of a shunting neck connected with line No. 6 and an engine holding line connected with ART line on RPZ end at UDZ station in Ajmer Division NWR.(Signalling Items)		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	17/02/2026 15:30	Date Time Of Uploading Tender	22/01/2026 14:04
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	22457001.05	Tendering Section	SIG WORKS
Bidding Style	Single Rate for Tender	Bidding Unit	Above/Below/Par
Earnest Money (Rs.)	262300.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	180 Days
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	03/02/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-SOR ITEMS							8624664.15	
1	01011300	1.00	Station	175967.35	175967.35	AT Par	175967.35	
	Description:- Design, preparation & supply of drawings in computer print copies and original tracing in AUTO CAD FORMAT for Electronic Interlocking at each station. After completion of the work, the completion drawings incorporating completion details are to be supplied as per Technical Specifications given in tender document (upto 6 Line). The technical specifications are as per ANNEXURE 1.13 of SOR. Inspection: Consignee Inspection charges: None Payment terms: 100% after execution							
2	01012100	1.00	Station	3598.62	3598.62	AT Par	3598.62	
	Description:- Preparation of SWR literature in english alongwith associated mid-section interlocked gate with all corrections as per approved SWRD & approved SIP. For this all technical corrections, editing, grammatical correction etc. are to be carried out and one rough print to be given to railways for approval before printing, as required for final processing of CRS sanction. This also includes preparation of maintenance cards in format provided by Rly. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.							
3	01012200	1.00	Station	4478.18	4478.18	AT Par	4478.18	
	Description:- Translation of Station Working Rules from english to hindi and framing out in DIGLOT form (or similar software)as per extant Rly practice. The required SWR in english will be provided by the contractor and has been covered separately in item no. 1.21 of Chapter 1 of this SOR. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.							
4	01012300	8.00	Set	178.52	1428.16	AT Par	1428.16	
	Description:- Making photocopies & binding of the SWR literature in English/hindi/Diglot form as per Railway practice. Inspection: Consignee Inspection charges: None Payment terms:100% after execution.							
	01013000	60.00	Per Relay	524.10	31446.00	AT Par	31446.00	

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

5	Description:- Addition/alteration in existing relay room wiring. It includes supply of PVC insulated indoor Railway signalling cable @ 40<45@Core/40-Core) of (1/0.6) sqmm as per RDSO Spec.No.IRS/S-76/89 (Amnd.2 or latest) for wiring between relay room and SM's/Panel room & Relay room to DP in SM office for block working. This also includes supply of PVC insulated jumper wires of multi strand 16/2 mm, tinned in all colours as per RDSO Specn.No.IRS-S-76/89(Amnd.2 or latest). This item will include bringing all the power supplies from power room to respective bus bars on relay racks by using 10/6 sqmm copper flexible wire as per instructions of engineer incharge. This will include wiring between control panel and relay room if required. All wiring will be done as per standard practice of North Western Railway with neat dressing & threading. The item includes supply & wiring of tag block, fuse with bases(G-Type and ND Type) and all other related material required for complete indoor wiring in relay room. Inspection: Consignee Inspection charges: None Payment terms:100% after commissioning.						
6	03011500	150.00	Numbers	390.37	58555.50	AT Par	58555.50
	Description:- Fixing of Q series relay base plate/metal to metal relay mini group and major group base plate, laying, bunching, lacing, dressing & packeting of 60/40 core PVC indoor cable/flexible wire and termination of 60/40 core cable/flexible wire on tag block/base plate & base plates & soldering. This includes fuse wiring, bus bar looping etc. required for keeping installation ready for circuit wiring work & panel throughing work. The work shall be done as per approved plan, extant practice on NWR & the instruction of Rly. Engineer at site. Inspection authority:- Consignee Inspection charges:- None Payment Terms:- 100% after Commissioning						
7	03011400	15.00	Kg	175.27	2629.05	AT Par	2629.05
	Description:- Supply of Sealing wire used for sealing of signaling relays & equipments. Inspection authority:- Consignee Inspection charges:-None Payment Terms:- 100% after supply.						
8	04010100	2.00	Kilometre	5813.26	11626.52	AT Par	11626.52
	Description:- Supply of PVC insulated multi strand, single core copper conductor of size 16/0.2 mm (0.5sqmm) as per IS 694:2010 and RDSO Specn.No.IRS:S-76/89 (Amnd-3) or latest. Each coil should be of 100/200/500 meters length. Colour of the wire which is required will be specified by the Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
9	04010800	1.00	Kilometre	2413.22	2413.22	AT Par	2413.22
	Description:- Supply of indoor PVC jumper wire (1x 0.6 mm) of all colours as per RDSO Specn.No.IRS:S-76/89 (Amnd.3) or latest. Note: wires colours will be specified/decided by site Engineer incharge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
10	04011100	1.00	Numbers	46394.04	46394.04	AT Par	46394.04
	Description:- Supply of Powder Coated Relay Racks as per Drg.No.CSTE/ NWR/SOR/01 with scaffolding and suitable grouting arrangements. The relay racks shall be supplied & completed with scaffolding, bus bars, fuse strips, fuses (G/NDT), fuse bases, resistors, capacitors, insulators and 200-Way tag blocks with poly carbonate covers, grouting bolts, tripods etc. It includes supply of Tag Blocks as per RDSO Specn.No.IRS:S-77/2006 (Rev.1) or latest and RDSO Drg.No.SA-24751. The top of relay racks will be supported through an angle iron with one side fixed on supporting wall. Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
11	04011200	1.00	Numbers	11598.51	11598.51	AT Par	11598.51
	Description:- Erection of Powder Coated Relay Racks as per Drg.No.CSTE/ NWR/SOR/01 with scaffolding and suitable grouting arrangements. The relay racks shall be completed with scaffolding, bus bars, fuse strips, fuses (G/NDT), fuse bases, resistors, capacitors, insulators and 200-Way tag blocks with poly carbonate covers, grouting bolts, tripods etc. It includes fixing of Tag Blocks as per RDSO Specn.No.IRS:S-77/2006 (Rev.1) or latest and RDSO Drg.No.SA-24751. The top of relay racks will be supported through an angle iron with one side fixed on supporting wall. After installation of relay racks, one coat of paint will be done by contractor before fixing the fuses. Scaffolding should include 1 relay rack position as spare at every Station/ Level Crossing Gate for future expansion. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on execution						
12	04011300	1.00	Numbers	22732.41	22732.41	AT Par	22732.41
	Description:- Supply of Cable Termination(CT) racks as per Drg.No.CSTE/NWR/ SOR/02 complete along with fitting arrangements and also with arrangement for fixing four 8-way terminal strips/ Screw less terminals/ ARA terminals on each row having 16 such rows. Supply of 8 way terminal strips/ Screw less terminals / ARA terminals not covered under this item. Cable termination rack shall be Powder Coated. Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
	04011400	1.00	Numbers	8687.12	8687.12	AT Par	8687.12

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

13	Description:- Installation of Cable Termination Racks Assembly complete including wall supports, scaffolding and suitable grouting arrangements with installation of 8 way/ARA terminals /Screw less connectors, Tag blocks & other necessary accessories etc. The work shall be done as per approved plan, extant practice on NWR & the instruction of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% on commissioning.						
14	04011500	2000.00	Numbers	87.41	174820.00	AT Par	174820.00
	Description:- Supply of ARA Terminal Block (M-6) made of PBT/Poly Carbonate as per RDSO Specn.No.IRS:S-75/2006 (Rev.2) or latest and RDSO Drg.No. SA-23741A(Alt. 4) or latest. Inspection: RDSO. Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.						
15	04011600	50.00	Numbers	152.98	7649.00	AT Par	7649.00
	Description:- Supply of Cartridge Fuse Block made of PBT and as per RDSO Drg. No. SA-23748 (Alt. 4) or latest and RDSO Specn.No.IRS:S-75/2006 (Rev.2) or latest. Inspection: RDSO. Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.						
16	04011900	100.00	Numbers	54.64	5464.00	AT Par	5464.00
	Description:- Supply of round head type non-deteriorating type low voltage cartridge fuse as per RDSO Specn.No.IRS:S-78/92 or latest and Capacity - 2/4/6/10A/16A/20A Amp. (material will be supplied only from approved vendors of RDSO). Inspection: Consignee Inspection Charges: Borne by Railways. Payment Terms: 100% on supply.						
17	04012400	1.00	Kilometre	154443.58	154443.58	AT Par	154443.58
	Description:- Supply of PVC insulated Railway Signaling multi-core Indoor Cable 60core (0.6mm dia) conforming to IRS:76/89(Amd3) or latest. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
18	04012500	5000.00	Per Conductor	8.46	42300.00	AT Par	42300.00
	Description:- Termination of Outdoor Cables (Main Cables /tail cables) at both ends in location boxes, cable termination rack in relay room, station building, generator room etc. The item includes dressing of cables and wires with dressing threads as per standard practice. All material required for this item will be supplied by contractor. The outdoor cable shall be terminated in Relay Room, DG Room, ASM Room etc under supervision and instructions issued by Engg. incharge of the work. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution						
19	04012700	2.00	Kilometre	159140.52	318281.04	AT Par	318281.04
	Description:- Supply of PVC insulated Railway Signaling multi-core Indoor Cable 24 core (1 mm dia) conforming to IRS:76/89(Amd3) or latest. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
20	04012801	500.00	Numbers	54.63	27315.00	AT Par	27315.00
	Description:- Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signaling) With latest amendments. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply Supply of Disconnect Terminal Block, Screw less type, 4-wire front entry (Two in-put & Two out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3)						
21	04012802	100.00	Numbers	10.24	1024.00	AT Par	1024.00
	Description:- Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signaling) With latest amendments. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply Supply of End plate for item 4.28(i) of Chapter 4 of revised SOR 2.5mm/0.091 in thick as per site requirement.						
22	04012803	50.00	Numbers	10.24	512.00	AT Par	512.00
	Description:- Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signaling) With latest amendments. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply Supply of End Stopper for item 4.28(i) of Chapter 4 of revised SOR 10mm/0.0394 in width as per site requirement.						
	04012804	10.00	Metre	106.98	1069.80	AT Par	1069.80

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

23	Description:- Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signaling) With latest amendments. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply Supply of Carrier Rails for item 4.28(i) of Chapter 4 of revised SOR 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.						
24	04012805	100.00	Numbers	15.93	1593.00	AT Par	1593.00
24	Description:- Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signaling) With latest amendments. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply Supply of Markers strip for item 4.28(i) of Chapter 4 of revised SOR						
25	04013400	2.00	Per Unit	29277.62	58555.24	AT Par	58555.24
25	Description:- Supply of Fuse auto changeover system for Railway Signaling System as per RDSO/SPN/209/2012 rev.1 with latest amendments. One Automatic changeover Unit comprise 32 nos. of external Non Deteriorating Type or 'G' type fuses from 0.6 Amp to 4 Amp capacities which are in signaling circuits. System shall have 8 cards with monitoring arrangement of 4 fuses in one card. Inspection:(i) RDSO/RITES: if value of item in work more than 5 lakhs (ii) Consignee: subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy. Inspection charges:(i)Borne by Railways (ii) None Payment Terms: 100% after supply. (Per Unit should be read as Per Module)						
26	04013500	1.00	Per Unit	48285.03	48285.03	AT Par	48285.03
26	Description:- Supply of Fuse auto changeover system for Railway Signaling System as per RDSO/SPN/209/2012 rev.1 with latest amendments. One Automatic changeover Unit comprise 24 nos. of external Non Deteriorating Type or 'G' type fuses from 4 Amp to 10 Amp capacities which are in signaling circuits. System shall have 6 cards with monitoring arrangement of 4 fuses in one card. Inspection: (i) RDSO/RITES: if value of item in work more than 5 lakhs (ii) Consignee: subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy. Inspection charges: (i)Borne by Railways (ii) None Payment Terms: 100% after supply. (Per Unit should be read as Per Module)						
27	04013600	3.00	Per Unit	885.44	2656.32	AT Par	2656.32
27	Description:- Installation wiring testing and commissioning of Fuse change over system (FACS). This includes provision of common Buzzer & indication at ASM Room & ESM Duty Room and painting of fuse details. This also includes fabrication of frame for installation of FACS at Station/ LC gate where installation of relay racks not feasible. Inspection: Consignee Inspection charges: None Payment Terms: 100% on commissioning(Per Unit should be read as Per Module)						
28	05012601	50.00	Numbers	2067.93	103396.50	AT Par	103396.50
28	Description:- Supply of uncharged Low Maintenance Lead Acid (LMLA) secondary cell, shelf mounting type conforming to RDSO Specn.No.IRS:S-88/2004 or latest with inter cell connectors, nuts and bolts etc. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply. 2V, 80 AH						
29	05012602	13.00	Numbers	5665.46	73650.98	AT Par	73650.98
29	Description:- Supply of uncharged Low Maintenance Lead Acid (LMLA) secondary cell, shelf mounting type conforming to RDSO Specn.No.IRS:S-88/2004 or latest with inter cell connectors, nuts and bolts etc. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply. 2 V, 200 AH						
30	05012604	60.00	Numbers	11251.70	675102.00	AT Par	675102.00
30	Description:- Supply of uncharged Low Maintenance Lead Acid (LMLA) secondary cell, shelf mounting type conforming to RDSO Specn.No.IRS:S-88/2004 or latest with inter cell connectors, nuts and bolts etc. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply. 2V, 500AH						
31	05012701	50.00	Numbers	371.02	18551.00	AT Par	18551.00
31	Description:- Charging of Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice of N.W.Rly & instruction of Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by contractor & Rly's site-in-charge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution. 2V 80AH						
	05012702	12.00	Numbers	985.59	11827.08	AT Par	11827.08

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

32	Description:- Charging of Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice of N.W.Rly & instruction of Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by contractor & Rly's site-in-charge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution. 2V 200AH						
33	05012703	55.00	Numbers	986.73	54270.15	AT Par	54270.15
	Description:- Charging of Lead Acid Batteries with contractors own battery grade sulphuric acid and distilled water with minimum two charge - discharge cycles, installation of charged batteries in groups & their connection & wiring. The work shall be done as per extant practice of N.W.Rly & instruction of Engineer-in-charge. Detailed measurements of initial charging shall be recorded jointly by contractor & Rly's site-in-charge. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution. 2V 300AH/ 500 AH						
34	05014400	15.00	Kg	106.98	1604.70	AT Par	1604.70
	Description:- Supply of Rubber Mat for Power Equipment room. (5mm/10mm/12 mm/20 mm thick) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.						
35	06010100	5.00	Numbers	60412.20	302061.00	AT Par	302061.00
	Description:- Supply of ELECTRIC POINT MACHINE 143 MM STROKE AC IMMUNITY 160V AC COMPLETE WITH LOCK DETECTOR AND SLIDES FOR LOCK DETECTOR NON -TRILABLE TO OPERATE ON 110 V DC ROTARY LOCKING WITH CRANK HANDLE UNIVERSAL TPE AS PER RDSO SPECN. NO. IRS:S-24/2002 (AMND 1) RDSO DRG. NO S-10800 (ALT.5) WITH JUNCTION BOX TELESCOPIC. THE MOTOR WILL BE AS PER RDSO SPECN. NO. IRS: S-37/82 (AMND. 3) WITH RDSO DRG. NO. S-10910. This includes supply of Set of tools as per para20.1 & 20.2 of RDSO SPECN. NO. IRS:S-24/2002 (AMND 1) 20.1 The following set of tools in a suitable tool box shall be supplied along with every set of eight point machines or less. i). Hand operated square drive socket wrenches of 12.5 mm driving square (short type) as per IS: 7381 for M8, M10, M12 & M18 threads. (One 250 mm long 12.5 mm square extension bar as per IS: 7991 alongwith compatible Tee handle Square drive as per IS: 7975 suitable for above socket wrenches shall also be provided.) ii). Open jaw wrenches (spanners) for M10, M12, M20, M24 & M33 threads as per IS: 2028. iii). Adjustable wrench. iv). Screw driver 300 mm long. 20.2 Junction box and two numbers of telescopic pipes of approved type shall be supplied as an integral part of the point machine. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.						
36	06010200	1.00	Numbers	72450.00	72450.00	AT Par	72450.00
	Description:- Supply of ELECTRIC POINT MACHINE 143 MM STROKE AC IMMUNITY 400V AC COMPLETE WITH LOCK DETECTOR AND SLIDES FOR LOCK DETECTOR NON -TRILABLE TO OPERATE ON 110 V DC ROTARY LOCKING WITH CRANK HANDLE UNIVERSAL TPE AS PER RDSO SPECN. NO. IRS:S-24/2002 (AMND 1) RDSO DRG. NO S-10800 (ALT.5) WITH JUNCTION BOX TELESCOPIC. THE MOTOR WILL BE AS PER RDSO SPECN. NO. IRS: S-37/82 (AMND. 3) WITH RDSO DRG. NO. S-10910. This includes supply of Set of tools as per para20.1 & 20.2 of RDSO SPECN. NO. IRS:S-24/2002 (AMND 1) 20.1 The following set of tools in a suitable tool box shall be supplied along with every set of eight point machines or less. i). Hand operated square drive socket wrenches of 12.5 mm driving square (short type) as per IS: 7381 for M8, M10, M12 & M18 threads. (One 250 mm long 12.5 mm square extension bar as per IS: 7991 alongwith compatible Tee handle Square drive as per IS: 7975 suitable for above socket wrenches shall also be provided.) ii). Open jaw wrenches (spanners) for M10, M12, M20, M24 & M33 threads as per IS: 2028. iii). Adjustable wrench. iv). Screw driver 300 mm long. 20.2 Junction box and two numbers of telescopic pipes of approved type shall be supplied as an integral part of the point machine. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.						
37	06010300	12.00	Numbers	27586.01	331032.12	AT Par	331032.12
	Description:- Fixing, wiring, testing and commissioning of Electrical Point Machine on the extended sleepers at points as per std. practice and as per RDSO Drg No. SA 9151-52 or 9710 or 9161 or 10800 or 11000 as per section of rails used. Item includes fixing switch extension bracket, providing insulation for switch extension bracket, fixing ground connection, adjusting opening of the switches and adjusting the point machine with crank handle.The item also includes : (i)Complete material for installation like ground-connections, switch extension brackets, point insulation material, I pipes, wiring materials, various fixing nuts & bolts including castle nuts, spring washers (ii) All smithy & fitting works required at site for complete installation. (iii) Installation of gauge tie plate & providing insulation for gauge tie plate (Insulation in William Stretcher Bar will be Provide by Railways). (iv) Wiring inside the point machine, insertion and termination of tail cable in point machine and junction boxes / location box /cable hut as per extent practice on NWR and the instruction of Railway Engineer at site. (v) Supply and fixing of suitable size GI pipes with flange for taking cable into point machine. Note ; The ground connections shall be suitable to the Point Machines as specified by Engineer-in-charge and shall be suitable to the point lay out i.e. 60 Kg. / 52 Kg / 90R as per yard layout. Electrical Point Machine and M-6 / Screw less terminals will be supplied by Railways / covered in Schedule separately Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.						
	06010500	20.00	Set	1156.31	23126.20	AT Par	23126.20

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

38	Description:- Supply of Gauge Tie plate insulation as per RDSO/SPN/168/2005 as per RDSO drg No: T- 10372Alt2, T- 10368, T- 10371Alt2, T-15083/88/Alt2 & T-11690/Alt2 and as per RDSO/SPN/168/2005 with latest amendments as applicable. Gauge tie plates (52 Kg/60Kg as per site requirement) Insulation for (BG) complete with insulating bush and washer each set comprising of: (a) Insulating plate for insulated tie plate BG as per RDSO Drg.No.T-10372-1 No. (b) Insulating bushing for insulated stretcher bar BG as per RDSO Drg.No.T10368 - 3 Nos. (c) Insulating Washer for insulated stretcher bar BG to IRS 40/84 as perRDSO drg.No.T-10371 - 6 Nos. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
39	06010600	20.00	Set	6829.74	136594.80	AT Par	136594.80
	Description:- Supply of Ground connections, complete set suitable for IRS type / approved point Machine for ordinary turnout with tongue attachment insulation and other insulation as per RDSO Drg. S/3361@ 47>47@ 63 (for IRS type point machine) or RDSO Drg No.SA-9151/52 (for Siemens point machine) with latest amendments. However the ground connection shall be procured only after confirmation from Railway engineer as per site condition /type of machine/turnout. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
40	06010700	4.00	Set	5847.56	23390.24	AT Par	23390.24
	Description:- Supply of Ground connections, complete set suitable for IRS type/approved point Machine for derail switch with tongue attachment insulation as per RDSO Drg. S/3361@ 47>47? 40@for IRS type point machine) or RDSO Drg No. SA 9151/52 (for Siemens point machine) with latest amendments. However the ground connection shall be procured only after Confirmation from Railway engineer as per latest site condition /type of machine/turnout. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
41	06011400	20.00	Set	386.13	7722.60	AT Par	7722.60
	Description:- Supply of William Stretcher Insulation Set (complete) as per RDSO/SPN/168/2005 with insulating bush and washer to suit point layout and conforming to RDSO Drg.No.T-10372 or latest, T-10368 or latest and T-10371 or latest. 1.1 Insulation for Leading stretcher bars(BG) each set comprising of (a) Insulating plate for leading insulated stretcher bars BG as per RDSO Drg.No.T-10384 - 2 Nos. (b) Insulating bushing for leadingg insulated stretcher bars for BG as per RDSO Drg.No.T-10535- 4 Nos. (c) Insulating Washer for insulated stretcher bar BG as per RDSO drg.No.T-10371 - 6 Nos. 1.2 Insulation for following stretcher bars BG. Each set comprising of: (a) Insulating side plate for insulated stretcher bars BG as per RDSO Drg.No.T-10367 - 3 No. (b) Insulating bushing for insulated stretcher bars BG as per RDSO Drg.No.T-10368 - 6 Nos. (c)Insulating washer for insulated stretcher bars BG as per RDSO Drg.No.T10371 - 12 Nos Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
42	07010100	5.00	Numbers	4505.12	22525.60	AT Par	22525.60
	Description:- Supply of Track feed Battery Charger as per RDSO Specn. No.IRS: S-89/2013 Ver.1.0 or latest. Charging Capacity Rating 10 Amps for Charging 80 AH Battery. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply.						
43	07010200	10.00	Numbers	1439.17	14391.70	AT Par	14391.70
	Description:- Supply of Adjustable Track Feed Resistance 30 Ohms (Disc Type) as per RDSO Drg. No.SA-20161-66/M or latest. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.						
44	07010300	5.00	Per Track Circuit	6354.01	31770.05	AT Par	31770.05
	Description:- Fixing and wiring of DC track circuit equipments i.e. track feed charger, resistance, track relay, battery, B type choke etc., in the Apparatus Case and battery box as per standard practice. Termination of tail cable on M 6 / Screw less terminals WAGO or FINOLEX or similar approved make teminals/ fuse blocks / HRC fuse. Item includes testing /commissioning of track circuit. Complete wiring material will be supplied by contractor. (Supply of Track feed battery charger, track feed battery, resistances & 'B' type choke & Track relays, ARA terminal/Modular terminals wago/phoenix contact type will be supplied by Railways / covered in Schedule separately). Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.						
	07010400	5.00	Per Track Circuit	7952.90	39764.50	AT Par	39764.50

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

45	Description:- Installation of DC track circuits covering all types of Track circuits including points zones also. The item includes provision of doubled continuity GI wire bonds on rail joints after drilling bond-hole of 7.0/7.2mm dia, skimming of fish plate, insertion of insulated block joint(if required), fixing of TLJB (separate for positive & negative rails) with angle iron for track feed/jumper/track relay ends of track circuits and also for fixing jumper cables as per approved Track Circuit Plan, making rail connections through suitable insulated sleeves from TLJB at TF, jumper & TR end with GI wire, rail clips for fixing bond wire on the TLJB as per standard practice, termination of tail cables on TLJB terminals etc. TF/TR wiring shall be fixed on the suitable arrangement on PRC sleepers with the help of Hooks. In case Engineer at site desires that jumpering from TLJBs is to be done using signalling cable 2 core X 2.5 sqmm , contractor shall provide the jumpering cable using 2 X 2.5 sqmm signalling cable. The signalling cable will be supplied by Railways. Hooks shall be provided on PRC sleepers with the help of suitable steel bracket. This item also includes fixing & supply of channel pins, Hooks etc. The item does not include supply of TLJB as per RDSO Drg.No.RST-11509 or latest as per technical specs Installation of of Track Lead Junction Box(TLJB) as per Drg.No.RST-11509 or latest made from FRP material including brass bolts and hylam board sheet with terminals etc. (a) Installation and commissioning of TLJB complete with cover to be in black/red having approximate weight of 4.0 Kg with L-262mm W-212mm and H 90 mm and all the holes required for mounting on FRP stump (verticall two for each FRP angle) HDPE pipe , cable etc. (b) Installation and commissioning of Each TLJB having two bakelite terminal block fitted horizontally : each bakelite terminal block shall have two nickel chrome plate M10 brass terminal, 50mm long. Alongwith each TLJB , nickel chrome plated brass links(two nos. Of adequate strength for vertical linking of the terminals to be wired and fixed properly. (c) Installation of HDPE pipe of size 32/35mm , 380 mm long alongwith two nuts for fixing on the TLJB hole . (d) Installation of the FRP stump for mounting the TLJB to be made of one meter long 30mm X30mmX 4mm angle(2 nos.) and 300mm long 30mm X30mmX 4mm angle(1 no.) fixed at 50 mm from the bottom using galvanised nuts and bolts. The TLJB and the angles for stump should be fixed in given holes on them for fixing using galvanised nuts and bolts . Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.						
46	07010500	50.00	Numbers	1778.40	88920.00	AT Par	88920.00
	Description:- Supply of Track Lead Junction Box(TLJB) as per Drg.No.RST-11509 or latest made from FRP material including brass bolts and hylam board sheet with terminals etc. The technical specifications are as follows: (a) TLJB complete with cover to be in black/red having approximate weight of 4.0 Kg with L-262mm W-212mm and H 90 mm and all the holes required for mounting on FRP stump (verticall two for each FRP angle) HDPE pipe , cable etc. (b) Each TLJB shall have two bakelite terminal block fitted horizontally : each bakelite terminal block shall have two nickel chrome plate M10 brass terminal, 50mm long. Alongwith each TLJB , nickel chrome plated brass links(two nos. Of adequate strength for vertical linking of the terminals to be supplied. (c) HDPE pipe of size 32/35mm , 380 mm long alongwith two nuts for fixing on the TLJB hole . (d) The FRP stump for mounting the TLJB to be made of one meter long 30mm X30mmX 4mm angle(2 nos.) and 300mm long 30mm X30mmX 4mm angle(1 no.) fixed at 50 mm from the bottom using galvanised nuts and bolts. The TLJB and the agles for stump should come alongwith holes on them for fixing using galvanised nuts and bolts of adequate strength to be supplied alongwith TLJB drawing no. 11509. Inspection: (i) RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i) Borne by Railways (ii) None Payment Terms: 100% on Supply						
47	07010600	25.00	Numbers	1315.64	32891.00	AT Par	32891.00
	Description:- Erection, Fitting and Rail connection of Track Lead Junction Box on two supports (FRP stumps) with contractor's fixing material . This will include drilling of holes for track lead/side connections on rail. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution.						
48	07010700	10.00	Numbers	4098.94	40989.40	AT Par	40989.40
	Description:- Supply of B Type Choke as per RDSO Specn.No.IRS:S-65/83 (Amnd. 1) or latest. Inspection: RDSO Inspection Charges: Borne by Railways. Payment Terms: 100% after supply.						
49	07010800	2000.00	Numbers	5.69	11380.00	AT Par	11380.00
	Description:- Supply of Channel Pins MS (Galvanized) single groove, 7 mm suitable for 4mm dia bonding wire as per spec No IRS S 17 & RDSO Drg No. S-69/M. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.						
50	07010900	10.00	Kg	66.01	660.10	AT Par	660.10
	Description:- Supply of GI wire 8 SWG (4mm dia) suitable for track circuit rail bonding. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Supply.						
51	07011000	50.00	Numbers	179.82	8991.00	AT Par	8991.00
	Description:- Provision/Installation of bonding with GI wire 4mm dia (8 SWG) for track jumper & fish plate joints bonds. This will include drilling of 7.0/7.1/7.2 mm dia holes in rails (4 Nos.) and provision of two jumpers for each bond, clipping of bonds etc. with contractors own tools as per instruction of Rly. Engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after Execution.						
	07014100	2.00	Numbers	8051.14	16102.28	AT Par	16102.28

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

52	Description:- Supply of hand operated track drilling machine for bonding hole. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after supply.						
	07012600	2.00	Set	19999.83	39999.66	AT Par	39999.66
53	Description:- Installation testing & commissioning of High Availability Single Section digital axle counter (HASSDAC) single section type system complete with track devices and other associated accessories. This include fixing of device, relays, wiring, lacing /dressing, cable termination with lug eyelet, drilling holes in rails, Installation of track devices and make it functional along with existing UFSBI/blockinstrument. Material required other then supply item of HASSDAC in item no. 7.25 of SOR shall be arranged by contactor to make it functional. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.						
	08010400	150.00	Numbers	178.89	26833.50	AT Par	26833.50
54	Description:- Installation of LED signals lamps for auxiliary/subsidiary signals/main signals (i.e. route, shunt , calling on, Red , Yellow, Green) as per instructions given by engineer incharge. The contractor will supply all materials required for installation. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.						
	08010500	2.00	Numbers	10791.46	21582.92	AT Par	21582.92
55	Description:- Supply of Colour Light Signal Complete. This includes: - (1). Post Tubular 140 mm Dia, as per IRS: S-6/81 or Latest & RDSO Drg. No. SA-24625 (Advance). (2). CI Base (As per IRS S-10 & RDSO Drg. No. 2011/M with latest assembly). (3). Number plate to Drawing No. S 23149 Alt.1 =1 No , Number plate clamps to Drawing No. S 23148 Alt.1 =2 no (4). Ladder Assembly, as per RDSO Drg. No. SA-23156, with Base, Ladder Guard rail (complete) to Drawing No. SA 23138 Alt.1(1No), Platform to Drawing No. SA 23134 Alt.1(1 No), Front Maintenance Platform, MS Supporting bracket to Support Ladder.Ladder stay (small) to Drawing No. S 23159 Alt. 1 (2 Nos.) , Ladder stay (large) to Drawing No. S 23160 Alt. 1 (2 Nos.) , Ladder section to Drawing No. SA 23157 Alt. 1(1 Nos.)Stay clamp to Drawing No. SA 2062/M (2 no), Rail Clamp to Drawing No. S 2066/M (1 No.) (5). Signal Front Staging Complete Assembly for CLS Unit. (6). Signal back staging as per extent NWR Practice. Note: Note: Height of the Post shall be 5.5 Long. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
	08010600	2.00	Numbers	4462.49	8924.98	AT Par	8924.98
56	Description:- Supply of Offset brackets for Main Signal, made of tubular steel, outer diameter 140 mm, thickness of pipe 4.5 mm. horizontal length of pipe 545 mm & vertical length of pipe 324 mm with fixing arrangement on Main Signal post as per Drawing No SW/554/G/R Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
	08010700	3.00	Numbers	4336.16	13008.48	AT Par	13008.48
57	Description:- Supply of Offset brackets for Shunt Signal, made of tubular steel, outer diameter 89 mm, thickness of pipe 4.5 mm. horizontal length of pipe 324 mm & vertical length of pipe 324 mm with fixing arrangement on Shunt Signal post as per Drawing No SW/354/I Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
	08010801	3.00	Numbers	3227.65	9682.95	AT Par	9682.95
58	Description:- Erection of CLS Post with base and signal unit on top or on OFFset Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. The item includes cutting of Signal post if required by Site In charge. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning. 2/3/4 aspect signal unit mounted on offset bracket with junction type route indicator 1/2/3/4/5/6 or multilamp lamp route indicators/Stencil type rout indicator mounted on signal post.						
	08010802	2.00	Numbers	2187.43	4374.86	AT Par	4374.86
59	Description:- Erection of CLS Post with base and signal unit on top or on OFFset Bracket, fixing of front and back staging, ladder and guards, signal name plates / boards if any with contractor's own brackets and fixing materials. This also includes erection of auxiliary signals like calling on, shunt signal if any. The work shall be done as per instructions of Rly engineer at site. It also includes provision & fixing of maintenance platform as per design given by Engineer -In-Charge at site. The item includes cutting of Signal post if required by Site In charge. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning. 2/3/4 aspect signal unit mounted directly on signal post.						
	08011000	2.00	Numbers	28042.78	56085.56	AT Par	56085.56

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

60	Description:- Supply of Non Metallic (FRP) colour light signal housing multi unit type for railway signaling suitable for RE area THREE Aspects. Complete without lenses, lamps and signal transformer as per RDSO DRG. No. SA 23001/A/M Adv. Alt- S and as per SPEC. No. RDSO/SPN/194/2006 (Rev 2.0) or latest and FRP material as per RDSO SPEC. No. RDSO/SPN/151/1997 or latest. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
61	08011200	3.00	Set	4297.47	12892.41	AT Par	12892.41
	Description:- Supply of Position Light Shunt Signal Unit Complete with Post(made of GI Pipe of 80 mm Diameter Medium Class IS Spec. No. IS: 1239 Pt. 1/1990, Base, Hood, Cover etc as per Drg. No. SA-23840 suitable for LED Signal Lighting Unit.(Supply of LED Unit is not covered in this item) Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
62	08011300	3.00	Numbers	1779.99	5339.97	AT Par	5339.97
	Description:- Erection of Position Light Shunt signal with Base, Post, Signal unit and fixing of Number Plates. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.						
63	08011400	2.00	Numbers	3358.53	6717.06	AT Par	6717.06
	Description:- Supply of Position Light Shunt Signal Unit Complete, with offset bracket, hood, Cover etc as per Drg. No. SA-23840 suitable for LED Signal Lighting Unit.(Supply of LED Unit is not covered in this item)Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
64	08011500	3.00	Numbers	1967.77	5903.31	AT Par	5903.31
	Description:- Erection of Position Light shunt signal on Offset bracket on main signal. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.						
65	08011700	1.00	Numbers	20490.35	20490.35	AT Par	20490.35
	Description:- Supply of Junction route indicator unit 2 way (Without Lenses & Holder) as per Drg. No. RDSO SA 23402 suitable for LED Signal Lighting Unit & as IRS:S-66/84 amndt-1 or latest.(Supply of LED Unit is not covered in this item) Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board. Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% on Supply						
66	08012300	1.00	Numbers	590.67	590.67	AT Par	590.67
	Description:- Fixing of Junction type Route Indication 1-Way/2-Way/3-Way/4-Way/5-Way/6-Way on the top of the signal post. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Commissioning.						
67	08012700	3.00	Numbers	2144.18	6432.54	AT Par	6432.54
	Description:- Supply of Stop Board as per RDSO Drg No 7235/B / Block Section Limit Board/Shunting Limit Board as per RDSO Drg. No. SA2375 (Adv.) . This includes Painting and retro reflective arrangement should be as per SEM. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.						
68	08012800	3.00	Numbers	4637.76	13913.28	AT Par	13913.28
	Description:- Supply of Different warning Boards / Calling on Board used for Railway Signalling system as per RDSO Drg. No. SA2380 (Adv). This includes Painting and retro reflective arrangement should be as per SEM. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.						
69	08012900	6.00	Numbers	334.60	2007.60	AT Par	2007.60
	Description:- Fixing of Stop Board, Block section limit Board, Shunting Limit Board, goods warning board , Calling on Board with contractors own material. This excludes supply of Stop Board / Block section limit Board / Goods warning board/Calling on board. The work shall be done as per instruction of Rly Engineer at site. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.						
70	08013000	10.00	Numbers	1223.46	12234.60	AT Par	12234.60
	Description:- Supply, Fabrication and fixing of Signal Number Plate(CSTE Drg No CSTE/6186) , 'A' Marker (Drg No. CSTE/6180), 'AG' Marker (Drg No. CSTE/6181), 'P' Marker (Drg No. CSTE/6182), Arrow Marker (Drg No. CSTE/6183), 'G' Marker (Drg No. CSTE/6184), 'C' Marker (Drg No. CSTE/6185). marker disk on signals as per standard practice All material required for this work shall be supplied by Contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.						
	08013100	5.00	Numbers	5087.65	25438.25	AT Par	25438.25

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

71	Description:- Supply and fixing of protective screen of expanded metal 12 SWG of size 1200 x 1500 mm on signals as per std. practice in RE Area. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.						
	08013200	3.00	Numbers	9361.50	28084.50	AT Par	28084.50
72	Description:- Casting of CC Foundation for Signal Post in the ratio of 1:3:6 as per Drg.No.CSTE/NWR/SOR/21/A using standard size of foundation/galvanized holding down bolts required for erection of colour light signal post. Item includes excavation, ramming of CC using vibrator, curing and plastering with 1:4 cement-sand mixture (aggregate will not exceed 3.8 cm). Aggregate, cement, sand and holding down bolts will be supplied by contractor. Any machines & tools, if required for execution of this item, will be arranged/provided by contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.						
	08013300	4.00	Numbers	6310.26	25241.04	AT Par	25241.04
73	Description:- Casting of C.C. Foundation for Position Light Shunt Signal/ Indicator/SPI as per Drg.No.CSTE/NWR/SOR/ 22 in ratio 1:3:6 by using standard size of galvanized holding down/foundation bolts. Item includes excavation, ramming of CC using vibrator, curing and plastering with 1:4 cement sand mixture. Aggregate cement, sand and holding down bolts, will be supplied by contractor. Any machines and tools, if required for execution of this item, will be arranged/provided by contractor. Note: As per available site conditions, if sizes of foundations are required to be decreased/ increased and same has been approved/agreed by engineer incharge then variation in CC work will be calculated on volumetric basis as per rates of these items. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation. ."						
	08013400	30.00	cum	4323.85	129715.50	AT Par	129715.50
74	Description:- Cement concrete work for miscellaneous items in ratio 1:3:6. Item includes excavation, ramming of CC by using vibrator, curing and plastering with cement and sand mixture (aggregate will not exceed beyond 3.8 cm). The aggregate cement and sand will be supplied by contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.(Unit is per cubic meter)						
	09010500	4.00	Set	25128.93	100515.72	AT Par	100515.72
75	Description:- Supply of (02) nos. electrical lifting barrier booms of 9.76 meter each as per DRG RDSO/S 11600 . The material will be as per RDSO Specn.No.RDSO/SPN/208/2012/Ver.2.0 and Amendment 1 or latest. Inspection: Consignee subject to procurement from RDSO approved supplier. Inspection Charges: None. Payment Terms: 100% after Supply						
	10013700	5.00	Numbers	5301.70	26508.50	AT Par	26508.50
76	Description:- Supply of CO2 type fire extinguisher capacity 4.5 Kg capacity ISI Mark IS: 15683 operating temperature (-30) ° to (50) ° for class 13 B type of fire with 1 mtr. Hose pipe fitted with PVC bend horn complete in all respect. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.						
	10011400	1.00	Numbers	16271.42	16271.42	AT Par	16271.42
77	Description:- Supply of Steel Plain Almirah with 4 adjustable slavesSize: 1980mm height, 915 mm width and 485 mm depth.Make: Godrej Storewel Plain Large or Similar of reputed brand. Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.						
	11010100	5.00	Numbers	14945.53	74727.65	AT Par	74727.65
78	Description:- Supply of Apparatus Case Single(Large) NE Rly Type as per Drg. No. CSTE/6088 fitted with two nos of E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11500. Note: This item includes the supply of 2 Nos E Type Lock fitted on both doors, along with two Keys. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RECOMMENDED LIST OF FIRMS FOR MECHANICAL SIGNALLING ITEMS if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.						
	11010200	20.00	Numbers	1039.09	20781.80	AT Par	20781.80
79	Description:- Installation of Apparatus Cases Single(Large) with 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. Supply of 'E' Type lock has been covered in supply of Apparatus case separately. It covers fixing of lamp holder , switch and lamp etc. in Apparatus Case. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.						
	11010300	4.00	Numbers	9439.40	37757.60	AT Par	37757.60
80	Description:- Supply of Apparatus Case half (Medium) NE Rly Type as per Drg. No. CSTE/6088 fitted with two nos of E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11507. Note: This item includes the supply of 2 Nos E Type Lock fitted on both doors, along with two Keys. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RECOMMENDED LIST OF FIRMS FOR MECHANICAL SIGNALLING ITEMS if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.						

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

81	11010400	10.00	Numbers	632.78	6327.80	AT Par	6327.80	
	Description:- Installation of Apparatus Cases Half (Medium) with 'E' type lock on CC foundation. This includes filling of location foundations with river bed sand and plastering on top of the sand. Supply of 'E' Type lock has been covered in supply of Apparatus case separately. It covers fixing of Location lamp holder , switch and lamp etc. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.							
82	11010801	20.00	Numbers	6888.92	137778.40	AT Par	137778.40	
	Description:- Excavation and Casting of Apparatus Case foundation in ratio 1:3:6 with contractor's own materials including cement and galvanized anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost.The item also includes additional masonry work as well as earthwork if required on bank where there will be possibilities of foundation sinked, fallen or tilted. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation. Single (Large) Case Apparatus case / SS location box as per Drg No. CSTE/5074							
83	11010802	10.00	Numbers	5259.16	52591.60	AT Par	52591.60	
	Description:- Excavation and Casting of Apparatus Case foundation in ratio 1:3:6 with contractor's own materials including cement and galvanized anchor bolts of standard size. The required scaffolding Ferma etc for Casting of foundation will have to be brought by the contractor at his own cost.The item also includes additional masonry work as well as earthwork if required on bank where there will be possibilities of foundation sinked, fallen or tilted. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation. Half (Medium) Case Apparatus case / SS location box as per Drg No CSTE/5074							
84	11010900	10.00	Numbers	9563.45	95634.50	AT Par	95634.50	
	Description:- Supply of Phenolic laminated Sheet, grade P3 in standard size of 1220 X 1220 x 20 mm as per spec. No IS 2036 of 1995 or latest. Test report of manufacture to be supplied. Inspection: (i) RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee Inspection Charges:(i) Borne by Railways (ii) None Payment Terms: 100% after Supply.							
85	11011201	20.00	Numbers	2344.49	46889.80	AT Par	46889.80	
	Description:- Fabrication and fixing of phenolic laminated sheet of size 10/12/20 mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation. Single Case (Large Case)							
86	11011202	10.00	Numbers	684.00	6840.00	AT Par	6840.00	
	Description:- Fabrication and fixing of phenolic laminated sheet of size 10/12/20 mm thick in location box by providing all fixtures as per Railway Drawing including fixing of PVC coated string rods at the back side for cable support with contractor's own materials. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation. Half Case (Medium Case)							
87	11011300	5000.00	Numbers	12.52	62600.00	AT Par	62600.00	
	Description:- Fixing of ARA(M-6) Terminals /Screw less connectors / modular disconnect terminal blocks and fuse blocks on phenolic laminated sheets and fixing by stainless steel/brass nuts & bolts. This includes provision of two additional holes on the board on either side for cable conductor entry. (Supply of all above terminals have been covered separately in Chapter 4 of SOR) Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.							
88	11011400	70.00	Numbers	59.18	4142.60	AT Par	4142.60	
	Description:- Supply of Round head type non deteriorating type low voltage cartridge fuse as per Spec No IRS/S/78/92 with latest amendments 2A/4A/6A capacity. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after supply.							
89	11011500	100.00	Numbers	63.73	6373.00	AT Par	6373.00	
	Description:- Supply of HRC fuses block complete with 2A fuse link as per IS 9224/79 Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after supply.							
90	11012000	2.00	Numbers	2193.20	4386.40	AT Par	4386.40	
	Description:- Fixing of KLCR relays in field in half location boxes if Gate lodge is not provided or at any other location as decided by engineer in charge. Item includes supply and fixing of MS sheet and wiring of KLCR relays, push buttons and LEDs for KLCR circuit. The KLCR relays, push buttons, LEDs will be fixed on a MS sheet of min. 3mm in the half location box. The MS sheet will cover full length and breadth of the half location box and divided in two pieces of approx. 48cm x 46cm and 80cm x 46cm. The first piece to be fitted on top and will contain the KLCR relays, LEDs and push buttons. The second piece to be fitted below the first piece. (Supply of KLCR relays covered in separate item of SOR). Inspection: Consignee Inspection Charges: None Payment Terms: 100% after installation.							
	12010200	100.00	Metre	760.66	76066.00	AT Par	76066.00	

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

91	Description:- Supply of Medium class GI pipes 100 mm dia(4.5 mm thickness) as per IS 1239 (Part 1) : 2004 with coupling on culverts bridges as per Drg.No.CSTE/NWR/SOR/06 to 12 or at any other locations as decided by Site Engineer. It includes supply of all material required for fixing arrangement. Contractor will also supply flexible/corrugated HDPE pipe at the end of GI pipe to protect the cables from sharp edges and sudden bends. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.						
92	12010300	100.00	Metre	190.17	19017.00	AT Par	19017.00
	Description:- Fixing of Medium class GI pipes 100 mm dia(4.5 mm thickness) as per IS 1239 (Part 1) : 2004 with coupling on culverts bridges as per Drg.No.CSTE/NWR/SOR/06 to 12 or at any other locations as decided by Site Engineer. It includes installation of all material required for fixing arrangement. Contractor will install flexible/corrugated HDPE pipe at the end of GI pipe along with any masonry work(if required) to protect the cables from sharp edges and sudden bends. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after installation.						
93	12010601	2000.00	Metre	14.80	29600.00	AT Par	29600.00
	Description:- Supplying and placing of one layer of standard size of B grade quality bricks of the local make spreading on cables laid.(minimum size of brick 200mm X 100mm X 70mm) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Installation. Lengthwise (up to 2 cables).(Unit is per RM Running Meter)						
94	12010602	25000.00	Metre	31.87	796750.00	AT Par	796750.00
	Description:- Supplying and placing of one layer of standard size of B grade quality bricks of the local make spreading on cables laid.(minimum size of brick 200mm X 100mm X 70mm) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Installation. widthwise (more than 2 cables).(Unit is per RM Running Meter)						
95	12010700	100.00	Numbers	1798.20	179820.00	AT Par	179820.00
	Description:- Supply of Double Walled Corrugated (DWC) HDPE Pipe/duct with associated collars etc. as per RDSO Specification No. RDSO/SPN/204/2011 or latest anti-rodent & anti-oxidant and non flame propagating type in 6 meters straight length and of size 120 mm outer dia,& 103.5 mm inner dia. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber O-Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap (The total quantity of above items is equal to no. of pipes supplied.) DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vendor name and year of manufacture can be easily identified. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply						
96	12010900	600.00	Metre	383.47	230082.00	AT Par	230082.00
	Description:- Supply of Double Wall Corrugated (DWC)-HDPE pipe/duct of size 200 mm outer dia, & 175 mm inner dia. It includes supply of Double Wall Corrugated -HDPE pipe/duct as per RDSO Specn.No. RDSO/SPN/ 204/2011 (version 1.1) or latest and conforming to ISI Spec. No.IS:14930, Part-II. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement. 1) Suitable snap fit coupler with rubber O-Ring 2) Spacers 3) Tees 4) Bend, 5) End-cap DWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vendor name and year of manufacture can be easily identified. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy Inspection Charges: (i)Borne by Railways (ii) None Payment Terms: 100% after Supply						
97	12011600	500.00	Metre	29.59	14795.00	AT Par	14795.00
	Description:- Placing of DWC HDPE/RCC/GI pipes along with collars in trenches at places near track and road, crossings, platform cuttings etc. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is RM running meter.)						
98	12012000	50.00	Numbers	2148.73	107436.50	AT Par	107436.50
	Description:- Supply of Thermo shrink Universal Jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amd. Inspection: RDSO Inspection Charges: Borne by Railways Payment Terms: 100% after Supply						
99	12012300	500.00	Metre	122.74	61370.00	AT Par	61370.00
	Description:- Horizontal Drilling by using manual pushing method at minimum depth of 1.5 meter below the formation level of earth as per decision of Engineer in charge .Pipe Supply is not covered under this item Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution						
100	12012700	50.00	Numbers	241.28	12064.00	AT Par	12064.00
	Description:- Supply of galvanized cable markers as per Drg.No.CSTE/NWR/SOR/15. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Supply.						
	12012800	50.00	Numbers	60.32	3016.00	AT Par	3016.00

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

101	Description:- Transportation at site and Fixing of galvanized cable markers as per Drg.No.CSTE/NWR/SOR/15. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution						
	12013200	20.00	Numbers	361.92	7238.40	AT Par	7238.40
102	Description:- Transferring of Signaling/Telecom cables from existing Location box to New Location box . The work include breaking/ Dismantling of Existing foundation of locations, excavating and removing / segregating coils of 2C/6C/12C/19C/24C/30C/Quad cables which may be about 10 mtrs. in length. These cables are to be disconnected and removed from the existing location one by one as per the instruction and under the supervision of Railway staff present at site. The cable is then to be inserted and terminated in new location box. The item includes neatly dressing of cable, making wiring tree etc.The material required to dressing /lacing will be arranged by contactor. The work is required to be done systematically and with due precaution during the block or disconnection within the time that may be allowed. The excavation work to be done carefully without damaging the cable to avoid undue failure. (Termination charges will be given separately). Note: Proportionate payment will be made if cable of other length. One No unit = One cable of 10 m length) Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution						
	12013600	20.00	cum	138.14	2762.80	AT Par	2762.80
103	Description:- Removal of excavated/slip earth/ debris/ malba from the site of works to any other place outside Railway land/premises, including all excavations, handling, re-handling, loading, unloading and leading, etc. all labour and material as a complete job. Removal of Earth (all kinds of soils)/ROCKS, BOULDERS including mud/slush, slipped earth in catch water drains, side drains, over berms in cutting, water way of bridges, over coping of toe/breast/retaining walls etc. including crossing of nallah, railway tracks, making/repairing approach roads if required, all lead, lift, ascent, descents, or any other obstruction. Earth spoils to be dumped outside the cutting or railway embankments as per direction of Engineer in charge Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is Cubic Meter)						
	12013700	1800.00	cum	274.28	493704.00	AT Par	493704.00
104	Description:- Excavation of cable trench as per cable route plan, 1.2 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr. wide at bottom as per RDSO sketch No. SDO/CABLE LAYING/003 or latest alongside the track in normal (all type) soil/strata, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc, covering of cable laid in trench by loose soil for a layer of 50mm thickness approximately before covering by bricks. The work shall be done as per the extant practice on North Western Railway and instructions of Railway Engineer at site. In case 1.2m depth of trench is not achievable due to site conditions, specific approval of JA grade officer will be required for each site where trench depth of 1.2m is not possible. Without the approval of JA Grade officer, no payment for trenching will be made for trench depth less than 1.2m. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is Cubic Meter)						
	12013800	600.00	cum	274.28	164568.00	AT Par	164568.00
105	Description:- Digging of trench 1.2 Mtrs. deep from rail flange/ road level and 0.3 Mtrs to 0.6 Mtrs wide and back filling after placing of DWC/ RCC/GI pipe. (Placing of DWC/RCC/GI pipe covered separately).The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. For track crossing, Drg. No.CSTE/3644 Pg.7 of 11 and for Road Crossing, Drg. No. CSTE/3644 Pg. 5 of 11 are to be followed. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is Cubic Meter)						
	12013900	600.00	cum	503.04	301824.00	AT Par	301824.00
106	Description:- Digging of cable trench 0.3 Mtrs. Deep and 0.3 Mtrs. Wide on Asphalted Platform / Road / Hard rocky area. Refilling with earth leveling of trenches & restoring the original surface of trenches.The sharp edges will be smoothened out in bottom of the chase and will be leveled properly. In hard rocky ground area , cables will be laid normally on layer of shifted earth of 0.05 mtrs thickness previously deposited at bottom of the trench and cables will be covered with layer of sand or shifted earth of 0.1 mtr thickness. In case sharp edges of rocky ground can not be protected from shifted earth then GI/ CI /PVC /DWC/ HDPE pipes will be used, if numbers of cables is small.In case number of cables are large RCC duct will be used. In isolated cases, it can be given smooth surface by using either masonry bricks or cement concrete. A row of bricks shall then be placed length wise on the top and jointed with cement mortar and layer of concrete with cement plaster shall be provided on top of the same. Note: This item in hard rocky area will be operated only where normal depth i.e.1.2 mtr is not possible and it will be decided by site engineer/unit officer incharge of work. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is Cubic Meter)						
	12014000	5.00	Numbers	12506.58	62532.90	AT Par	62532.90
107	Description:- Digging of cable pit (min 2x2x1m) as per instruction of Site Engineer, supplying and filling of sand before and after coiling the cables, covering top of the cable pit with stones and providing brick masonry on all four sides of the cable pit and plastering thereafter. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution						
	12014100	39000.00	Metre	9.10	354900.00	AT Par	354900.00

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

108	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each Gantry Post/hectometer post.(Cables will be meggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(unit is RM running meter)						
109	12014300	15.00	cum	1990.54	29858.10	AT Par	29858.10
109	Description:- Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks sand and cement to be supplied by the contractor. Inspection: Consignee Inspection Charges: None. Payment Terms: 100% after Execution(Unit is cubic meter)						
110	13010100	2.00	Numbers	158443.22	316886.44	AT Par	316886.44
110	Description:- Supply of Earth Leakage Detector (ELD) 12 Channels as per RDSO Specn.RDSO/SPN/256/2002 or latest. Inspection: RDSO Inspection Charges:Borne by Railways Payment Terms: 100% after Supply.						
111	13010200	2.00	Numbers	39610.81	79221.62	AT Par	79221.62
111	Description:- Wiring, installation, testing and commissioning of Earth Leakage Detector (ELD) 12 Channels as per RDSO Specn.RDSO/SPN/256/2002 or latest. This includes supply of fuse terminal strip for incoming power supply wires. On job training at site will be given by OEM engineer for installation and maintenance of ELD. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after commissioning.						
112	13010300	6.00	Lot	17530.73	105184.38	AT Par	105184.38
112	Description:- Supply of basic material to construct unit maintenance free earth as per RDSO Specs. No RDSO/SPN/197/2008 or latest and conforming to RDSO Drg.No.SDO/ RDSO/E&B/001 dtd.19.09.08 . It consist of following: (a) Copper bonded steel electrode of 3.0 m long, 17.2 mm dia with copper bonding thickness of minimum macrons and UL listed and marked = 1 no. (b) Earth enhancement material supplied in sealed bags of minimum 10 kg = 3 nos. © Copper strip of 150x25x6 mm, to terminate earth rod = 1 no. (d) Copper strip of 300x25x6 mm (MEEB) = 1 no. (e) Copper strip of 150x25x6mm (SEEB) = 1 no. (ii) Supply of 35 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting main earth electrode to MEEB in the equipment room in duplicate.(minimum 10 meter) (iii) Supply of 16 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting MEEB to SEEB and SPD to MEEB (minimum 10 meter) (iv) Supply of 10 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting various equipments to SEEB (v) Supply of copper lug sleeve for 3/16 cable Inspection: RDSO Inspection Charges:Borne by Railways Payment Terms: 100% after Supply.						
113	13010400	6.00	Set	7861.68	47170.08	AT Par	47170.08
113	Description:- Installation of Unit Maintenance Free Earth as supplied under item no. 13.3 of Chapter 13 of SOR . It includes (i) Digging the earth to the required depth. (ii) Insertion of electrode. (iii) Filling of earth enhancing compound (Approx.30 Kg) (iv) Provision of exothermic weld connections to copper tape of 25 mm x 6 mm x 150 mm to the earth electrodes. All material tools and features required for weld will be arranged by contractor. (v) This also includes CC cover 1.5 ft x 1.5 ft. 1 ft wall thickness 2 inch with cover 3 inch thickness. Cables 35 Sq mm/ 16 Sq mm/10 sq mm for connecting earth to busbar, busbar to busbar and busbars to various equipments. Earth electrode of 17.20 mm dia and 3.00 meter long high tensile low carbon steel circular rods molecularly bonded with copper and outer surface (minimum copper bonding thickness of 250 microns to made requirement of under writer's laboratories (UL) 467-2007 or latest. Copper strips of 150 mm x 25 mm x 6 mm to be welded with each earth electrode, copper strips of 300 mm x 25 mm x 6 mm for main equip- potential busbar, copper strips of 150 mm x 25 mm x 6 mm sub equip-potential busbar in relay room, power room and panel room. GI strip 25 mm x 2 mm for ring formation of earth pits Earth enhancement material in bags for each Earth Electrode. Inspection chamber of site 300 mm x 300 mm x 300 mm (Inside dimension) of approximate 50 mm thick with pulling hooks to cover the earth pits. Note: The installation of this item shall be carried out by the contractor as per RDSO Specn.No.RDSO/SPN/ 197/2008 or latest and conforming to RDSO Drg.No.S DO/RDSO/E&B/001 or latest. Inspection: Consignee Inspection Charges: None Payment Terms: 100% after execution and testing.						
114	13010500	20.00	Numbers	2232.81	44656.20	AT Par	44656.20
114	Description:- Supply of earth electrode as per standard practice and as per Drg No.CSTE/NWR/SOR/14A & 14B. It includes supply of GI pipe of 3m length. Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.						
	13010600	20.00	Numbers	558.20	11164.00	AT Par	11164.00

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

115	Description:- Installation of earth electrode as per standard practice and connecting it to the equipments which are required to be earthed including digging of earth pit 3 mtr deep and fixing earth electrode pipe, casting of cement concrete enclosure with cover as per Drg No.CSTE/NWR/SOR/14A & 14B. It includes installation of 7 strand GI wires as earth lead wires and soldering one end of earth lead wire to earth electrode and other end to block equipments, power equipments, cable sheath, signals etc. as per site requirement and as per instructions given by engineer incharge. Inspection: Consignee Inspection Charges:None Payment Terms: 100% after execution and testing.							
116	13011000	5.00	Numbers	44045.61	220228.05	AT Par	220228.05	
	Description:- Supply of Digital Multimeter of Fluke 287 Industrial or superior True RMS with temperature, Analog bar graph, Digital display, Backlight, 1000V AC/DC, measure up to 10A, 20A for up to 30 second . Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.							
117	13011100	10.00	Numbers	13946.28	139462.80	AT Par	139462.80	
	Description:- Supply of Professional AC/DC clamp meter 3 ¾ digit , true RMS measurement, For Measurement of DC/AC currents up to 1000A, Voltage up to 600V, resistance up to 40 M and frequency up to 1 MHz with set of leads & carrying case. Model - DCM 39A or equivalent/ higher make Motwane/Stanlay/Fluke/Megger Inspection: Consignee Inspection Charges:None Payment Terms: 100% after Supply.							
118	14011300	1.00	Station	53251.72	53251.72	AT Par	53251.72	
	Description:- Dismantling of existing lever frames/signal fittings/point fittings/lifting barriers (within station limit)/indoor and outdoor equipment and all other released material of S&T at way side station (3/4 Line). All the released material will be transported to the place/location as decided by site engineer. The item includes i). Mechanical Signalling gears like levers, down rods, locking trough, Rodding, wire transmission, signal posts and hoods etc. ii). Electrical Signalling gears like relays, batteries, indicators, SM slide control and all released wire transmission for slot, telephone, selector control and their related items etc. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution							
119	14011401	100.00	MT	628.23	62823.00	AT Par	62823.00	
	Description:- Transportation of S&T material leading up to 1 Km including Loading from Starting point, unloading & Stacking at destination.The work is to be done as per the instructions of Railway Representative at site. Consignee will also provide gate pass / road permit to the transporter. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution Transportation of S&T material leading up to 1 Km including Loading from Starting point, unloading & Stacking at destination.The work is to be done as per the instructions of Railway Representative at site. Consignee will also provide gate pass / road permit to the transporter. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution(Unit is metric ton)							
120	14011402	400.00	MT-Km	5.69	2276.00	AT Par	2276.00	
	Description:- Transportation of S&T material leading up to 1 Km including Loading from Starting point, unloading & Stacking at destination.The work is to be done as per the instructions of Railway Representative at site. Consignee will also provide gate pass / road permit to the transporter. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution Extra for each additional 1 Km or part thereof. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution							
121	14011700	1.00	Station	50626.69	50626.69	AT Par	50626.69	
	Description:- Complete painting and varnishing work at a station (5/6 or more Line). This includes painting of signal posts and fittings, apparatus cases, point machines, junction boxes, rail post etc. This also includes varnishing, letter writing on relays, terminal Nos., apparatus cases, point machine, Signal Nos. and other details as per Signal Engineering Manual and instructions of Engineer at site. The item includes painting of distances of main cable run from G.P nearest to cable run and painting of distances of signals from nearest line on the signals base. At least two coats of paint is to be applied besides primary coating of red oxide. This includes supply of paints, varnishes and all other material required for complete painting work at a station.This includes painting on existing functional units also. The painting shall consist of initial red oxide / base paint followed by at least two coat of the paint as per standard painting scheme. This item also includes painting of interlocked gate attached to the station. Location box no. shall be painted on both sides. Inspection:Consignee Inspection Charges: None Payment Terms: 100% after Execution							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-NS ITEMS							13832336.90	
1	B	1.00	Station	2692298.00	2692298.00	AT Par	2692298.00	
	Description:- Alteration Of Existing Application Logic Programme To Suit Modified SIP.							
2	B	1.00	Station	1120255.00	1120255.00	AT Par	1120255.00	

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

	Description:- Alteration To Existing Interface Circuit Diagram To Suit Modified SIP						
3	B	1.00	Station	487473.00	487473.00	AT Par	487473.00
	Description:- Factory Acceptance Test (FAT) of EI system						
4	B	1.00	Station	347449.00	347449.00	AT Par	347449.00
	Description:- Site Acceptance Test (SAT) of EI system						
5	B	1.00	Station	314409.00	314409.00	AT Par	314409.00
	Description:- Installation, Testing & Commissioning Of EI System As Per Modified SIP						
6	B	1.00	Numbers	605381.00	605381.00	AT Par	605381.00
	Description:- Supply Of Materials Required For Alteration Of Existing EI i.e. PIO3C(PIO2-LOG)BOARDS. Inspection-RDSO.						
7	B	1.00	Numbers	161541.00	161541.00	AT Par	161541.00
	Description:- Interconnecting Cables, Connectors ,Terminals, Mounting Arrangements, Fixures & Accessories To Make EI System Alteration Functional.						
8	B	1.00	Numbers	118000.00	118000.00	AT Par	118000.00
	Description:- Supply of ASMADE documents as per NWR practice.						
9	B	40.00	Numbers	3003.28	120131.20	AT Par	120131.20
	Description:- Supply of Relay AC immunized, plug-in type, Style 'QTA2' Neutral track relay 9ohms, contacts 4F/2B front and back contacts, metal to carbon, complete with plug board retaining clip and connectors, As per BRS: 939A, BRS:966 (Appendix F2),IRS:S 34 & IRS : S 23 (as applicable).The interlocking code for this unit shall be FGHKX. Inspection: RDSO.						
10	B	50.00	Numbers	4956.00	247800.00	AT Par	247800.00
	Description:- Supply of Relay AC Immune Plug in type style QNNA1 DC Twin DC Neutral line 24-volt 6F/2B for LH and RH front and back contact metal to carbon complete with plug board retaining clip and connector conforming to BRS 960, IRS:S@58"44@ S:60 and IRS S-23. The interlocking code for this unit shall be CDEHX.						
11	B	20.00	Numbers	3321.24	66424.80	AT Par	66424.80
	Description:- Supply of magneto Telephone Desk Type (push button) spec No.TC-79/2000 with Amendment No. 3 or latest. Inspection:Consignee						
12	B	50.00	Numbers	6.78	339.00	AT Par	339.00
	Description:- Supply, fixing and wiring of PPTC Fuses2/4/6 A maketyco/Raychem/Bourn/Fuzetech/Little Fuseor similar. Capacity wise distribution will bedecided by Consignee. Inspection:Consignee.						
13	B	20.00	Numbers	663.17	13263.40	AT Par	13263.40
	Description:- Casting, transportation and provision of Cement Earth Enclosure As per NWR Drawing Painting and writing work to be done after testing of earth value at site. All materials required for this work will besupplied by contractor.Inspection:Consignee.						
14	B	20.00	Numbers	928.28	18565.60	AT Par	18565.60
	Description:- Supply of Smoke Detector Tester Spray (200ml/117 gm) brand Aerol or Superior with a 3 feet throw.NON STAINING,NON-TOXIC,NO RESIDUE. Inspection:Consignee.						
15	B	50.00	Numbers	2377.11	118855.50	AT Par	118855.50
	Description:- Supply and installation of MS flat of on location box to earth pipe and signal unit to earth pipes and other S&T gear for earthing arrangement with proper nut & bolt of appropriate size. The material like nut and bolt washer and other requirement will be supply by the contractor .This item does not include supply and installation of earth pipe and its in closer.(Earthing should be as per Technical circular No PCSTE/NWR/01/2018) 3						
16	B	40.00	Numbers	217.51	8700.40	AT Par	8700.40
	Description:- Supply of drill bit of size 9/32" (7.2mm) twist drill morse shank suitable for making holes in rails. Contractor should get the approval of sample from railway engineer before supply. Inspection: Consignee .Inspection Charges: None Payment Terms: 100%after Supply.						
17	B	20.00	Pair	697.03	13940.60	AT Par	13940.60
	Description:- Supply of Rubber hand gloves suitable for 1500 Volts. ISI marked Tested certificate to IS: 4770-1968-91 as per IS:13774-1993. Make commander or Similar. Inspection by Consignee.						
18	B	10.00	Set	7153.64	71536.40	AT Par	71536.40
	Description:- Supply of RE Tool Kit for signal maintenance with following items (with small size can was log)(i). Insulated combination pliers of " =1 No (ii). Insulated long nose pliers (Road wise)6" = 1 No (iii). Insulated wise stroper piler 6" = 1No (iv). Insulated Screw driver set (5 piece) = 1set (v).Insulated "Side cutting plier 6" = 1 No(vi). Insulated Hex with frawise 12" = 1 No (vii).Insulated Double end spanner set (6 to 32mm) = 1 set (viii).Insulated Adjustable spanner set 8" = 1 No(ix). Insulated Ball pin hammer 200 gm = 1 No(x). Soldering iron 25 w= 1 No (xi). Torch cell LED (3cell) exeredy/Jeep= 1 No (xii). Auto Ranging digital multimode(Meeco/Rishabh) = 1No.Inspection by Consignee.						
	B	25.00	Numbers	41660.14	1041503.50	AT Par	1041503.50

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

19	Description:- Supply of 21/25 KHZ RX coils assembly suitable for GG Tronics make HASSDAC as per RDSO specification No.RDSO/SPN/177/2012 (ver.3) or latest (Warranty Period : Upto 30 months from thedate of supply) Inspection:RDSO						
20	B	22.00	Numbers	41660.14	916523.08	AT Par	916523.08
20	Description:- Supply of 21/25 KHZ TX coils assembly suitable for GG Tronics make HASSDAC as per RDSO specification No.RDSO/SPN/177/2012 (ver.3) or latest (Warranty Period : Upto 30 months from thedate of supply) Inspection agency: RDSO						
21	B	20.00	Numbers	37977.12	759542.40	AT Par	759542.40
21	Description:- Supply of HASSDAC Spares cards. Item : PD -1 21 KHZ CARD. Make : G.G.Tronics India Private Limited. Bengaluru-560058. (Inspection by :- RDSO)						
22	B	11.00	Numbers	35817.72	393994.92	AT Par	393994.92
22	Description:- Supply of HASSDAC Spares Cards. Item : PD-2 25 KHZ Card, Make : G.G.Tronics India Pvt. Ltd, Bengaluru-5600058. (Inspected by RDSO)						
23	B	10.00	Numbers	25856.32	258563.20	AT Par	258563.20
23	Description:- Supply of System card for UFSBI (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
24	B	6.00	Numbers	61600.00	369600.00	AT Par	369600.00
24	Description:- Supply of automatic media change over with built in modem card (webfil make) qty in pair.As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
25	B	10.00	Numbers	30276.96	302769.60	AT Par	302769.60
25	Description:- Supply of communiation driver card (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver0. or latest.						
26	B	10.00	Numbers	13002.08	130020.80	AT Par	130020.80
26	Description:- Supply of Input card (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
27	B	10.00	Numbers	13002.08	130020.80	AT Par	130020.80
27	Description:- Supply of feed back card (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
28	B	10.00	Numbers	25486.72	254867.20	AT Par	254867.20
28	Description:- Supply of output card (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
29	B	10.00	Numbers	38900.96	389009.60	AT Par	389009.60
29	Description:- Supply of PSU card (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
30	B	5.00	Numbers	20013.28	100066.40	AT Par	100066.40
30	Description:- Supply of display card with reset card (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
31	B	5.00	Numbers	38324.16	191620.80	AT Par	191620.80
31	Description:- Supply of back plane (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
32	B	10.00	Numbers	33813.92	338139.20	AT Par	338139.20
32	Description:- Supply of alarm extender card (webfil make).As per RDSO Specn. IRS:S-105/2012 Ver 0. or latest.						
33	B	15.00	Numbers	26514.60	397719.00	AT Par	397719.00
33	Description:- CPU card Compatible with existing Deltron UFSBI System.as per Specn. IRS:S-105/2012 Ver 0. or latest,						
34	B	15.00	Numbers	11525.06	172875.90	AT Par	172875.90
34	Description:- Supply of Input Card Compatible with Deltron Make UFSBI System as per Specn. IRS:S-105/2012 Ver 0. or latest, Make :- Deltron or Equal.						
35	B	15.00	Pair	54619.84	819297.60	AT Par	819297.60
35	Description:- MODEM CARDS COMPATIBLE WITH UFSBI SYSTEM OF DELTRON MAKE.as per Specn. IRS:S-105/2012 Ver 0. or latest,						
36	B	15.00	Numbers	22656.00	339840.00	AT Par	339840.00
36	Description:- Supply of CCC Card (Control Communication Card) compatible with existing Deltron make UFSBI system as per RDSO Specification No. IRS:S-105/2012. Make/Brand:- DELTRON, OEM.						

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less ; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet. As per Clause No. 10.2 of Tender Form (second Sheet) of Annex.I of Part-I of GCC2022,updated as per RB Letter No.2022/CEI/CT/GCC2022/Policy Dated-14.07.22 with up to date correction slip.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	a) The tenderer must have successfully completed or substantially completed anyone of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of the tender. (b) (1) In case of tenders for composite works (e.g. works involving more than one distinct component, such as Civil Engineering works, S&T works, Electrical works, OHE works etc. and in the case of major bridges substructure, superstructure etc.), tenderer must have successfully completed or substantially completed anyone of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of each component of tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of each component of tender, or (iii) One similar work each costing not less than the amount equal to 60% of advertised value of each component of tender. Note for b(1): Separate completed works of minimum required values shall also be considered for fulfillment of technical eligibility criteria for different components. (b) (2) In such cases, what constitutes a component in a composite work shall be clearly pre-defined with estimated tender cost of it, as part of the tender documents without any ambiguity. (b) (3) To evaluate the technical eligibility of tenderer, only components of work as stipulated in tender documents for evaluation of technical eligibility, shall be considered. The scope of work covered in other remaining components shall be either executed by tenderer himself if he has work experience as mentioned in clause 7 of the Standard General Conditions of Contractor through subcontractor fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract or jointly i.e., partly himself and remaining through subcontractor, with prior approval of Chief Signal & Telecom Engineer in writing. However, if required in tender documents by way of Special Conditions, a formal agreement duly notarised, legally enforceable in the court of law, shall be executed by the main contractor with the subcontractor for the component(s) of work proposed to be executed by the subcontractor(s), and shall be submitted along with the offer for considering subletting of that scope of work towards fulfillment of technical eligibility. Such subcontractor must fulfill technical eligibility criteria as follows: The subcontractor shall have successfully completed at least one work similar to work proposed for subcontract, costing not less than 35% value of work to be sub-letted, in last 5 years, ending last day of month previous to the one in which tender is invited through a works contract.	No	No	Allowed (Mandatory)

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

1.1	Note: for subletting of work costing up to Rs 50 lakh, no previous work experience of subcontractor shall be asked for by the Railway. In case after award of contract or during execution of work it becomes necessary for contractor to change subcontractor, the same shall be done with subcontractor(s) fulfilling the requirements as per clause 7 of the Standard General Conditions of Contract, with prior approval of Chief Signal & Telecom Engineer in writing. Note for Item 15.1: Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organization, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate.	No	No	Not Allowed
1.2	Meaning of similar works: " Any RRI/PI/EI/MACLS Supply ,Installation, Testing, Commissioning Signalling work OR Any RRI/PI/EI/MACLS Alterations Signalling work OR Any CTC/TMS Work."	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
-------	-------------

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)
---	---

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Submission of undertaking by the tenderer that "Authorization of OEM Kyosan Make EI system for Supply, Installation, Testing ,Commissioning and support after commissioning from OEM for trouble free working of installed EI system will be submitted before the supply of materials to confirm compliance with extent RDSO guidelines and to meet contract specific requirements" at the time of bidding. Non submission of undertaking will lead to summarily rejection of the bid.	No	No	Allowed (Mandatory)

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Certificate to be submitted by tenderer along with the tender documents as per Annexure-II & Annexure-II(A) attached in tender Document.	Yes	Yes	Allowed (Mandatory)
2	Declaration regarding constitution of firm & Bank Details as per Annexure-I attached in tender Document.	Yes	Yes	Allowed (Mandatory)
3	Mandatory undertaking Regarding Employment/ Partnership of Retired Railway Employees as per Annexure - XXIII attached in Tender Document.	Yes	Yes	Allowed (Mandatory)
4	Relevant Annexure is to be submitted in connection with status of their firms. i. e. Either for Sole Proprietorship/Partnership/Company registered under companies Act 2013/LLP (Limited Liability Partnership)) Registered under LLP Act 2008/Registered Society and Registered Trust/HUF (Hindu undivided Family) Firm's. Prescribed Format (Relevant Annexure) as per Firm's status is attached in tender document as per clause 16.2	Yes	Yes	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	SNT-AII-33-2025-26Re-tenderUDZSHUNTINGNECK.pdf	tender document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

**AJMER DIVISION-S AND T/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: SNT-AII-33-2025-26Re-tend

Closing Date/Time: 17/02/2026 15:30

Signed By: VIPIN BIHARI SHARMA

Designation : DSTEAll