

Closing Date/Time: 26/02/2026 11:00

1. NIT HEADER

Name of Work	Infringement Removal and associated activity in relation to engineering work from Rampurhat to Dumka(excluded) length 64 Km of Howrah Division of Eastern Railway in connection with Bhagalpur - Dumka- Rampurhat Doubling (177 Km).		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Two Packet System
Tender Closing Date Time	26/02/2026 11:00	Date Time Of Uploading Tender	04/02/2026 16:15
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	456036617.77	Tendering Section	SNT/C/HWH
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	2430200.00	Validity of Offer (Days)	90
Tender Doc. Cost (Rs.)	0.00	Period of Completion	12 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	12/02/2026		
Are JV allowed to bid	Yes	Number of JV Member Allowed	3
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 01-Group-A (Revised SOR(S&T)-Nov.'2023 Items)							275254842.77	Above, Below/P a
	010102	360.00	Per Functional Vital Bit	72036.00	25932960.00	11.09	28808925.26	

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

1	Description:- "Design, manufacture and supply of Electronic Interlocking (EI) system complete with architecture of EI i.e. Distributed or Centralized as per the requirement of Zonal Railway, as per RDSO specification No.RDSO/SPN/ 192/2019 Ver. 2 or RDSO/SPN/203/2011 Ver. 1 for Big Yard having more than 200 Routes or latest or as per approval of PCSTE for specification to be adopted and from RDSO approved source only and as per special conditions of contract mainly consisting of Microprocessor Equipment, Interface Equipment, EI vendor specific Interfacing Relays , In-built event Logger, In-built Power Supply equipment, Racks (Only Relay Rack/EI Rack), Indoor cables, Wires, Fuses , Fixtures, Mounting arrangements along with all accessories required to make complete EI system functional. Design of indoor EI system should be compatible as per outdoor interlocking requirement based on Signal Interlocking Plan & Selection Table of station/yard and will be done by OEM after following all theof cards are not to be submitted as per latest guidelines of Railway Boardguidelines/directives issued by RDSO from time to time as per RE requirements , hot standby with Dual VDU [two nos. of industrial grade high resolution VDUs (Note: Size of VDU to be provided shall be based on the no. of routes, (i)For less than 100 Routes-55"" LED based VDU with 4K resolution suitable for 24x7 application,(ii)For more than 100 routes and less than 200 Routes-65"" LED based VDU with 4K resolution suitable for 24x7 application,(iii)For more than 200 routesLarger size of LED based VDU with 4K resolution suitable for 24x7 application or array of LED panel with minimum/zero bezel or video wall with redundant controller in hot standby configuration, as specified by purchaser is to be provided) conforming to SIL-II certification for operator console at central location, Maintenance Terminals (Size of VDU should be same as for operator VDU as indicated in (i) &(ii), however for (iii) purchaser will specify) along with laser printer at central & goomtys locations housing for EI equipment and Relay Racks, Fixture, mounting arrangements and accessories necessary to make the EI system functional, Tentative SIP is enclosed for station. This provision of hot-standby arrangement must have the supply, installation and commissioning of associated cards for the above arrangement such as communication card, synchronization card and others cards as required with supply & installation of supporting software and drives etc. also optical Fiber link with loop back (Protection ring) between center to goomtys. Breakup of (i) each type of main equipment module/cards (ii) each type of vendor specific relays(iii) dc-dc converters of all voltages (iv) switches, connectors, fuses, couplers. (v) consumables for wiring material & communication equipment required should also be quantified in the breakup. (module wise rates, inspection authority and quantity should be given in separate sheet.), without which offer will not be considered. Embedded industrial grade fan less PCs should be of rugged and reliable type like MOXA series V 2406, Kontron MPCX28R, MEN BC50M or latest with compact flash drives in non-AC and in normal environment to be used. Minimum requirement of Embedded PC for EI shall be as per RDSO Specification."For Station with routes more than 50 and less than 200 routes (Station : Shikaripara , Harinsing)"						
2	010104	2.00	Station	596262.00	1192524.00	11.09	1324774.91
	Description:- "Installation, wiring, testing (FAT & SAT) and commissioning of EI System with 'Hot Standby' architecture as supplied above item-100101/2/3. It includes transportation of material from consignee's depot to the site, erection and grouting of EI Relay Racks, fixing and wiring of all the interfacing relays (Vital & NonVital), installation and wiring of Microprocessor equipment, interface equipment, power supply equipment and all other associated accessories to make complete EI system to be functional. Note: (i) Technical Requirements are attached with tender document (ii) Contractor has to arrange simulator/simulation testing panel for testing and commissioning by Selection Table and Square Sheet for each Signalling function. (iii) Installation, wiring, testing and commissioning of EI system will be done by OEM after following all the guidelines/directives issued by RDSO from time to time"						
3	010301	2.00	Numbers	82918.00	165836.00	11.09	184227.21
	Description:- Supply of portable work station to run along with EI configuration tools, data input, simulation and functional testing, diagnostics and trouble shooting and commissioning of EI System. It also includes supply of Laser Printer (Only branded). The minimum configuration of workstation should be Intel i5 with 8 GB RAM,500 GB HDD and 15 inches LED display of standard make such as Dell/HP/Lenovo or Equivalent with required software as mentioned above and compatible ports to connect with EI. Detailed Technical Specifications should be attached with the tender document by Tendering authority. Inspection: Consignee						
4	010401	2.00	Station	234164.00	468328.00	11.09	520265.58
	Description:- "Maintenance supervision of Electronics Interlocking equipment for one years from the date of expiry of free maintenance period as per conditions of contract, as per the details given in special condition of contract agreement, as per the latest guidelines of PCSTE, and provision mentioned in Signal Engineering Manual. All the records are to be maintained as per latest circulars prevailing in the Division. During maintenance at least two expert personnel from the firm should be available at the station round the clock. NOTE-This item will be operated separately and will not restrict closure of contract. Separate bank guarantee will be submitted for this schedule item if require"						
5	010501	30.00	Man-Days	2901.00	87030.00	11.09	96681.63
	Description:- "Training of Railway Personnel by OEM for installation, Commissioning, Testing, troubleshooting & making changes in application data and logics by railway officials to suit yard modification done at later stage including documentation. (Hard copies of training material/ course modules to be given to each participant)"						

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

6	010601	4.00	Numbers	369001.00	1476004.00	11.09	1639692.84	
	Description:- "Supply, Installation, wiring, testing and commissioning of embedded fan less PC with VDU for control terminal/maintenance terminal as per RDSO spec. No. RDSO/SPN/192/2019 Ver. 2 or latest. Note: (i) Technical requirements & size of VDU shall be mentioned in the tender document"							
7	011001	3.00	Lot	12214.00	36642.00	11.09	40705.60	
	Description:- Design of circuits and plans to suit layout given in the signalling plan of IBS/ABS/LC GATE. All plans and wiring diagram shall be prepared on Auto Cad Drawing and supplied with CD. This will include supply of Control cum Indication panel diagram, Route section plan, square sheet, wiring diagrams, Relay rack/Relay arrangements, Bus bar details, Fuse analysis, contact analysis, Relay room tag block analysis, panel tag block analysis, Power panel diagram, IPS wiring diagram, Auto change over diagram, Power equipment arrangement with program switch, Block circuit wiring diagram, Digital Axle counter wiring diagram and all other relevant drawings. NOTE: The contractor shall initially supply 2 sets of documents (Paper Prints) for approval of Railways. Railway will return one set to the contractor duly approved with alterations/corrections, if any. The contractor shall incorporate Railways' alterations/ corrections/ comments, if any, in the tracing & CD without any deviation and submit all the tracings and Final CD complete with all respect for Approval of Railways. After Approval of Railways on the tracings, the contractor shall submit 3 sets of final approved diagrams to the Railways within 15 days. He shall ensure that each sheet has a block for signature of railway official as well as a block for signature of firm, duly signed by the authorized signatory of the firm. The name of the work as given by Railways shall be written on every sheet under the work column. All the drawing shall be supplied in a good quality folder for each IBS/ABS/LC Gate.							
8	011101	2.00	Station	58797.00	117594.00	11.09	130635.17	
	Description:- Design of circuits in connection with preparation of wiring diagrams as per approved Signalling Plan and submission of indoor as well as outdoor completion documents for alteration work. It includes Route Section Plan (RSP), Selection Table (ST), Locking Table (LT) and Control Panel Diagram (CPD). Two copies of prints with soft copy will be submitted to Railway for checking. If alterations are suggested/proposed by Railways, then again two copies of prints will be submitted for advance approval after carrying out all the alterations as suggested/proposed by the Railways. Tracings will be submitted for all the diagrams mentioned above for the purpose of approval by Railway prior to commissioning of station. All drawings will be prepared in CAD. The wiring diagrams will consist relay rack analysis, relay contact analysis, fuse details. Tag block analysis etc. A separate CD/Pen drive will be submitted to Railway for each station along with original tracings. It also includes preparation and supply of laminated one set of all completion plans including circuit diagrams and indoor as well as outdoor completion documents on standard 75-micron polyester film for station in Auto CAD. 6 (Six) sets photo copies will be submitted for each of the documents mentioned below: Cable Route Plan, Cable Core Chart, Location details plan for all the locations, Cable termination details, Signalling Plan, SWR Diagram, Wiring Diagrams, Selection Table, Locking Table, Contact Analysis, Fuse and Tag Block Analysis of Relay Rack and CT Rack, Control Cum Indication Panel, Power Panel Diagram, Track Circuit Plan, Rack Erection Plan and Junction Box details etc. Note: Total cost of design and completion documents for a station/yard will be calculated on basis of total possible movements/routes as per Selection Table (ST). Note: (i) This should comply ANNEXURE-010100 of SOR in special condition of contract Pt. No. 4.3.3 as applicable. (ii) EI Annexure at pt. No. 4.3 as given in Special Conditions of Contract is to be followed during execution of this item.							
9	020201	3.00	Numbers	496233.00	1488699.00	11.09	1653795.72	

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

10	Description:- Supply of Micro Processor based Data Logger System with 1024 digital and 32 analog inputs with DOT Matrix Printer,80 COL as per RDSO Spec. No. IRS (S) 99/2006 with Amdt. 3.0 or latest. It includes supply of all the items required for complete indoor relay room wiring from data logger to relay rack tag blocks, drawing/extension of power supply up to Data Logger. It includes relay room door lock checking arrangement, commercial power supply monitoring arrangement & monitoring of DG sets, ELD, IPS, UFSBI, BI, interlinking and networking of Data logger. It also includes supply of leased line MODEM and other interfacing cards, if required for networking of Data logger. This also includes supply of one no. composite computer with The minimum specification should be as given core i7 or higher version processor (speed 3.2 GHZ, 4 MB cache memory),8 GB RAM,2TB HDD or Higher, Two front and four rear USB port,1 Serial & 1 Parallel Port,1VGA Port,21" LED Colour Monitor (HP/DELL or equivalent) or Bigger Size, Sound Card with Speaker,1000 MBPS Network Card, Keyboard, Optical Mouse,10/100 T Lan Card, Combo Drive, Microsoft Windows 10 Licensed OS with Licensed (Antivirus, MS Office etc.),UPS 750 VA with 30 Minutes minimum backup(APC/Microtek or Equivalent), LaserJet Printer(HP Pro 1108 or superior)and printer table (Godrej work station table or similar) for keeping processor module workstation and one number Godrej operator chair Model PCH7001 or similar. Note: (1) Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No.STS/E/Data logger dtd.12.09.2011 or latest guidelines of Railway Board/RDSO/Zonal Railway. (2) Exceptional reports are to be generated by a computer connected to datalogger at the station and at a central location in Control Room. Datalogger software should be able to generate exceptional reports for maintenance, safety and operations as per latest guidelines of Railway Board/RDSO/Zonal Railway. Datalogger to be installed at Site by OEM. Manufacturing date of datalogger/RTU and printer should be of current year at the time of supply. Inspection: Consignee (For Furniture, PC,Printer and Accessories) Inspection: RDSO(For Data Logger and accessries) Inspection: RDSO for Datalogger. Inspection: Consignee for Printer & other items.						
	020202	3.00	Numbers	31637.00	94911.00	11.09	105436.63
	Description:- Supply of 24V power supply with Charger as per RDSO Spec. No. IRS-S-93/96B with Amdt.1 or latest with battery backup of 80AH capacity for data logger. Material to be procured from RDSO's approved source only. Inspection: -Consignee						
	020203	2.00	Numbers	24433.00	48866.00	11.09	54285.24
	Description:- Supply of Dual Leased Modem internal card to fit in central processing unit rack for networking of data logger system of other stations. Each set shall comprise of one pair of modem and shall have data compatibility 1TUV 21, V2, V22 BITS, V23V23A, B V25 BITS, V32, V32 BITS V42, V42 BITS, suitable to work in either ofc media or microwave or quad cable. Inspection: Consignee.						
11	020204	3.00	Numbers	51876.00	155628.00	11.09	172887.15
	Description:- Installation, wiring, testing & commissioning of Micro Processor based Data Logger System with 1024 digital and 32 analog inputs as per RDSO Spec. No. IRS (S) 99/2006 or latest It cover complete indoor relay room wiring from data logger to relay rack tag blocks, drawing/extension of power supply up to Data Logger. It includes relay room door lock checking arrangement, commercial power supply monitoring arrangement & DG sets, ELD, IPS, UFSBI, BI interlinking and networking of Data logger. All material required for wiring, networking, power supply monitoring, door-locking arrangement etc. will be supplied by contractor. Note: Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No.STS/E/Data logger dtd.12.09.2011 or latest guidelines of Railway Board/RDSO/Zonal Railway. Networking of data logger includes extraction of data report from Control room. Exceptional reports are to be generated by a computer connected to datalogger at the station and at a central location in Control Room. Datalogger software should be able to generate exceptional reports for maintenance, safety and operations as per latest guidelines of Railway Board/RDSO/Zonal Railway. Datalogger to be installed at Site by OEM.For networking, required communication channel (Quad/ OFC cable) will be arranged/provided by Rly in SM/ASM's room or in OFC/AUTO/EI Huts and it will be extended by contractor up to location of data logger by using CAT-5/6 telecom cable with proper casing and capping. The contractor will supply all the material like CAT-5/6 telecom cable, casing & capping, nuts, bolts etc. The final commissioning will be done after filling up of Pre- Commissioning checklist (circulated by RDSO) with the OEM representative. Datalogger to be validated and commissioned before simulation test and put in network, validation statement should be jointly signed by railway engineer (open line), railway engineer (construction) & OEM'S engineer before simulation test with name, designation and date. Payment for this item will be released only after submission of duly signed pre-commissioning checklist of data logger in standard RDSO format, joint signature of validation statement. OEM'S engineer will also impart training to rly staff at site for proper functioning /working and applications of data logger.Inspection: Consignee.						
12	020701	3.00	Numbers	116554.00	349662.00	11.09	388439.52

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

13	Description:- Supply of Failure Analysis System (FAS) with Fault Analysis Software (Datalogger Analyser) consisting of a PC (Make- Dell /HP or Equivalent) as per Technical Specifications. The specification of FAS should be got approved from the Engineer in charge before supply. Note: The minimum specification should be as given core i7 or higher version processor (speed 3.2 GHZ, 4 MB cache memory), 8 GB RAM, 2TB HDD or Higher, Two front and four rear USB port, 1 Serial & 1 Parallel Port, 1VGA Port, 21" LED Colour Monitor (HP/DELL or equivalent) or Bigger Size, Sound Card with Speaker, 1000 MBPS Network Card, Keyboard, Optical Mouse, 10/100 T Lan Card, Combo Drive, Microsoft Windows 10 Licensed OS with Licensed (Antivirus, MS Office etc.), UPS 750 VA with 30 Minutes minimum backup (APC/Microtek or Equivalent), Laserjet Printer (HP Pro 1108 or superior). Inspection: Consignee						
14	030102	20.00	Numbers	1591.00	31820.00	11.09	35348.84
	Description:- Relay fail safe electronic time delay device with fixed timing (0 -120) seconds and conforming to RDSO Specn.No.IRS: S-61/2000 with Amnd.2 and IRS: S-34 & S-23 with Amdt. up to date or latest mounted on Q-series relay base & covered complete with connectors, retaining clip etc. The interlocking code for this unit shall be "AFGKY". Inspection:- RDSO						
15	030103	20.00	Numbers	2118.00	42360.00	11.09	47057.72
	Description:- "Relay fail safe electronic time delay device with fixed timing (0 - 60) seconds and conforming to RDSO Specn.No.IRS: S-61/2000 with Amnd.1 or latest mounted on Q-series relay base & covered complete with connectors, retaining clip etc. The interlocking code for this unit shall be ""AFHKY"". Inspection authority:- RDSO "						
16	030302	600.00	Numbers	3737.00	2242200.00	11.09	2490859.98
	Description:- Q-Series Neutral Line Relay (QN1 Type), 8F/8B, 24V DC complete with plug board (base plate), connectors and retaining clips etc and conforming to BRS- 930 and RDSO Specn.No. IRS: S-34 & S-23 with Amdt. upto date as applicable or latest. The interlocking code for this unit shall be "ABCDF". Inspection authority:- RDSO						
17	030501	100.00	Numbers	5718.00	571800.00	11.09	635212.62
	Description:- Q-Series Magnetically Latched Neutral Line Relay (QL1 Type), 11F/4B, 24V DC complete with plug board (base plate), connectors and retaining clips and conforming to BRS-935A and RDSO Specn.No.IRS: S-34 & S-23 with Amdt. upto date as applicable or latest. The interlocking code for this unit shall be "ABDEG". Inspection authority:- RDSO						
18	031201	20.00	Numbers	6554.00	131080.00	11.09	145616.77
	Description:- "Track Relay QBAT, AC immunized, 2F-2B contacts, 9 ohms. Complete with plug board, retaining clip & connectors as per RDSO/SPN/84 Ver 2.0 or latest. The interlocking code for this unit shall be ""ABEJX"". Inspection authority:- RDSO"						
19	030801	64.00	Numbers	4912.00	314368.00	11.09	349231.41
	Description:- Q-Series LED ECR (Universal Type i.e. QECX-61), 4F/4B complete with plug board (base plate), connectors, retaining clips etc and conforming to BRS:941A STS/E/RELAYS/AC LIT LED SIGNAL/09-2002, Amdt. -1 and RDSO Specn.No.IRS:S-34 & S-23 with Amdt. upto date as applicable or latest. The interlocking code for this unit shall be "ABDHK". Inspection authority:- RDSO						
20	031301	100.00	Numbers	3845.00	384500.00	11.09	427141.05
	Description:- Q-Series Line Relay (QNA1 Type), AC immunized, 8F/8B, 24 V DC along with plug board (base plate), connectors, retaining clips etc and conforming to BRS-931A and RDSO Specn.No.IRS:S-34, S-23 and S-60 or latest. The interlocking code for this unit shall be "ABDGH". Inspection authority:- RDSO						
21	031401	40.00	Numbers	3815.00	152600.00	11.09	169523.34
	Description:- Q-Series Track Relay (QTA2 Type), AC immunized, 9 Ohms, 2F/1B along with plug board (base plate), connectors, retaining clips etc and conforming to BRS:939A & 966(Appendix F2) and RDSO Spec No. IRS:S-34, S-23 with amdt. upto date as applicable or latest with latest amdt. or latest. The interlocking code for this unit shall be "FGHKX". Inspection authority:- RDSO						
22	031501	40.00	Numbers	5230.00	209200.00	11.09	232400.28
	Description:- Q-Series Neutral Line Relay (QSPA1 Type), 24V DC, 8F/4B along with plug board (base plate), connectors, retaining clips etc and conforming to BRS-933A and RDSO Specn. No.IRS:S -34, S-23 & S 60 with amdt. upto date as applicable or latest. The interlocking code for this unit shall be "ABDEJ". Inspection authority:- RDSO						
23	031601	20.00	Numbers	6842.00	136840.00	11.09	152015.56
	Description:- Contactor Unit (QBCA1 Type), 24 V DC, 2F(HD)/4B or 2F(HD)2F-4B complete with plug board (base plate), connectors, retaining clips etc and conforming to BRS- 943 and RDSO Specn.No.IRS:S-34 & S-23 with amdt. upto date as applicable or latest. The interlocking code for this unit shall be "BCEJK" or "DEHJX". Inspection:- RDSO						
24	031702	60.00	Numbers	8035.00	482100.00	11.09	535564.89
	Description:- "Key Lock Checking Relay (KLCR) working on 24V DC, AC Immunized with different ward combinations and contact configuration 4F/4B with 6 extra ward plates and with case, RDSO spec no. RDSO/SPN/219/2016 ver 1.0 or latest, confirming to IRS S-23, S-34 & S -60 IRS S:46. Inspection authority:- For bare relay -Consignee. for key lock housing- consignee "						
	040202	400.00	Metre	119.00	47600.00	11.09	52878.84

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

25	Description:- "Supply of 1 x 10 Sq.mm. (Red/Black/Green) multi strand copper power wire as per IS: 694:2010 or latest, 140 conductor each dia 0.30mm +/- 0.01 with insulation thickness of 1.0 mm and nominal conductor resistance of 1.91 ohms/km and test parameters as per RDSO Specn.No.IRS-S- 76/89(Amnd.3) or latest. Color of the wire which is required will be specified by the Engineer in-charge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board."						
26	040205	200.00	Numbers	177.00	35400.00	11.09	39325.86
	Description:- "Supply of 1 x 35 Sq.mm. (Red/Black/Green) multi strand copper power wire as per IS: 694:2010 or latest, 276 conductor each dia 0.40mm +/- 0.01 with insulation thickness of 1.2 mm and nominal conductor resistance of 0.554 ohms/km and test parameters as per RDSO Specn.No.IRS: S- 76/89(Amnd.3) or latest. Color of the wire which is required will be specified by the Engineer in charge. Inspection: (i) RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board."						
27	040501	6.00	Numbers	25535.00	153210.00	11.09	170200.99
	Description:- Installation and wiring of relay rack as per DRG.NO.S&T/C-20/2001 with modification vide CSTE/ER'S LETTER NO.SG.42/9, DT.15/3/2016. Supply and fixing of fuses with base, diodes; resistances; condensers, terminal strips / tag blocks, bus bars & other equipment's required for the approved system design complete with scaffolding materials & required hardware & erection materials to accommodate 100 relays (station wise quantity to be specified by the tenderer). PVC wire as per RDSO SPEC.IRS-S-76/89, AMD-2 or latest (for wiring of relay rack) shall be supplied by the contractor, duly inspected by RDSO. This includes supply of relay rack to accommodate 100 relays complete with fittings as per DRG.NO.S&T/C-20/2001. Note: - this includes status of relay to be indicated through led indication at the top of relay rack and in this connection all the required materials to be supplied by the contractor. Rack to be fixed on rubber pad. Supply. Inspection:RITES						
28	040502	6.00	Numbers	83032.00	498192.00	11.09	553441.49
	Description:- Installation and wiring of relay rack as per DRG.NO.S&T/C-20/2001 with modification vide CSTE/ER'S LETTER NO.SG.42/9, DT.15/3/2016. Supply and fixing of fuses with base, diodes; resistances; condensers, terminal strips / tag blocks, bus bars & other equipment's required for the approved system design complete with scaffolding materials & required hardware & erection materials to accommodate 100 relays (station wise quantity to be specified by the tenderer). PVC wire as per RDSO SPEC.IRS-S-76/89, AMD-2 or latest (for wiring of relay rack) shall be supplied by the contractor, duly inspected by RDSO. This includes supply of relay rack to accommodate 100 relays complete with fittings as per DRG.NO.S&T/C-20/2001. Note: - this includes status of relay to be indicated through led indication at the top of relay rack and in this connection all the required materials to be supplied by the contractor. Rack to be fixed on rubber pad. Execution.						
29	040601	10.00	Numbers	44924.00	449240.00	11.09	499060.72
	Description:- Installation of cable termination rack with scaffolding materials ladder for supporting outdoor cable; wire guide complete with other necessary hardware as per requirements of rly. & erection materials. Wires to be procured from RDSO's approved firm only. This includes supply of cable termination rack as per DRG.NO. S&T/C- 17/2001 OR latest with screw less disconnect type connectors (Wago/Phoenix/Similar) , scaffolding materials, ladder for supporting outdoor cable, wire guide, NDT fuse complete with other necessary hardware as per requirements of railway & erection materials. Supply. Inspection: RITES						
30	040602	10.00	Numbers	5790.00	57900.00	11.09	64321.11
	Description:- Installation of cable termination rack with scaffolding materials ladder for supporting outdoor cable; wire guide complete with other necessary hardware as per requirements of rly. & erection materials. Wires to be procured from RDSO's approved firm only. This includes supply of cable termination rack as per DRG.NO. S&T/C- 17/2001 OR latest with screw less disconnect type connectors (Wago/Phoenix/Similar) , scaffolding materials, ladder for supporting outdoor cable, wire guide, NDT fuse complete with other necessary hardware as per requirements of railway & erection materials. Execution.						
31	040701	500.00	Numbers	78.00	39000.00	11.09	43325.10
	Description:- Supply of PBT ARA terminal as per IRS SPECN.NO. IRS: S-75-2006(REV-2) OR LATEST. Material to be procured from RDSO's approved firm only. Inspection: RDSO. 1 WAY,DRG.NO.23741A, ALT-4.						
32	040702	6000.00	Numbers	485.00	2910000.00	11.09	3232719.00
	Description:- Supply of PBT ARA terminal as per IRS SPECN.NO. IRS: S-75-2006(REV-2) OR LATEST. Material to be procured from RDSO's approved firm only. Inspection: RDSO. 6 WAY, DRG.NO.23756,ALT-3.						
33	040801	300.00	Numbers	61.00	18300.00	11.09	20329.47
	Description:- Supply of fuse block (PBT) to spec.no.IRS-S-75/2006(REV-2) OR LATEST,DRG.NO.SA-23748 with fuse inserts cartridge, non-deteriorating type to spec.IRS-S-78/92 with latest amendment, to be mounted inside the location box on hylum sheet. Inspection: -RDSO. Fuse, non-deteriorating(2A/6A/10A/16A) type, cylindrical(IRS-S-78/92) [quantity as per site requirement]						
	040802	300.00	Numbers	178.00	53400.00	11.09	59322.06

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

34	Description:- Supply of fuse block (PBT) to spec.no.IRS-S-75/2006(REV-2) OR LATEST,DRG.NO.SA-23748 with fuse inserts cartridge, non-deteriorating type to spec.IRS-S-78/92 with latest amendment, to be mounted inside the location box on hylum sheet. Inspection: -RDSO. Fuse Base.						
	041301	12000.00	Per Conductor	9.00	108000.00	11.09	119977.20
35	Description:- Termination of Outdoor Cables (Main Cables /tail cables) at both ends in location boxes, cable termination rack in relay room, station building, generator room etc. The item includes dressing of cables and wires with dressing threads as per standard practice. All material required for this item will be supplied by contractor. The outdoor cable shall be terminated in Relay Room, DG Room, ASM Room etc under supervision and instructions issued by Engr. incharge of the work. Inspection: Consignee						
	041402	12000.00	Numbers	10.00	120000.00	11.09	133308.00
36	Description:- Supply of Disconnect Terminal Block, Screw less type, as per RDSO Spec. No. RDSO/SPN/189/2004(Modular Terminal Blocks, Fuse Terminal Blocks &Miniature fuse link of international standard for Railway signalling) With latest amendments.Inspection: Consignee Supply of End plate 2.5mm/0.091 in thick as per site requirement.						
	041403	200.00	Numbers	10.00	2000.00	11.09	2221.80
37	Description:- Supply of End Stopper 10mm/0.0394 in width as per site requirement.						
	041404	100.00	Metre	109.00	10900.00	11.09	12108.81
38	Description:- Supply of Carrier Rails for above 35mm x 7.5mm, 1mm/0.039 in thickness un-slotted type as per site requirement.						
	041405	4000.00	Numbers	16.00	64000.00	11.09	71097.60
39	Description:- Supply of Markers strip.						
	041406	12000.00	Numbers	56.00	672000.00	11.09	746524.80
40	Description:- Supply of Disconnect Terminal Block, screw less type, 2-wire front entry (One in-put & One out-put) The colour will be decided by Engineer - in - Charge. (Preferably In Blue, Red & Grey Colors in the ratio of 1:2:3)						
	041407	1000.00	Numbers	2.00	2000.00	11.09	2221.80
41	Description:- Supply of shorting link (jumper) (part no - 283-402 or similar), suitable for 0.2 to 16 sqmm terminal block 283-901 or similar.						
	041408	100.00	Numbers	189.00	18900.00	11.09	20996.01
42	Description:- Supply of Fuse terminal block with LED indication up to 2.5 sq.mm screw type one in one out (suitable for (400 mA, 630mA, 1A. 1.6A, 2A, 4A, 6.3A & 10A) as per RDSO/SPN/189/2004 (without fuse).						
	041409	100.00	Numbers	45.00	4500.00	11.09	4999.05
43	Description:- Supply of Fuse links of (400 mA, 630mA, 1A. 1.6A, 2A, 4A, 6.3A & 10A)						
	041801	100.00	Per Relay	270.00	27000.00	11.09	29994.30
44	Description:- Carrying out relay alteration to the existing relay wiring at relay rack/location box as per the approved circuit diagram. These work includes the releasing of existing unused wires and wiring the relays using 16/0.2 mm copper wire as per RDSO Spec. Wire to be procured from RDSO's approved source and inspection: by RITES [for value of material above Rs. 5.0 lakhs.]. Inspection by consignee [for value of material below than Rs 5.0 lakh]. Note: - wire to be procured from RDSO's approved source only. All required material like wire, soldering material, paint etc. To be supplied by the contractor for execution of the work.						
	041901	3.00	Station	131515.00	394545.00	11.09	438300.04
45	Description:- Inter connection wiring with ladder arrangement from control panel to IPS to relay rack, battery & CTR. This includes interconnection, wiring with ladder arrangement between relay racks, CTRS, control cum indication panel and relay rack tag blocks for data logger. This also includes termination of cables / wires on all the above and dressing, bunching etc. As required at site. 16 sq. mm. cable to be used between IPS & it's battery duly soldered with good quality lugs in duplicate. From relay rack to panel wire should be of 40/60 core multicore cable of 1 sq.mm., 0.5mm dia., 16/0.2 mm for relays, 3/0.75 mm for MCBS and 10 sq.mm for power wiring. Indoor cable will be 60 x 1 mm /40 x 1 mm as per IRS-S-76/89, amd-2 or latest for interconnection. Supply of wires / cables by the contractor, shall be procured from RDSO's approved firm only & to be duly inspected. Note:1) necessary 40/60 multicore, 16/0.2 mm, 3.0.75 mm, 10 sq.mm cables required for wiring to be supplied by the contractor. 2)to suite load requirement necessary re-arrangement of DC-DC converters by OEM of IPS .Note: For payment purpose EI hut or any other installation having complete IPS Room, Relay Room, Battery room etc. will be considered as a station. Up to 6 Lines Station						
	041902	1.00	Station	69824.00	69824.00	11.09	77567.48

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

46	Description:- Inter connection wiring with ladder arrangement from control panel to IPS to relay rack, battery & CTR. This includes interconnection, wiring with ladder arrangement between relay racks, CTRS, control cum indication panel and relay rack tag blocks for data logger. This also includes termination of cables / wires on all the above and dressing, bunching etc. As required at site. 16 sq. mm. cable to be used between IPS & it's battery duly soldered with good quality lugs in duplicate. From relay rack to panel wire should be of 40/60 core multicore cable of 1 sq.mm., 0.5mm dia., 16/0.2 mm for relays, 3/0.75 mm for MCBS and 10 sq.mm for power wiring. Indoor cable will be 60 x 1 mm /40 x 1 mm as per IRS-S-76/89, amd-2 or latest for interconnection. Supply of wires / cables by the contractor, shall be procured from RDSO's approved firm only & to be duly inspected. Note:1) necessary 40/60 multicore, 16/0.2 mm, 3.0.75 mm, 10 sq.mm cables required for wiring to be supplied by the contractor. 2)to suite load requirement necessary re-arrangement of DC-DC converters by OEM of IPS .Note: For payment purpose EI hut or any other installation having complete IPS Room, Relay Room, Battery room etc. will be considered as a station. Alteration Work						
47	042001	16.00	Numbers	6621.00	105936.00	11.09	117684.30
	Description:- Dismantling of Microlok rack, relay rack , cable termination rack of existing relay room and equipments of existing panel room & power room etc.						
48	050202	3.00	Numbers	1183104.00	3549312.00	11.09	3942930.70
	Description:- Supply, Installation and Commissioning of SMPS based Integrated power supply (IPS) system as per RDSO Spec. No. RDSO/SPN/165/2023 (Ver4.0) with latest amendment if any and also as per Sketch No. DO/IPS/SMPS/6L RE-002 or Latest along with 300AH Low maintenance lead acid cell as per E. Rly. Practice. Inspection: RDSO						
49	050204	20.00	Numbers	24351.00	487020.00	11.09	541030.52
	Description:- Supply of IPS DC-DC converter 24-32V DC, 5 Amp /10 Amp or 60-66 V DC, 5 Amp or 60-100V DC,1 Amp/ 3 Amp/ 5 Amp as per specification No. RDSO/ SPN/ 165/ 2025, version-4.0 or latest. Make: M/s. Statcon Ltd. M/s. HBL Ltd./M/s. Amararaja Ltd. Or Other RDSO approved make, compatible for the IPS make specified by Purchaser. Inspection: Consignee						
50	050502	120.00	Numbers	3574.00	428880.00	11.09	476442.79
	Description:- Supply of uncharged Low Maintenance Lead Acid (LMLA) secondary cell, shelf mounting type conforming to RDSO Specn.No.IRS:S-88/2004 or latest with inter cell connectors, nuts and bolts etc. Inspection: RDSO 2V, 80 AH						
51	050505	120.00	Numbers	7062.00	847440.00	11.09	941421.10
	Description:- Supply of uncharged Low Maintenance Lead Acid (LMLA) secondary cell, shelf mounting type conforming to RDSO Specn.No.IRS:S-88/2004 or latest with inter cell connectors, nuts and bolts etc. Inspection: RDSO 2V, 300AH						
52	050602	120.00	Numbers	367.00	44040.00	11.09	48924.04
	Description:- Charging of lead acid cell (Secondary cell) of various capacities as per Manufacturer's/ Railway engineer's instruction. Acid and distilled water to be supplied by the contractor. Specific gravity acid should be approved type duly inspected by consignee. This includes installation and commissioning of battery in circuit. Battery to be kept on wooden rack. Inspection: Consignee. 2V, 80 AH						
53	050605	120.00	Numbers	987.00	118440.00	11.09	131575.00
	Description:- Charging of lead acid cell (Secondary cell) of various capacities as per Manufacturer's/ Railway engineer's instruction. Acid and distilled water to be supplied by the contractor. Specific gravity acid should be approved type duly inspected by consignee. This includes installation and commissioning of battery in circuit. Battery to be kept on wooden rack. Inspection: Consignee. 2V, 300/500 AH						
54	051401	9.00	Numbers	24449.00	220041.00	11.09	244443.55
	Description:- Supply and installation of lightning and surge protection device both Class 'B' & Class 'C' between line and neutral and neutral & earth of approved type. Inspection: Consignee						
55	060201	2.00	Numbers	6716.00	13432.00	11.09	14921.61
	Description:- Supply of Ground Connection [BG] Threaded Type for IRS type Point Machine, as per CWM/Signal Workshop/Howrah/E. Rly. drawing number, Sl. No., Description of Drawing & CWM/SW/HWH's Drawing No. mentioned below: - 1. Detector Rod (Far End) - BS/29/721 with ALT-1 Detector Rod (Near End)- BS/29/722 with ALT-1. 2. Lock Rod (Far End) - BS/29/723 with ALT-1, Lock Rod (Near End) - BS/29/724 with ALT-1. 3. Switch Extension Bracket - BS/29/725 with ALT-1. 4. Drive Rod - BS/29/726 with ALT-1 Drive Lug- BS/29/726 A with ALT-1. 5. Sleeve- BS/29/726 B with ALT-1. 6. Lug- BS/29/726 C with ALT-1. 7. Pin- BS/29/726 D with ALT-1. 8. Sketch showing the Layout arrangement- BS/29/727 with ALT-1. Amdt. and alt. up to date if any. Inspection: Consignee Turn Out						
	060202	2.00	Numbers	5750.00	11500.00	11.09	12775.35

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

56	Description:- Supply of Ground Connection [BG] Threaded Type for IRS type Point Machine, as per CWM/Signal Workshop/Howrah/E. Rly. drawing number, Sl. No., Description of Drawing & CWM/SW/HWH's Drawing No. mentioned below: - 1. Detector Rod (Far End) - BS/29/721 with ALT-1 Detector Rod (Near End)- BS/29/722 with ALT-1. 2. Lock Rod (Far End) - BS/29/723 with ALT-1, Lock Rod (Near End) - BS/29/724 with ALT-1. 3. Switch Extension Bracket - BS/29/725 with ALT-1. 4. Drive Rod - BS/29/726 with ALT-1 Drive Lug- BS/29/726 A with ALT-1. 5. Sleeve- BS/29/726 B with ALT-1. 6. Lug- BS/29/726 C with ALT-1. 7. Pin- BS/29/726 D with ALT-1. 8. Sketch showing the Layout arrangement- BS/29/727 with ALT-1. Amdt. and alt. up to date if any. Inspection: Consignee Trap						
57	060304	4.00	Numbers	10407.00	41628.00	11.09	46244.55
	Description:- "Installation of electric point machines on MS plate fixed on wooden/ concrete sleepers complete with fixing of junction boxes, ground connections including smithy works involved, insulation of MS plate on which the point machine is to be fixed from the gauge tie plate involving riveting/welding of angle cleats, installation of point JB, termination adjustment for operation of points by crank handle, painting and lettering as required including wiring, testing and commissioning. Note: MS plate/flat/angle /angle cleats, paints, bolts & nuts and washers of sizes as required for fixing the point machine shall be supplied by the contractor except point machine."						
58	060501	4.00	Set	8295.00	33180.00	11.09	36859.66
	Description:- Dismantling of existing point fittings, drilling of holes in stock rail/tongue rail/ gauge tie plate, re-arrangement and re-fixing of existing electrical detector and installation of IRS 24/2002 with latest Amdt. point machine on MS plate fixed on wooden/concrete sleepers complete with fixing of point JB ground connections including smithy job for welding & termination & wiring of point machine, adjustment and testing as per technical specification and dismantling of all new fittings excluding point machine and marking with paint for future and transportation up to railway's store.						
59	061101	4.00	Numbers	2613.00	10452.00	11.09	11611.13
	Description:- Supply of GI bend pipe, 'B' class, 50mm dia. for cable entry in point machines, alongwith required fixing arrangements as per standard practice on Eastern Railway. Inspection: Consignee.						
60	061301	4.00	Numbers	1169.00	4676.00	11.09	5194.57
	Description:- Dismantling of point machine with ground connection including point JB.						
61	070101	50.00	Numbers	4894.00	244700.00	11.09	271837.23
	Description:- Supply of Track feed Battery Charger as per RDSO Specn. No.IRS: S-89/2013 Ver.1.0 or latest. Charging Capacity Rating 10 Amps for Charging 80 AH Battery. Inspection: RDSO						
62	070103	50.00	Numbers	171.00	8550.00	11.09	9498.19
	Description:- Supply of Adjustable Track Feed Resistance 30 Ohms (Disc Type) as per RDSO Drg. No.SA-20161-66/M or latest. Inspection: Consignee						
63	070201	18.00	Per Track Circuit	3259.00	58662.00	11.09	65167.62
	Description:- Installation wiring, testing and commissioning of single rail dc track circuit (TRACK CIRCUIT (BEYOND 200 MTRS.)) as per approved track circuiting plan. The work includes track battery charging and installation, fixing of track bonding (double) with 8 SWG soft GI wire, laying of tail cables with track lead junction box, rail connector with galvanised iron wire, track jumpering(double) with supporting arrangement for holding as per track circuit plan. It also includes installation and wiring of track feed chargers, track relays, track circuit equipment's in the location box including fuses and ARA terminals required for the purpose as per DRG NO. SK/10/95(NKG) including drilling of 9/32" hole on rails where required. Fixing of track lead junction boxes. Note: - battery charging solution to be supplied by the contractor & double jumpering to be provided.						
64	070202	12.00	Per Track Circuit	3244.00	38928.00	11.09	43245.12
	Description:- Installation wiring, testing and commissioning of single rail dc track circuit (SHORT LENGTH TRACK CIRCUIT UPTO 200 MTS.) as per approved track circuiting plan. The work includes track battery charging and installation, fixing of track bonding (double) with 8 SWG soft GI wire, laying of tail cables with track lead junction box, rail connector with galvanised iron wire, track jumpering(double) with supporting arrangement for holding as per track circuit plan. It also includes installation and wiring of track feed chargers, track relays, track circuit equipment's in the location box including fuses and ARA terminals required for the purpose as per DRG NO. SK/10/95(NKG) including drilling of 9/32" hole on rails where required. Fixing of track lead junction boxes. Note: - battery charging solution to be supplied by the contractor & double jumpering to be provided.						
65	070203	16.00	Per Track Circuit	3348.00	53568.00	11.09	59508.69

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

	Description:- Installation, wiring, testing & commissioning of track circuit involving points & crossings as per track circuiting plan, track battery charging and installation including drilling 9/32" hole on rails; fixing of bonding(double) with 8 SWG soft GI wire, insulation of stretcher bars (leading & following), gauge / crossing tie plates involving cutting and riveting/welding of angle clit, split stretcher bars, fixing of track lead junction box, rail connector with GI wire, track jumpering (double) with supporting arrangement for holding termination of track lead wires, including series jumpers, jumper wire terminals, track feed set(track chargers, resistance, fuses, battery etc.) As per approved IYD for point zone track circuit. Note: - battery charging solution to be supplied by the contractor & double jumpering to be provided.						
66	070301	100.00	Numbers	3564.00	356400.00	11.09	395924.76
	Description:- Supply of Track Lead Junction Box(TLJB) made from FRP material including brass bolts and hylam board sheet with terminals etc. The technical specifications are as follows:(a) TLJB complete with cover to be in black/red having approximate weight of 4.0 Kg with L-262mm W-212mm and H 90 mm and all the holes required for mounting on FRP stump (vertically two for each FRP angle) HDPE pipe , cable etc.(b) Each TLJB shall have two bakelite terminal block fitted horizontally : each bakelite terminal block shall have two nickel chrome plate M10 brass terminal, 50mm long. Alongwith each TLJB , nickel chrome plated brass links(two nos.0f adequate strength for vertical linking of the terminals to be supplied.(c) HDPE pipe of size 32/35mm , 380 mm long alongwith two nuts for fixing on the TLJB hole .(d) The FRP stump for mounting the TLJB to be made of one meter long 30mm X30mmX 4mm angle(2 nos.) and 300mm long 30mm X30mmX 4mm angle(1 no.) fixed at 50 mm from the bottom using galvanised nuts and bolts. The TLJB and the angles for stump should come alongwith holes on them for fixing using galvanised nuts and bolts of adequate strength to be supplied alongwith TLJB.Inspection: Consignee						
67	070303	100.00	Numbers	1316.00	131600.00	11.09	146194.44
	Description:- Erection, Fitting and Rail connection of Track Lead Junction Box on two supports (FRP stumps) with contractor's fixing material. This will include drilling of holes for track lead/side connections on rail. The work shall be done as per instructions of Rly engineer at site. Inspection: Consignee						
68	070401	92.00	Numbers	5151.00	473892.00	11.09	526446.62
	Description:- Supply of B Type Choke as per RDSO Specn. No.IRS: S-65/83 (Amnd. 1) or latest. Inspection: RDSO.						
69	070501	6000.00	Numbers	4.00	24000.00	11.09	26661.60
	Description:- Supply of Channel Pins MS (Galvanized) single groove, 7 mm suitable for 4mm dia bonding wire as per spec No IRS S 17 & RDSO Drg No. S-69/M.Inspection: Consignee.						
70	070601	2000.00	Numbers	12.00	24000.00	11.09	26661.60
	Description:- Supply of GI wire 8 SWG (4mm dia) suitable for track circuit rail bonding. Inspection: Consignee.						
71	071601	60.00	Numbers	1346.00	80760.00	11.09	89716.28
	Description:- Supply & installation of 'C' class surge protection arrangement at feed end DC Track Ckt Specn no. As follows: - voltage 230 V AC rated voltage 350V AC DIS. CAP 10KA TO 20 KA TIME 100 MILI second protection 1.2V degree protection IP.20 TEC-61643-1. Inspection : by consignee.						
72	071701	60.00	Numbers	748.00	44880.00	11.09	49857.19
	Description:- Releasing of existing TLJB and its accessories						
73	070801	40.00	Per Detection Point (DP)	342558.00	13702320.00	11.09	15221907.29
	Description:- Supply, Transportation, Installation, Testing and Commissioning of Multi Section Digital Axle Counter (MSDAC) for mentioned detection Point by the purchaser & Track Section as per SIP uploaded with the tender, complete with all accessories, cable required with each track device & Card viz., Axle Detectors, Track Side Electronics/ DAC field units, Central Evaluator (Central Evaluator unit should be housed in a pre-fabricated Rack to be supplied along with the system), Reset unit, Relay unit, Event logger & Diagnostic terminals etc. required for different Detection Points & Track Sections as per RDSO Specification No. RDSO/SPN/176/2013, Ver.3 or latest as per Annexure-070801(A, B & C.) Inspection: RDSO						
74	070803	2.00	Numbers	76514.00	153028.00	11.09	169998.81
	Description:- Supply of Portable operator console for onsite programming of Axle Counters as per technical requirement given in tender document. Inspection: Consignee						
	070808	20.00	Per Detection Point (DP)	7718.00	154360.00	11.09	171478.52

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

75	Description:- Installation testing and commissioning of detection points as above as per RDSO specification no. RDSO/ SPN/ 176/ 2013(ver-3) or latest. This include installation, wiring, testing and commissioning of complete MSDAC system which includes track circuit electronics and its all accessories (track electronics unit, central evaluator and its accessories/interface device, if any. All the tools and plants for installation has to be arranged by the contractor. Wiring from cable termination rack to the central evaluator, installation of earth electrode (if required will be supplied by Railway), installation and wiring the reset box and wiring the power supply to the central evaluator including the supply of 2 core shielded cable for required size copper conductor as per IRS-S-76/89 OR IS:694/1977(or latest) as applicable with other accessories. Note- i: - all execution/installation materials as required to be supplied by the contractor. Note- ii: - (i) installation, testing and commissioning of MSDAC to be done by OEM'S engineer. (ii) pre-commissioning checklist issued by RDSO for MSDAC will be prepared by OEM's engineer and to be signed jointly with rly site engineer incharge (iii) payment for this item will be released only after submission of duly signed pre-commissioning checklist of MSDAC in standard RDSO format. (iv) OEM'S engineer will also impart training to rly staff at site for proper functioning /working and applications of MSDAC. Inspection: Consignee						
76	080101	30.00	Numbers	8362.00	250860.00	11.09	278680.37
77	080102	30.00	Numbers	8387.00	251610.00	11.09	279513.55
78	080103	30.00	Numbers	9438.00	283140.00	11.09	314540.23
79	080201	50.00	Numbers	5478.00	273900.00	11.09	304275.51
80	080202	40.00	Numbers	5675.00	227000.00	11.09	252174.30
81	080203	30.00	Numbers	6830.00	204900.00	11.09	227623.41
82	080301	8.00	Numbers	15707.00	125656.00	11.09	139591.25
83	080302	16.00	Numbers	15950.00	255200.00	11.09	283501.68
84	080303	6.00	Numbers	15727.00	94362.00	11.09	104826.75
	080801	20.00	Numbers	26583.00	531660.00	11.09	590621.09

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

85	Description:- "Installation, erection and wiring of CLS unit, post, ladder& base LED unit including paying out of tail cable from location box and earthing of CLS (LED type). Thisincludes supply of non - metallic (FRP) color light signal housing multi-unit type for Rly. Signalling suitable for REArea 2 Aspect complete without lenses, lamps and signal transformer as per DRG. NO. SA23001/A/M(ADV), ALT.8 and as per SPEC. NO. RDSO/SPN/194/2006 (VER1.0) OR LATEST. FRPmaterial as RDSO SPEC NO. RDSO/SPN/ 151/1997 OR LATEST. All drawings should be as per latest. Materialsto be procured from RDSO's approved firm only. Note: Signal unit should be compatible to 'LED' type. Note:installation, erection & wiring of signalling unit includes LED signal lighting unit including current regulator. This also includes protection of unit from rain water." "Supply. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board."						
86	080802	20.00	Numbers	1658.00	33160.00	11.09	36837.44
	Description:- "Installation, erection and wiring of CLS unit, post, ladder& base LED unit including paying out of tail cable from location box and earthing of CLS (LED type). Thisincludes supply of non - metallic (FRP) color light signal housing multi-unit type for Rly. Signalling suitable for REArea 2 Aspect complete without lenses, lamps and signal transformer as per DRG. NO. SA23001/A/M(ADV), ALT.8 and as per SPEC. NO. RDSO/SPN/194/2006 (VER1.0) OR LATEST. FRPmaterial as RDSO SPEC NO. RDSO/SPN/ 151/1997 OR LATEST. All drawings should be as per latest. Materialsto be procured from RDSO's approved firm only. Note: Signal unit should be compatible to 'LED' type. Note:installation, erection & wiring of signalling unit includes LED signal lighting unit including current regulator. This also includes protection of unit from rain water." Execution						
87	080901	10.00	Numbers	27309.00	273090.00	11.09	303375.68
	Description:- "Installation, erection and wiring of CLS unit, post, ladder& base LED unit including paying out of tail cable from location box and earthing of CLS (LED type). Thisincludes supply of non - metallic (FRP) color light signal housing multi-unit type for Rly. Signalling suitable for REArea 3 Aspect complete without lenses, lamps and signal transformer as per DRG. NO. SA23001/A/M(ADV), ALT.8 and as per SPEC. NO.RDSO/SPN/194/2006 (VER1.0) OR LATEST. FRP material as per RDSO spec no. RDSO/SPN/151/1997 or LATEST. All drawings should be as per latest. Materials to be procured from RDSO's approved firm only. Note:Signal unit should be compatible to 'LED' type. Note:Installation, erection & wiring of signalling unit includes led signal lighting unit including current regulator. This also includes protection of unit from rain water." "Supply. Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board."						
88	080902	10.00	Numbers	2352.00	23520.00	11.09	26128.37
	Description:- "Installation, erection and wiring of CLS unit, post, ladder& base LED unit including paying out of tail cable from location box and earthing of CLS (LED type). Thisincludes supply of non - metallic (FRP) color light signal housing multi-unit type for Rly. Signalling suitable for REArea 3 Aspect complete without lenses, lamps and signal transformer as per DRG. NO. SA23001/A/M(ADV), ALT.8 and as per SPEC. NO.RDSO/SPN/194/2006 (VER1.0) OR LATEST. FRP material as per RDSO spec no. RDSO/SPN/151/1997 or LATEST. All drawings should be as per latest. Materials to be procured from RDSO's approved firm only. Note:Signal unit should be compatible to 'LED' type. Note:Installation, erection & wiring of signalling unit includes led signal lighting unit including current regulator. This also includes protection of unit from rain water." Execution						
89	081103	4.00	Numbers	43270.00	173080.00	11.09	192274.57
	Description:- "Installation, erection and wiring of junction type route indicator [LED type] this include supply of nonmetallic FRP junction type route indicator for Railway Signalling suitable for RE Area without lamp. Lenses, signal transformer as per RDSO SPEC. NO. RDSO/SPN/194/2006 (VER - 1.0) OR LATEST. FRP material as per RDSO SPEC. NO. RDSO/SPN/151/ 1997 OR LATEST. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note: Signal unit should be compatible to LED type. Note: installation, erection & wiring of signalling unit includes LED signal, lighting unit including current regulator. This also includes protection of unit from rain water." "Supply of 2 WAY AS PER RDSO DRG. NO. SA-23402 (ADV)/ ALT.2 Inspection: (i)RDSO/RITES if value of item in work more than 5 lakhs. (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board."						
90	081104	4.00	Numbers	1203.00	4812.00	11.09	5345.65
	Description:- "Installation, erection and wiring of junction type route indicator [LED type] this include supply of nonmetallic FRP junction type route indicator for Railway Signalling suitable for RE Area without lamp. Lenses, signal transformer as per RDSO SPEC. NO. RDSO/SPN/194/2006 (VER - 1.0) OR LATEST. FRP material as per RDSO SPEC. NO. RDSO/SPN/151/ 1997 OR LATEST. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note: Signal unit should be compatible to LED type. Note: installation, erection & wiring of signalling unit includes LED signal, lighting unit including current regulator. This also includes protection of unit from rain water." Execution of 2 WAY AS PER RDSO DRG. NO. SA-23402 (ADV)/ ALT.2						
	081201	12.00	Numbers	5544.00	66528.00	11.09	73905.96

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

91	Description:- Installation, erection and paying out of tail cable from location box and wiring of shunt signal, LED unit on the same post below the main signal as per technical specification. This includes supply of position light shunt signal unit without lenses, lamps, base, post and without signal transformer as per RDSO DRG NO. SA-23840/ADV/ALT-2. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note- Signal unit should be compatible to 'LED' type. Supply. Inspection: Consignee						
92	081202	12.00	Numbers	505.00	6060.00	11.09	6732.05
92	Description:- Installation, erection and paying out of tail cable from location box and wiring of shunt signal, LED unit on the same post below the main signal as per technical specification. This includes supply of position light shunt signal unit without lenses, lamps, base, post and without signal transformer as per RDSO DRG NO. SA-23840/ADV/ALT-2. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note- Signal unit should be compatible to 'LED' type. Execution						
93	081301	4.00	Numbers	6782.00	27128.00	11.09	30136.50
93	Description:- Installation, erection and paying out of tail cable from location box and wiring of shunt signal, LED unit as per technical specification. This includes supply of position light shunt signal unit (without lenses, lamps) with Base Post and without signal transformer as per RDSO DRG NO. SA-23840/ADV/ALT-2. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note- Signal unit should be compatible to 'LED' type. Installation, erection and paying out of tail cable from location box and wiring of shunt signal, LED unit as per technical specification. This includes supply of position light shunt signal unit (without lenses, lamps) with Base Post and without signal transformer as per RDSO DRG NO. SA-23840/ADV/ALT-2. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note- Signal unit should be compatible to 'LED' type.						
94	081302	4.00	Numbers	502.00	2008.00	11.09	2230.69
94	Description:- Installation, erection and paying out of tail cable from location box and wiring of shunt signal, LED unit as per technical specification. This includes supply of position light shunt signal unit (without lenses, lamps) with Base Post and without signal transformer as per RDSO DRG NO. SA-23840/ADV/ALT-2. All drawings should be as per latest. Material to be procured from RDSO's approved firm only. Note- Signal unit should be compatible to 'LED' type. Execution						
95	081401	16.00	Numbers	2533.00	40528.00	11.09	45022.56
95	Description:- Supply of Calling ON/ Guard Repeater Signal Unit with Brackets & Fixing accessories. Calling ON/ Guard Repeater Signal Unit shall conform to RDSO Drg no 24351(Adv) Alt1 suitable to LED Signal Lighting Unit. Inspection: Consignee						
96	081403	16.00	Numbers	2331.00	37296.00	11.09	41432.13
96	Description:- Fixing of Calling-on Signal/A-Sign/AG-Sign unit on signal post including Guard Repeater Signal. The item includes fixing of Co- On signal /'A' sign/ 'AG' sign unit on signal post with bracket, hood etc. Item includes supply of bracket & fixing materials etc. by the contactor. The item also includes termination of cables & wiring inside Co- On signal /'A' sign/ 'AG' sign unit as per standard practice. Inspection: Consignee.						
97	081501	8.00	Numbers	3502.00	28016.00	11.09	31122.97
97	Description:- Supply and fixing of protective screen of expanded metal 12 SWG of size 1200 x 1500 mm on signals as per std. practice in RE Area. Inspection: Consignee.						
98	081701	8.00	Numbers	550.00	4400.00	11.09	4887.96
98	Description:- Supply and installation of P/ C / G/ A/ AG marker (size 250mm dia circle) high intensity prismatic(TYPE-IV) retro reflective sheet over 2 mm thick aluminium sheet & letter will be screen printing (250 mm dia circle) as per drg. S&T/SDAH/SK-1383 and technical specification attached. This will include cost of all materials including fixing clamp required for this work. Inspection: Consignee						
99	081801	36.00	Numbers	373.00	13428.00	11.09	14917.17
99	Description:- Supply, Fabrication and Fixing of Retro reflective Nomenclature Board of size 254 mm x 358 mm made of 2mm thick aluminium sheet & high intensity prismatic (hip) grade retro reflective sheet (TYPE -IV) including fixing arrangement for fixing them on existing post per DRG. NO. S&T/SDAH/SK-1386 and as per standard practice Inspection: Consignee						
100	081901	12.00	Numbers	2041.00	24492.00	11.09	27208.16
100	Description:- Supply of offset bracket for position light shunt signal (90mm outside Dia.) post with U clamps, nuts, washers complete as per RDSO DRG. NO.SA-23080/ADV/ALT-1 all drawings should be as per latest. Inspection: by consignee						
101	081902	6.00	Numbers	2513.00	15078.00	11.09	16750.15
101	Description:- Supply of cast iron offset bracket for Main Signal with U clamps, nuts, washers complete DRG. NO. SA-23080/ ADV/ ALT-1. RDSO SPEC. NO. IRS-S-10/78. Inspection: consignee. Note : Offset bracket has to be connected wherever necessary as per site engineer.						
102	082001	30.00	Numbers	8065.00	241950.00	11.09	268782.26
102							

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

	Description:- Casting, concreting & curing of foundation for Main signal including cost of all materials required for casting and concreting. All materials required for execution will be supplied by the contractor including cement, sand & stone chips as per DRG. NO. S&T/C-42(NKG).						
103	082101	4.00	Numbers	4087.00	16348.00	11.09	18160.99
	Description:- Casting, concreting and curing of foundation for Shunt signal including cost of all materials required for casting and concreting. All materials required for execution will be supplied by the contractor, including holding down galvanised bolts & nuts with washers, cement, sand, stone chips, etc. As per DRG. NO SK/5/95/NKG						
104	082201	20.00	Numbers	3065.00	61300.00	11.09	68098.17
	Description:- Releasing of existing tail cables and drawl of new tail cables for colour light signals up to four aspects with or without route indicator, post type shunt signal and calling signals. Termination of new tail cables and wiring using wire PVC 3/0.75 mm copper as per latest RDSO spec. This work includes drawl of new tail cables into the signal post duly releasing the existing tail cables from the relevant signals [Wire PVC 3/0.75 mm copper, paints and all other miscellaneous materials shall be supplied by the contractor. Wire to be procured from RDSO's approved source only]. Inspection- consignee.						
105	082301	24.00	Numbers	1218.00	29232.00	11.09	32473.83
	Description:- Dismantling of existing main signal including dependent shunt signal, calling on signal if any, fitted on the same post along with signal post, signal unit, ci base without damaging any part.						
106	082302	24.00	Numbers	2212.00	53088.00	11.09	58975.46
	Description:- Dismantling of existing Signal Foundation (upto formation level by hydraulic breaker).						
107	090301	1.00	Numbers	15976.00	15976.00	11.09	17747.74
	Description:- "Supply and installation of LED type table mounting gate control-cum-indication panel of required size as per site engineer and as per signalling plan including supply of wooden table (hard wood) of standard height for mounting of panel, cable entry in panel with 50 mm dia gallant. Note- gate panel should have button operation for gate close & open instead of switch. The switch for signal operation preferably should have 2NC/2RC contact. Make-Deltron or similar. Inspection-Consignee."						
108	090401	5.00	Numbers	197347.00	986735.00	11.09	1096163.91
	Description:- Supply of lifting barrier LC gate complete including pedestal, winch machine, stop post and boom of 10.00 mtr. Long as per RDSO DRG.NO.SA-8843-46 & SA-8843A-46A(ADV), SA-8839-42 & SA-8839A-42A(ADV) SA-8157A(ADV). Material to be procured from approved list of firms for manufacturer & supply of mechanical signalling item.Inspection: Consignee						
109	090402	5.00	Numbers	39522.00	197610.00	11.09	219524.95
	Description:- "Supply of boom locking arrangement complete as per DRG. NO. SA-8158/M(ADV).1) pole lock base as per RDSO's DRG. NO.8159/M (ADV). Specification no. GR. FG-200. IS-210-78. IRS-S-10.2). Pole lock cover as per RDSO'S DRG. NO. S-8160/M specification no.GR. FG- 200.IS-210-78. IRS-S-10. And one set consists of one lock and one cover including all accessories as required. Material to be procured from approved list of firms for manufacturer & supply of mechanical signalling item. Inspection: consignee"						
110	090403	5.00	Numbers	92310.00	461550.00	11.09	512735.90
	Description:- "Supply of complete operating and transmission system of L.C. gate right from winch machine to L.C. gate. This item includes supply of all the materials required like foundations, cranks, joints, wires, wire insulators, wheels, arc lever etc. by contractor. Inspection: consignee & materials to be procured from original manufacturer or dealer."						
111	090404	5.00	Numbers	61668.00	308340.00	11.09	342534.91
	Description:- "Installation of lifting barrier complete along with casting, concreting, curing of foundation (mixture of cement, sand and stone chip of size - 20 with 1:3:6 ratio). ARC lever, winch machine, pedestal, cranks, compensators, A-type foundation, diversion wheel, rod run etc. Including RDSO type boom locking as per standard practice of eastern railway for level crossing gate and as per instruction of site engineer. All materials for fixing, nuts & bolts and concrete foundation to be supplied by the contractor. This includes testing and commissioning."						
112	090501	1.00	Numbers	197415.00	197415.00	11.09	219308.32
	Description:- "Supply of sliding boom gate as per eastern railway signal workshop/ Howrah's drawing no. BSA/29/730, BSA/29/731 & BSA/29/737 or Latest. This includes supply of 8 nos. E-type lock with key as per IRS SPEC. NO. IRS-S-30/64 with latest amendment. Key lock 'e' type as per drawing no. SA-3376/M, 3377/M with latest amendment or Latest. Ward no. To be decided by the site engineer. 'E' type lock to be on MS plate as mentioned in the drawing. Inspection: by rites [for value of material above Rs. 5.0 lakhs.]. Inspection by consignee [for value of material below than Rs 5.0 lakh]."						
113	090502	1.00	Numbers	53129.00	53129.00	11.09	59021.01

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

113	Description:- "Casting, concreting & curing of foundation (1:3:6) for sliding boom gate as per drawing no. SGWSDAH/SLIDING GATE FOUNDATION/2012 or Latest including supply & fixing of holding down bolts with washers and nuts, MS plates of size 350x350x8 mm, cement, sand, stone chips etc. For foundations required in each set of gates."						
114	090503	1.00	Numbers	7032.00	7032.00	11.09	7811.85
	Description:- "Installation & commissioning of sliding boom gate. This includes levelling, fixing of sliding boom with fixing of E-type lock, etc. Note: all materials to be supplied by the contractor except sliding boom gate and E-type lock."						
115	090601	3.00	Numbers	7044.00	21132.00	11.09	23475.54
	Description:- "Installation, wiring and testing of electrical key transmitter for LC gate control as per yard diagram, approved circuit diagram. Installation portion shall include supply of necessary angles, wooden shelf, nuts & bolts as required for the work. The ward no. Of key shall be advised by the site engineer. This includes supply of electrical key transmitter with key for LC gate control as per yard diagram, approved circuit diagram and specn.no. IRS-S-21/01(LATEST) AND IRS-S- 23(LATEST), DRG.NO.SA-22601 (ADV)ALT.2. [key combination will be intimated by site engineer]" Supply. Inspection: RDSO						
116	090602	3.00	Numbers	6672.00	20016.00	11.09	22235.77
	Description:- "Installation, wiring and testing of electrical key transmitter for LC gate control as per yard diagram, approved circuit diagram. Installation portion shall include supply of necessary angles, wooden shelf, nuts & bolts as required for the work. The ward no. Of key shall be advised by the site engineer. This includes supply of electrical key transmitter with key for LC gate control as per yard diagram, approved circuit diagram and specn.no. IRS-S-21/01(LATEST) AND IRS-S- 23(LATEST), DRG.NO.SA-22601 (ADV)ALT.2. [key combination will be intimated by site engineer]" Execution.						
117	090701	8.00	Numbers	195.00	1560.00	11.09	1733.00
	Description:- "Installation of magneto / control telephone, annunciator with all accessories and dry cells (2 nos.). For each phone with wooden battery box. This includes supply of magneto telephones with all accessories including supply of 2 nos. Dry cell for each telephone with wooden battery box. (i) SPEC.FOR magneto telephone - IRS-TC-79/2000.AMD-1 OR LATEST" Execution.						
118	090702	8.00	Numbers	3509.00	28072.00	11.09	31185.18
	Description:- "Installation of magneto / control telephone, annunciator with all accessories and dry cells (2 nos.). For each phone with wooden battery box. This includes supply of magneto telephones with all accessories including supply of 2 nos. Dry cell for each telephone with wooden battery box. (i) SPEC.FOR magneto telephone - IRS-TC-79/2000.AMD-1 OR LATEST" Supply of magneto telephone, desk type, spec. No IRS-TC-79/2000 AMDT. 1 or latest. Inspection: by consignee						
119	090803	5.00	Numbers	5210.00	26050.00	11.09	28938.94
	Description:- Supply of Gate (slave)telephone. Inspection: Consignee						
120	090804	5.00	Numbers	741.00	3705.00	11.09	4115.88
	Description:- "Execution of Gate (slave)telephone. This Includes testing and commissioning, all installation related material to be supplied by the contractor as per site requirement. "						
121	100401	8.00	Numbers	5176.00	41408.00	11.09	46000.15
	Description:- Supply of CO2 type fire extinguisher capacity 4.5 Kg capacity ISI Mark IS: 15683 operating temperature (-30)° to (50)° for class 13 B type of fire with 1 mtr. Hose pipe fitted with PVC bend horn complete in all respect.Inspection: Consignee						
122	110101	160.00	Numbers	13916.00	2226560.00	11.09	2473485.50
	Description:- Supply of full size apparatus case (Large) (as per DRAWING NO. RDSO/S-11500).This includes supply of location box (GKP type) with 'E' type lock & key, fitted on location door on both side, E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11500. Inspection: RITES						
123	110103	160.00	Numbers	3532.00	565120.00	11.09	627791.81
	Description:- Casting, concreting and curing of concrete foundation ((in ratio 1:3:6), erection and installation of full size apparatus case (GKP type)/Stainless Steel (SS) Apparatus Case as per DRG.NO. S&T/C-6/98(NKG) with 'E' type lock on CC foundation. This includes cost of all materials required for fixing holding down bolts, casting, concreting. Note: - bolts, nuts and washers, bitumen compound to be supplied by contractor and bitumen compound to be used in between apparatus case and foundation as per site engineer. This also includes bottom of apparatus cases filled with sand and the outside covered with masonry work and neat cement plastering. Note: - Location boxes to painted with anti-corrosive paints as per IS:- 9862-1981, one and half feet from the bottom, on all surfaces-both inside and outside. Inspection: Consignee						
	110104	160.00	Numbers	4830.00	772800.00	11.09	858503.52

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

124	Description:- Fixing by slotted angle, wiring of terminal strips, hylam strip, relays, fuses with base, fixing of hard wood shelves for full size apparatus case with termination & Earthing of cables and wiring with lettering as required including supply of slotted angles, wires, ferrules for marking and miscellaneous materials per location to be supplied by contractor. (all materials except relay, terminal strips, Bakelite strip, fuses with base and hard wood shelves to be supplied by the contractor). Wires to be used for this purpose should be procured from RDSO'S approved firm and to be inspected by RDSO. [Quantity of wires to be specified by contractor]. NB- power cable to be terminated with proper lugs and required buss bar and other terminals to be supplied by the contractor. Inspection: Consignee						
125	110201	15.00	Numbers	7860.00	117900.00	11.09	130975.11
	Description:- Supply of half size apparatus case (GKP type) (As per GKP TYPE DRAWING NO.SE/FE/2004/21 & other applicable GKP SW Drawing). This includes supply of location box (GKP type) with 'E' type lock & key, fitted on location door on both side, E Type lock (ward No will be specified by Engineer-in Charge) as per RDSO Drg. No. SA 3376 and Key to Drg. No. 3377 as per RDSO drawing No. RDSO/S-11500. Inspection: Consignee						
126	110202	15.00	Numbers	3105.00	46575.00	11.09	51740.17
	Description:- Casting, concreting and curing of concrete foundation (in ratio 1:3:6), erection and installation of half size apparatus case (GKP type) Apparatus Case as per DRG.NO. RE/S&T/SIG/TENDER/SK/8/85 with 'E' type lock on CC foundation. This includes cost of all materials required for fixing holding down bolts, casting, concreting. Note: - bolts, nuts and washers, bitumen compound to be supplied by contractor and bitumen compound to be used in between apparatus case and foundation as per site engineer. This also includes bottom of apparatus cases filled with sand and the outside covered with masonry work and neat cement plastering. Note: - Location boxes to be painted with anti-corrosive paints as per IS:- 9862-1981, one and half feet from the bottom, on all surfaces-both inside and outside. Inspection: Consignee.						
127	110203	15.00	Numbers	3536.00	53040.00	11.09	58922.14
	Description:- Fixing, wiring of terminal strips, hylam strip, relays, fuses with base and supply and fixing of shelves for half apparatus case with termination earthing of cables and wiring with lettering as required including supply of slotted angles, wires, ferrules for marking and miscellaneous materials per location to be supplied by contractor. (all materials except relay, terminal strips, Bakelite strip, fuses with base and hard wood shelves to be supplied by the contractor). Wires to be used for this purpose should be procured from RDSO's approved firm and to be inspected by RDSO. [quantity of wires to be specified by contractor]. NB- power cable to be terminated with proper lugs and required buss bar and other terminals to be supplied by the contractor. Inspection: Consignee						
128	110301	40.00	Numbers	563.00	22520.00	11.09	25017.47
	Description:- Supply of hard wood shelves thickness 25 mm for keeping equipment's and batteries in the location box (FULL or HALF GKP /other type) with suitable varnish and anti-termite chemicals fitted on angles with nuts & bolts. Inspection: -Consignee (note-balance quantity may be taken from rly store if available). 950 x 400 x 25 MM for full size location box .						
129	110302	15.00	Numbers	450.00	6750.00	11.09	7498.57
	Description:- Supply of hard wood shelves thickness 25 mm for keeping equipment's and batteries in the location box (FULL or HALF GKP /other type) with suitable varnish and anti-termite chemicals fitted on angles with nuts & bolts. Inspection: -Consignee (note-balance quantity may be taken from rly store if available). 450 x 400 x 25 MM for half size location box .						
130	110401	500.00	Sqm	5370.00	2685000.00	11.09	2982766.50
	Description:- Supply of paper base hylam sheet 12 mm thick. Inspection: consignee.						
131	110701	60.00	Numbers	2782.00	166920.00	11.09	185431.43
	Description:- Alteration/modification in the existing location boxes (full size), fixing of equipment's, cable insertion, termination, wiring, testing & commissioning, two coat painting, lettering to suit the circuits as per approved wiring diagrams. This includes filling with sand and plastering the same.						
132	110702	10.00	Numbers	1607.00	16070.00	11.09	17852.16
	Description:- Alteration/modification in the existing location boxes (Half size), fixing of equipment's, cable insertion, termination, wiring, testing & commissioning, two coat painting, lettering to suit the circuits as per approved wiring diagrams. This includes filling with sand and plastering the same.						
133	110801	160.00	Numbers	651.00	104160.00	11.09	115711.34
	Description:- Dismantling of location box / RCC Goomty including all its accessories & concrete foundation.						
134	110901	40.00	Numbers	2759.00	110360.00	11.09	122598.92
	Description:- Shifting/lifting of location box to facilitate earthwork of Engg/Con.This includes filling with sand and plastering inside location box.						
135	120201	2000.00	Metre	762.00	1524000.00	11.09	1693011.60

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

133	Description:- Supply of Medium class perforated GI pipes 100 mm dia (4.5 mm thickness) as per IS 1239 (Part 1): 2004 or Latest with socket & coupling on culverts bridges or at any other locations as decided by Site Engineer. It includes supply of all material required for fixing arrangement. Contractor will also supply flexible/corrugated HDPE pipe at the end of GI pipe to protect the cables from sharp edges and sudden bends. Inspection: RITES						
136	120202	2000.00	Metre	98.00	196000.00	11.09	217736.40
	Description:- Laying & Fixing of Medium class perforated/unperforated GI pipes 50/100 mm dia (4.5 mm thickness) as per IS 1239 (Part 1): 2004 with socket & coupling on culverts bridges or at any other locations as decided by Site Engineer. It includes installation of all material required for fixing arrangement. Contractor will install flexible/corrugated HDPE pipe at the end of GI pipe along with any masonry work(if required) to protect the cables from sharp edges and sudden bends.						
137	120401	300.00	Kilometre	62867.00	18860100.00	11.09	20951685.09
	Description:- Supply of 40 mm dia permanently lubricated HDPE telecom: ducts (with chord) as per RDSO SPEC.NO. RDSO/SPN/TC/45/2013 REVISION 2.0 with latest amendments or Latest in length of 1000 mtrs/roll For each km. Of HDPE duct following items are to be supplied (a) end plugs-2 nos. (b) cable sealing plugs - 2 nos. (c) plastic couplers slip fit/push fit type-2 nos. (d) end plugs to be provided along with drum 2 nos. Inspection: RITES. Material to be supplied only after confirmation from Dy. CSTE/Con/HWH. Colour of the pipe will be as per "Technical Circular-124-A" (Modified) dated 19.01.2026 issued by CCE/ERly						
138	120601	300000.00	Metre	26.00	7800000.00	11.09	8665020.00
	Description:- "Laying of HDPE pipe duct, 40/33mm or 50/42 mm intrenches and protective works including pulling of monomode armored ofc cable (24/48 fibers) through duct in trenches and as advised by site engineer. Note: - (1) the contractor will take over the ofc cable from railway store to site of work duly checked the continuity of each fiber from end to end. (2) before & after laying of optical fiber cable through duct, continuity test from end to end of each fiber to be made by the contractor to ensure availability of all 24/ 48 fiber duly certified by the site engineer. NOTE: - Laying to be done as per Technical Circular No 124-""A"" (Modified)Dated:- 19.01.2026 issued by CCE/E.Rly"						
139	120701	2000.00	Metre	397.00	794000.00	11.09	882054.60
	Description:- Supply of Double Wall Corrugated (DWC)-HDPE pipe/duct of size 200 mm outer dia, & 175 mm inner dia. It includes supply of Double Wall Corrugated -HDPE pipe/duct as per RDSO Specn.No. RDSO/SPN/ 204/2011 (version 1.1) or latest and conforming to ISI Spec. No.IS:14930, Part-II. (The manufacturers, suppliers must produce valid IS license and should be certified under ISO 9000 and shall submit copy of certificate). One of the following coupling arrangements should also be supplied with each pipe as per the site requirement.1) Suitable snap fit coupler with rubber O-Ring 2) Spacers3) Tees4) Bend,5) End-capDWC pipe shall be marked at every 1 mtr length in such a way that manufacturer's name, vendor name and year of manufacture can be easily identified .Inspection-RITES						
140	120802	2000.00	Metre	31.00	62000.00	11.09	68875.80
	Description:- Placing of DWC HDPE/RCC/GI pipes along with collars in trenches at places near track and road, crossings, platform cuttings etc.						
141	120901	150.00	Numbers	2185.00	327750.00	11.09	364097.47
	Description:- Supply of Thermo shrink Universal Jointing kit for Quad Cable (for straight joints) as per RDSO spec IRS/TC-77/2012 revision 3 With latest Amdt. Inspection: Consignee						
142	120902	150.00	Numbers	956.00	143400.00	11.09	159303.06
	Description:- Jointing of 4 / 6 quad /Signaling cable with Heat Shrinkable straight through Jointing Kit. All the material required for the work are to be arranged by contractor himself at his own cost except Thermo shrinkable Joint Kit/Rapid joint kit. After jointing the cable through test such as insulation test, continuity cable losses etc. to be carried out jointly with Railway Engineer. If any defect or any damage is observed during jointing, the contactor has to redo the joint free of cost.						
143	121001	8000.00	Metre	1804.00	14432000.00	11.09	16032508.80
	Description:- "Transportation of HDT machine with accessories including handling of stores materials, preparation of sites and boring for placing of 110 mm dia HDPE PIPE for crossing of S&T cables together a bridges/culverts, pucca road/crossing boring trench shall be minimum 3 (three) meter below the river bed and 1(one) meter below the track/road/pucca road crossing area. This includes supply of accessories for HDPE pipes, including, cost of fuel and all other items etc. which will be required for laying of cable through it. The work shall be executed as per instruction of site engineer. HDPE PIPE TO BE SUPPLIED AS PER RDSO SPEC. Contactor shall provide all material required for boring and adequate nos. of labors for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable." Boring up to the length of 150 meters. Preparation of site for Horizontal Boring shall be carried out in presence of Railway Representative.						
144	121002	4000.00	Metre	2379.00	9516000.00	11.09	10571324.40
	Description:- Boring above the length of 150 meters. Preparation of site for Horizontal Boring shall be carried out in presence of Railway Representative.						
145	121101	72000.00	Metre	8.00	576000.00	11.09	639878.40

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

	Description:- Laying of 6 quad/Signalling cable/Power Cable with nylon rope through 110 mm HDPE pipe and back filling of boring pit.						
	121201	40000.00	Metre	1758.00	70320000.00	11.09	78118488.00
146	Description:- TRANSPORTATION OF HDT MACHINE WITH ACCESSORIES INCLUDING HANDLING OF STORES MATERIALS, PREPARATION OF SITE AND BORING (BORING SIZE UPTO 175MM) FOR LAYING OF (I) TWO (02) NOS. OF 40MM HDPE PIPES & TWO (02) 50MM HDPE PIPE OR AS PER SITE ENGINEER FOR PLACING AND FOR CROSSING OF SIGNALLING /TELECOM. CABLE THROUGH HDPE PIPE AT BRIDGES/ CULVERTS/ TRACK CROSSING/ PUCCA ROAD CROSSING, BORING TRENCH SHALL BE MINIMUM 03 (THREE) METER BELOW THE RIVER BED AND 01(ONE) METER BELOW THE TRACK/ROAD/PUCCA ROAD CROSSING AREA. THIS INCLUDES SUPPLY OF PERMANENTLY LUBRICATED HDPE TELECOM. DUCTS (I) 40MM/33MM & 50MM/ 42MM (WITH CHORD) AS PER RDSO SPEC. NO. RDSO/SPN/TC/45/2013 REV. 2.0 WITH LATEST AMENDMENTS OR AS PER SPECIFICATION NO. TEC GR. NO. G/CDS-08/02, NOV.2004 OR LATEST INCLUDING PULLING OF VARIOUS CABLES THROUGH IT. FOR EACH KM. OF HDPE DUCT THE FOLLOWING ITEMS ARE TO BE SUPPLIED (A) END PLUGS - 02 NOS. (B) CABLE SEALING PLUGS - 02 NOS. (C) PLASTIC COUPLERS SLIP FIT / PUSH FIT TYPE - 02 NOS. (D) END PLUGS TO BE PROVIDED ALONGWITH DRUM - 02 NOS. INSPECTION OF SUPPLY ITEMS - CONSIGNEE. NOTE:- (i)COST OF FUEL AND ALL OTHER ITEMS WHICH WILL BE REQUIRED FOR LAYING OF CABLE THROUGH HDPE PIPE. THE WORK SHALL BE EXECUTED AS PER SITE ENGINEER.INSPECTION OF HDPE PIPE: CONSIGNEE AS MATERIAL WILL BE REQUIRED AS AND WHEN WORK EXECUTED AND IN EXACT QUANTITY AND MOREOVER COST OF THE PIPE CAN NOT BE ACCESSED SEPERATELY. (ii) In case of pipe required as per site requirement is not a multiple of 4 then payment will be done on pro-rata basis.						
147	121401	100.00	Metre	1758.00	175800.00	11.09	195296.22
	Description:- Mechanised drilling/microtunnelling under important/busy metal / concrete road/railway track with supply & laying of 100 mm GI pipe and pulling of cable through GI pipe . This includes re instatement of the surface to the original state. As per Site requirement. G.I. Pipe as per latest IS Spec. Inspection: Consignee as GI Pipe will be required as per site requirement and the item being a composite one, seperate cost of pipe can not be ascertained.						
148	121501	60.00	Metre	256.00	15360.00	11.09	17063.42
	Description:- Repair of pucca roads to original state in level crossing area after cable laying.						
149	121701	4000.00	Numbers	417.00	1668000.00	11.09	1852981.20
	Description:- Supply, Transportation at site and Installation of RCC cable route marker engraved and painted on both side along the route at every 50 meter and at route diversion. The cable marker is to be fabricated as per RDSO drawing No. RDSO/Cable Laying/020, issued vide RDSO document No. RDSO/SI/G/2010 Version 1.1 dated 04.02.2014 or latest. The fixing work is to be done as per extant practice of E. Rly. and as per Railway site supervisor.						
150	121801	100.00	Numbers	93.00	9300.00	11.09	10331.37
	Description:- Removal of Rail (13 mtrs.) in the way of cable route. In case of panel (39 Mtrs. Each) will be consider as three rails for payment purpose.						
151	121802	100.00	Numbers	93.00	9300.00	11.09	10331.37
	Description:- Removal of PRC Sleeper in the way of cable route.						
152	122002	10.00	cum	15.00	150.00	11.09	166.63
	Description:- Extra for mechanical compaction of earth/blanketing material filled in embankment with contractor's rollers of suitable capacity, type and size to achieve specified density as per specification, testing as per IS codes incl. cost of water, T&P consumable material and all labour as a complete job. The work is to be executed as per Latest edition of "Guidelines for Earthwork in Railway Projects" issued by RDSO, Lucknow.						
153	122102	10000.00	cum	245.00	2450000.00	11.09	2721705.00
	Description:- Excavation of cable trench as per cable route plan, 1.2 Mtr. deep and of 0.3 Mtr. to 0.6 Mtr. wide at bottom without brick as per DRG. NO. S&T/C-40(NKG), SK/4/95/NKG, SK/8/95/NKG. or latest alongside the track in all kinds of soil, conforming to distances as per cable route plan and refilling. This work includes clearing of route from bushes etc. The work shall be done as per the extant practice on Eastern Railway and instructions of Railway Engineer at site. Note:-(a) for all trenches from distant signal to home signal and to relay room, the minimum headway above the uppermost cable in the trench should be 600mm. If due to a large no. Of cables headway is not available, 4" of 1:2:4 concreting should be done.Note:-(b-1) payment will be made as per actual work done on pro-rata basis, if required depth is not available at site.Note:-(b-1) payment will be made as per actual work done on pro-rata basis, if required depth is not available at site.(b-2) if the depth of trench is not uniform in a span of 100 mtr. Or shorter lengths if site condition demands along the cable run, minimum depth will be taken for that particular stretch for payment.						
154	122104	8000.00	cum	278.00	2224000.00	11.09	2470641.60

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

	Description:- Digging of trench 1.2 Mtrs. deep from rail flange/ road level and 0.3 Mtrs to 0.6 Mtrswide and back filling after placing of DWC/ RCC/GI pipe. (Placing of DWC/RCC/GI pipe covered separately). The ballast disturbed be screened and dressed as required by Engineer-in-charge or his representatives and road tarred immediately. For track crossing, RDSO sketch No. SDO/CABLE LAYING/009 or latest and for Road Crossing, RDSO sketch No. SDO/CABLE LAYING/010 or latest are to be followed.						
155	122105	2000.00	cum	497.00	994000.00	11.09	1104234.60
	Description:- "Digging of cable trench 0.3 Mtrs. Deep and 0.3 Mtrs. Wide on Platform / Road / Hard rocky area. Refilling with earth leveling of trenches & restoring the original surface of trenches. The sharp edges will be smoothened out in bottom of the chase and will be leveled properly. In hard rocky ground area , cables will be laid normally on layer of shifted earth of 0.05 mtrs thickness previously deposited at bottom of the trench and cables will be covered with layer of sand or shifted earth of 0.1 mtr thickness. In case sharp edges of rocky ground cannot be protected from shifted earth then GI/ CI /PVC /DWC/ HDPE pipes will be used, if numbers of cables is small. In case number of cables are large RCC duct will be used. In isolated cases, it can be given smooth surface by using either masonry bricks or cement concrete. A row of bricks shall then be placed length wise on the top and jointed with cement mortar and layer of concrete with cement plaster shall be provided on top of the same.Note: This item in hard rocky area will be operated only where normal depth i.e.1.2 mtr is not possible and it will be decided by site engineer/unit officer incharge of work. "						
156	122201	60.00	Numbers	6674.00	400440.00	11.09	444848.80
	Description:- Excavation of OFC pit for cable jointing of size 1.5m x 1.5m x 1.2 m for all type of soils. The section. Back filling the pit and ramming after jointing. Provision of brick walling the four walls and bottom of pit with RCC slab, back filling with earth and ramming as per drawing. N.B. all the materials including cement required for the above will be supplied by the tenderer.						
157	122301	300000.00	Running Metre	5.00	1500000.00	11.09	1666350.00
	Description:- Laying of S&T Cables of various cores/ pairs/ quads in trenches/ GI pipes/ RCC pipes/ DWC pipes/ Trunking. This also includes laying of cables in track crossings & road crossings. Item includes provision of labels of coloured plastic adhesive tapes or any other identifiable material on each cable to give the cable number at each Gantry Post/hectometre post.(Cables will be meggered before and after its laying by contractor under supervision of Railway Representative and he will submit the meggering report of each testing). Length of the cable laid includes the length of the cable coiled for termination purposes.						
158	122401	150.00	cum	3596.00	539400.00	11.09	599219.46
	Description:- Cement concrete work for miscellaneous items in the ratio 1: 3: 6. Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor). Wherever depth of 0.5 m cable trench is not feasible, cable shall be protected as :- Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench.						
159	122801	8000.00	Metre	2314.00	18512000.00	11.09	20564980.80
	Description:- "Supply, installation & laying of polyolefin cable channel of size width 240/340 mm, height 155/230 mm, internal/external, length 1m produced of polyolefin with fire protection class k-1 in accordance with din-53438 part ii for laying signalling/telecom cables, channel attachable to each other with male female swallow tail connectors and having suitable detachable cover, as per the following technical spec. : Width (Internal/External)- 240mm/340mm, Height (Internal/External)- 155mm/230mm, Length per PC/per Mt.- 1000mm (approx.), Material- Polyolefin/Polymers/Engineering Plastics, Fire Behaviors- Fire protection class K1 in accordance with DIN-53438 part-2, Breaking Load (Minimum)- >=12KN, at room temperature, over the specified surface area of 250mm x 150mm, Thermal Characteristics- Thermal stability from -10 degree to +70 degree (as per IS 9000-part-2 & part-3 :1977), Electrical Characteristics- Dielectric strength ; 48kv (Min. breakdown voltage) as per IEC-60243-1-2013, Tolerance-(+/-) 10mm, Complying to- RDSO Reference No. STS/Cable-Laying Practice Vol-IV."						
160	122901	75.00	Numbers	3558.00	266850.00	11.09	296443.66
	Description:- Supply of optic fibre splice closure (48 fibre) as per tec. Specification no. G/OJC-02/01, March'99 with latest amendment or latest including all miscellaneous items and consumables for fibre splicing. Inspection:- by consignee.						
161	122902	75.00	Numbers	10625.00	796875.00	11.09	885248.44
	Description:- jointing, terminating & splicing of 48 fibre optic fibre cable and fixing of termination box/FDF/placing of joint closures in the pit required at various locations including transportation of all the jointing & terminating materials from railway store to the work site and returning leftover materials to the railway store.						
	130101	3.00	Numbers	167829.00	503487.00	11.09	559323.71

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

162	Description:- Supply Wiring, installation, testing and commissioning of Earth Leakage Detector (12 nos. channel) as per RDSO specification no. RDSO/SPN/256/2002 or latest having 6-digit counter, 12 Channel bus bar voltage of 110V AC/DC and/or 60V/24V/12V DC measurement in 19" sub rack along with insulation resistance meter, remote indication & buzzer in ASM room at station. The tenderer should submit three years' warranty certificate along with supply of material. This includes supply of fuse terminal strip for incoming power supply wires. On job training at site will be given by OEM engineer for installation and maintenance of ELD. Inspection by RDSO.						
163	130201	20.00	Lot	15147.00	302940.00	11.09	336536.05
	Description:- "Supply of basic material to construct unit maintenance free earth as per RDSO Specs. No RDSO/SPN/197 Ver.1.0 or latest and conforming to RDSO Drg. No. SDO / RDSO/ E&B/001 or Latest. Necessary testing certificate of UL, IEC to be produced. It consist of following: (a) Copper bonded steel electrode of 3.0 m long, 17.2 mm dia with copper bonding thickness of minimum macrons and UL listed and marked = 1 no. (b) Earth enhancement material supplied in sealed bags of minimum 10 kg = 3 nos. (c) Copper strip of 150x25x6 mm, to terminate earth rod = 1 no. (d) Copper strip of 300x25x6 mm (MEEB) = 1 no. (e) Copper strip of 150x25x6mm (SEEB) = 1 no. (ii) Supply of 35 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting main earth electrode to MEEB in the equipment room in duplicate.(minimum 10 meter) (iii) Supply of 16 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting MEEB to SEEB and SPD to MEEB (minimum 10 meter) (iv) Supply of 10 sq. mm multi strand single core PVC insulated copper cable as per IS: 694 for connecting various equipments to SEEB (v) Supply of copper lug sleeve for 3/16 cable Inspection: RDSO"						
164	130202	20.00	Set	6579.00	131580.00	11.09	146172.22
	Description:- "Installation of Unit Maintenance Free Earth as supplied in above item. It includes (i) Digging the earth to the required depth. (ii) Insertion of electrode. (iii) Filling of earth enhancing compound (Approx.30 Kg) (iv) Provision of exothermic weld connections to copper tape of 25 mm x 6 mm x 150 mm to the earth electrodes. All material tools and features required for weld will be arranged by contractor. (v) This also includes CC cover 1.5 ft x 1.5 ft. 1 ft wall thickness 2 inch with cover 3 inch thickness. Cables 35 Sq mm/ 16 Sq mm/10 sq mm for connecting earth to busbar, busbar to busbar and bus bars to various equipments. Earth electrode of 17.20 mm dia and 3.00 meter long high tensile low carbon steel circular rods molecularly bonded with copper and outer surface (minimum copper bonding thickness of 250 microns to made requirement of under writer's laboratories (UL) 467-2007 or latest. Copper strips of 150 mm x 25 mm x 6 mm to be welded with each earth electrode, copper strips of 300 mm x 25 mm x 6 mm for main equip- potential bus bar, copper strips of 150 mm x 25 mm x 6 mm sub equip-potential bus bar in relay room, power room and panel room. GI strip 25 mm x 2 mm for ring formation of earth pits Earth enhancement material in bags for each Earth Electrode. Inspection chamber of site 300 mm x 300 mm x 300 mm (Inside dimension) of approximate 50 mm thick with pulling hooks to cover the earth pits. Note: The installation of this item shall be carried out by the contractor as per RDSO Specs. No RDSO/SPN/197 Ver.1.0 or latest and conforming to RDSO Drg. No. SDO / RDSO/ E&B/001 or Latest.Inspection: Consignee"						
165	130301	250.00	Numbers	1496.00	374000.00	11.09	415476.60
	Description:- Supply of earth electrode mild steel galvanized, light class, IS:1239(PART-I)-1979.earth electrode pipe should be with 3 mm thick, 50 mm dia and perforated(staggered),5 mm dia holes, 2 nos per 305 mm length with clamp of MS FLAT(galvanised) of size 35 mm x 6 mm (SPEC.NO.226 STD). Earth pipe should include CI threaded cap. Materials to be procured and designed as per CSTE/ER'S DRG.NO.SI/TYP/0097 or latest.. Inspection: - Consignee						
166	130302	250.00	Numbers	911.00	227750.00	11.09	253007.48
	Description:- Supply of MS FLAT (SPEC. NO. 226 STD or latest) of size 35 mm x 6 mm with length 5 mtr with holes of 12 mm dia at both ends as per CSTE/ER'S DRG. NO. S&T-1/2007 (or latest). Inspection : by consignee.						
167	130303	250.00	Numbers	1161.00	290250.00	11.09	322438.72
	Description:- Fixing of earth electrode including laying and installation of MS flat of size 35 mm x 6 mm with length 5 mtr or as per extant practice of Eastern Railway. As per CSTE/ER'S DRG. NO. SI/TYP/0097 for apparatus cases, signal post & other equipment as per instruction of site engineer. Provision for fixing MS flat at apparatus cases/ signal post/other equipment should be made by the firm at site. Full threaded bolts of 10 mm dia and length 40 mm should be welded in the apparatus cases in such way that the MS flat at apparatus case end can be fixed from outside or from inside. Welding arrangement with accessories and welding materials should be arranged by the contractor for fixing of bolts at equipment end where required as per instruction of site engineer. All hardware and other miscellaneous materials required for installation to be supplied by the contractor except earth electrodes and MS flat. Note:-all materials required to be arranged by the contractor except 2 core cable will be supplied by the railway.						
168	130304	250.00	Numbers	571.00	142750.00	11.09	158580.98
	Description:- Provision of cement concrete enclosure for earth electrodes as per DRG. NO. S&T/C-36(NKG). This includes supply of all materials by the contractor duly inspected by consignee.						
	130401	3.00	Station	235844.00	707532.00	11.09	785997.30

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

169	Description:- Earthing of EI equipment, relay rack and power equipment etc. to be done along with the supply of all requisite materials, Earthing shall be in the form of Ring Earth conforming to RDSO spec RDSO/SPN/197 Ver.1.0 or Latest (with a minimum 10 maintenance free earth electrodes) and as per CSTE/ER/Kolkata's technical circular No.92, using copper rings with earth resistance less than 1 ohm. The earthing shall be maintenance free. The ring earth shall be connected to copper flat of size 25x3 mm in the relay room and IPS room. The copper flat fixed on the wall to the entire breadth of Relay room and IPS room as an earth bus bar and all earth connections shall be taken from it. A, B ,C & D class protection shall be provided for all EI equipment.Inspection: Consignee						
170	130504	1.00	Numbers	410718.00	410718.00	11.09	456266.63
	Description:- Supply of electronic Cable route tracer/locator with underground cable and pipe locating receiver and cable avoidance tool that provide location of armoured OFC , signalling and telecom , power cable etc. make : C Scope Stanley/3M Dynatel , model: DXL-4 DBG /2273M-iD 30 or Similar/ superior. Item to be supplied after successful demonstration and Approval of Railway. Inspection: Consignee						
171	130505	1.00	Numbers	4300.00	4300.00	11.09	4776.87
	Description:- Supply of Road Measuring Cycle, made of Aluminum with 05 digit counter, foldable with bag. Item to be supplied after successful demonstration and Approval of Railway.Inspection: Consignee						
172	130508	1.00	Numbers	58579.00	58579.00	11.09	65075.41
	Description:- Supply of Cable Fault Locator to localize the faults of underground cables. Aplab make (Model No.3049) OR C Scope Stanley make (Model TS-90) or Similar/ superior from any reputed make. It also includes supply of all accessories required to localize faults of underground cables. Item to be supplied after successful demonstration and Approval of Railway.Inspection: Consignee						
173	130509	1.00	Numbers	8761.00	8761.00	11.09	9732.59
	Description:- Supply of Digital Earth Resistance Tester for measurement of earth resistance with 3.5 digital LCD, 12.5 mm screen segment and Range -0.5 Ohms to 500 Ohms. WACO or Similar make. Item to be supplied after successful demonstration and Approval of Railway. Inspection: Consignee						
174	140101	200.00	Metre	19.00	3800.00	11.09	4221.42
	Description:- Supply of UTP CAT-6 cable make Siemen/ Systemax /Panduit/ Tyco/ Krone/ AMP or similar. Inspection: Consignee						
175	140301	100.00	Numbers	909.00	90900.00	11.09	100980.81
	Description:- "Supply of patch chord cable (10-meter-long) with FC/PC connectors compatible with SDH equipment as per TEC Specn.No.GR/OFFJ-02/01 May 2004 with latest Amendment. Inspection: Consignee."						
176	140401	3.00	Numbers	37570.00	112710.00	11.09	125209.54
	Description:- "Supply, installation and complete indoor wiring of 19 inch (42U) covered Rack of size 2035 mm x 600 mm x 600 mm (Approx.). The rack shall be complete with all fittings for housing SDH equipment, Primary MUXES, DDF, MDF using crone modules and other equipment like runway ladders etc. completely wired and equipped with integrated protection modules for all channels as per technical specifications and other stipulations of tender document. It should be possible to lock all the equipment with only order wire telephone remaining outside the rack. Inspection: Consignee."						
177	140501	3.00	Numbers	92728.00	278184.00	11.09	309034.61
	Description:- "Supply of SMPS based Battery Chargers as per RDSO Spec for Telecom use 48 volts, 25 Amps in 2+1 configuration modules of 25 Amps with ultimate expandable capacity 50 Amps, automatic switching between the modules as per RDSO Spec No. RDSO/SPN/TC/23/1999 version 4 or latest along with two potential free contacts. Inspection: (i) RDSO if value of item in work more than 5 lakhs (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs as per extant instructions by Railway Board."						
178	140502	3.00	Numbers	4578.00	13734.00	11.09	15257.10
	Description:- "Installation of Battery chargers, Power distribution Board along with MCBs of suitable ratings and wiring and commissioning of External alarm contacts through EMS. The work includes supply of battery rack, MCBs, battery cable and battery lugs and other accessories required for installation of power plant. Inspection: Consignee"						
179	140503	3.00	Numbers	89393.00	268179.00	11.09	297920.05
	Description:- Supply of 48Volt/200AH maintenance free VRLA Batteries duly charged as per IRS Spec. No. S-93/96(A) with amendments-1 or latest. Inspection: RDSO						
180	140504	3.00	Numbers	19268.00	57804.00	11.09	64214.46
	Description:- "Installation, wiring, testing & commissioning of 48Volt/200AH maintenance free VRLA Batteries duly charged as per IRS Spec. No. S-93/96(A) with amendments-1 or latest. Inspection: Consignee"						
181	140701	8.00	Numbers	5203.00	41624.00	11.09	46240.10
	Description:- "Supply of Universal 2/4 wire way side DTMF controln telephone as per RDSO spec. no. IRS: TC:82: 2005 (with Amdt. 3) or latest. Inspection: Consignee."						

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

182	140702	6.00	Numbers	3740.00	22440.00	11.09	24928.60	
	Description:- "Supply of power supply unit for telecom installation at way side station suitable to operate max 6 equipment of DTMF type (12V/7AH) battery with suitable battery charger) as per RDSO spec. No. IRS: TC-72-97 or latest. Inspection: consignee."							
183	140703	2.00	Numbers	6710.00	13420.00	11.09	14908.28	
	Description:- "Supply of 4W way station DTMF equipment as per RDSO spec. no IRS-TC 60/93 93 or latest (with 4 wire telephone as per spec. No IRS-TC 38/ 97 or latest. Make- Bentrion, Epsilon or similar and supply of 12V/7AH power supply unit for control phone. Inspection by Consignee"							
184	140704	2.00	Numbers	1257.00	2514.00	11.09	2792.80	
	Description:- "Installation of 4W way station DTMF equipment as per RDSO spec. no IRS-TC 60/93 or latest (with 4 wire telephone as per spec. No IRS-TC 38/97 or latest. Make- Bentrion, Epsilon or similar and supply of 12V/7AH power supply unit for control phone."							
185	140801	4.00	Station	10663.00	42652.00	11.09	47382.11	
	Description:- "Testing of all fibres of the optic fibre cable, quad, PIJF cable, ADMS, mux and other accessories installed above and final commissioning of optic fibre communication link conforming to railway's specification including end to end testing for realisation of optic fibre system. Inspection: Consignee."							
186	140802	8.00	Numbers	2782.00	22256.00	11.09	24724.19	
	Description:- "Supply of OFC Termination box as per TEC Spec No. TEC/GR/TX/FTB-02/02/APR-2010 with latest amendment including all miscellaneous & consumable for fibre splicing. It should have the capacity to terminate 02 No. 24 OFC cable through separate entry holes & to take out & terminate 6 or 24 pigtailed through separate exit holes. Make: JT Optics/Raychem/Aras Telecom/equivalent. Inspection-Consignee"							
187	141501	2.00	Station	9122.00	18244.00	11.09	20267.26	
	Description:- "Shifting and installation of control and other telecom equipment like control phone, magneto phone, auto phone, VHF sets, VF Repeaters etc. from old station building to new station building as per instructions of site engineer. All the material required for fixing and installation will be supplied by the contractor. Inspection: Consignee."							
188	141801	500.00	Metre	49.00	24500.00	11.09	27217.05	
	Description:- "Supply of 10 pair switchboard indoor copper cable 0.6 dia as per specification IRS:TC:24:91. or TEC/GR/WIR-06/03. MAR 2002 with latest amendment. Inspection: Consignee"							
189	141901	6.00	Numbers	149308.00	895848.00	11.09	995197.54	
	Description:- "Supply of 2 MB Programmable Primary Digital drop interface circuit to the Krone type. Inspection:(i) RDSO if value of item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy. insert multiplexer as per RDSO Specs. IRS TC- 68/2004 (Amnd.1) or latest with conference facility and other stipulation to tender documents and fully wired for 30 channels complete with power supply card, remote control, supervision facility and all other accessories, installation material, manuals etc. It should have facilities to accommodate data interface card in multi drop mode and should be able to support cards needed for video conferencing and ISDN. It shall support NMS installed at Test Room and may operate local/remote location of entire section. It also includes submission of all technical documents, manuals and supply of all miscellaneous items which will be required for final testing and commissioning of system. The above MUX should be equipped with following circuits: -i) 2 wire/ 4 wire E&M VF circuits (minimum 16 nos ckts) ii) Subscriber loop circuits (minimum 4 nos ckts) iii) Exchange loop interface circuits (minimum 8 circuits) iv) This also includes connecting all pigtailed, optical patch cords etc. to the SDH equipment. This also includes connection of SDH and primary MUX equipment with all interface cards to the 48V Bus including supply of wires and connectors termination of all evens on DDF taking PVC cable over runway or a wall and termination of VF interface circuit to the Krone type. Inspection : (i) RDSO if value of the item in work more than 5 lakhs or as per extant policy (ii) Consignee subject to procurement from RDSO approved vendors if value of whole item in work less than 5 lakhs or as per extant policy."							
	141902	6.00	Numbers	11372.00	68232.00	11.09	75798.93	

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

190	Description:- Installation, wiring, testing and commissioning of 2 MB Programmable Primary Digital drop insert multiplexer as per RDSO Specs. IRS TC- 68/2004 (Amnd.1) or latest with conference facility and other stipulation to tender documents and fully wired for 30 channels complete with power supply card, remote control, supervision facility and all other accessories, installation material, manuals etc. It should have facilities to accommodate data interface card in multi drop mode and should be able to support cards needed for video conferencing and ISDN. It shall support NMS installed at Test Room and may operate local/remote location of entire section. It also includes submission of all technical documents, manuals and supply of all miscellaneous items which will be required for final testing and commissioning of system. The above MUX should be equipped with following circuits: - i) 2 wire/ 4 wire E&M VF circuits (minimum 16 nos ckts) ii) Subscriber loop circuits (minimum 4 nos ckts) iii) Exchange loop interface circuits (minimum 8 circuits) iv) This also includes connecting all pigtails, optical patch cords etc to the SDH equipment. This also includes connection of SDH and primary MUX equipment with all interface cards to the 48V Bus including supply of wires and connectors termination of all evens on DDF taking PVC cable over runway or a wall and termination of VF interface circuit to the Krone type. All materials such as wires for Earthing & power supply, wire carrying aluminium ladder, MCB, Connectors, foundation bolts, nuts, base frame, mounting accessories for fitting of transformers, U-Link Panels, inter connecting cables etc. required for the above shall be supplied by the contractor.						
191	141903	3.00	Numbers	12252.00	36756.00	11.09	40832.24
	Description:- "Supply of Subscribe loop interface cards, minimum 4 circuits per card."						
192	141904	3.00	Numbers	12024.00	36072.00	11.09	40072.38
	Description:- "Supply of 2W/4W E&M interface cards, minimum 4 circuits per card"						
193	141905	3.00	Numbers	8151.00	24453.00	11.09	27164.84
	Description:- "Supply of Exchange loop interface card, 6 circuits per card"						
194	142001	3.00	Numbers	199228.00	597684.00	11.09	663967.16
	Description:- "Supply of standard 19""rack mountable , -48V DC working, Add-Drop STM-4 SDH equipment conforming to GR No. TEC/GR/TX/SDH - 010/03.Jan 2011 (with latest amendment) complete with redundant power supply, 2 no. STM 4 of aggregate L.4.2 Optical interfacemodules/Cards one each for East and west side, TX/RX and 2 nos. of STM-1 S 1.1 optical interface modules complete with 5 mtrs long optical fibre cords, 21 EIs with DDFs and cable assembly for termination to DDF and minimum 8 nos. of 10/100 Base-T Ethernet ports, Fast Ethernet on SDH [EoS] 10/100 Base-I interface module/card supporting with LCAS and GEP, order wire sub Rack DDF installation material, manuals and other accessories. Complete Engineering order wire (EOW) arrangement. Necessary/Firmware for local/remote monitoring/configuration of the equipment through EMS and Software/Firmware interface to work all Network elements as Gateway Network Element [GNE], 2 nos of MCBs of appropriate rating and necessary connecting cords and cables for power supply modules"						
195	142002	3.00	Numbers	23495.00	70485.00	11.09	78301.79
	Description:- Installation and commissioning of STM-4 in the existing rack with ready infrastructure or in new rack as desired by the site Engineer.						
196	142201	300.00	Metre	19.00	5700.00	11.09	6332.13
	Description:- "Laying of Power Cable/STP/UTP CAT-6/LS cablethrough flexible PVC Conduit Pipe/ GI Pipe/HDPE Pipe (where necessary) as per direction of the Rly.Representative, including any fixing of cables/PVC pipe/PVC Casing on wall/shed with suitable clamps (the clamps and screws should be made of Stainless steel). All the fixing materials including Collar, bend, junction etc. shall be supplied by the contractor. This also includes transportation of cable, PVC Pipe, GI Pipe, HDPE Pipe etc. to the site"						
197	142202	300.00	Metre	45.00	13500.00	11.09	14997.15
	Description:- "Laying of UTP/STP CAT-6 cable/power cable in PVC casing capping of appropriate size. The work also includes supply and fixing of casing and capping, fixing and connection of patch panel, fixing of CAT-6 cable with RJ 45 connectors. Work to be done as per instructions of site in-charge."						
198	142401	500.00	Metre	35.00	17500.00	11.09	19440.75
	Description:- Supply, installation, testing a commissioning of 2 core screened/shielded multistrand PVC insulated wire (24/0.2 mm dia) for speaker load line.						
199	142402	500.00	Metre	53.00	26500.00	11.09	29438.85
	Description:- Supply of screened 5 pair (10 core) color coded and twisted Data Communication Cable, each core made of Copper Conductor of 0.20 mm diameter(7/0.20mm) ABC (Annealed Bare Copper) & Polyethylene Insulated. Tolerance in dimensions should be within $\pm 10\%$.						
200	081601	2.00	Numbers	1225.00	2450.00	11.09	2721.70
	Description:- Casting, concreting and curing of foundation (1:3:6) and erection of SLB/BSLB/SB/WB/Stop board/Other Miscellaneous Board as per DRG. NO S&T/C /3 4 (NKG) all materials required for the work including cement, rail post etc. To be supplied by the contractor. This includes supply of SLB/BSLB/SB/WB/Stop board as per RDSO DRG NO. SA-2375 (ADV.) (WITH LATEST AMDT.) for SLB/BSLB and as per RDSO DRG NO. 7235/B (WITH LATEST AMDT.) for SB/WB/Stop Board. Supply. Inspection: Consignee.						

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

201	181602	2.00	Numbers	5720.00	11440.00	11.09	12708.70	
	Description:- Casting, concreting and curing of foundation (1:3:6) and erection of SLB/BSLB/SB/WB/Stop board/Other Miscellaneous Board as per DRG. NO S&T/C/34 (NKG) all materials required for the work including cement, rail post etc. To be supplied by the contractor. This includes supply of SLB/BSLB/SB/WB/Stop board as per RDSO DRG NO. SA-2375 (ADV.) (WITH LATEST AMDT.) for SLB/BSLB and as per RDSO DRG NO. 7235/B (WITH LATEST AMDT.) for SB/WB/Stop Board. Execution							
202	020401	1.00	Numbers	177112.00	177112.00	11.09	196753.72	
	Description:- "Supply of Micro Processor based Remote Terminal Unit (RTU) with 64 digital input & 16 analog input as per RDSO Spec. No. IRS (S) 99/2006 with Amdt. 3.0 or latest. It includes supply of all the items required for complete indoor relay room wiring from RTU to relay rack tag blocks, drawing/extension of power supply up to RTU. It includes supply of relay room door lock checking arrangement, commercial power supply monitoring arrangement & monitoring of DG sets, ELD (if installed), IPS, interlinking and networking of RTU It also includes supply of leased line MODEM, suitable online UPS (minimum 6 hours' backup) and other interfacing cards, if required for networking of Data Logger. Note: (1) Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No.STS/E/Data logger dtd.12.09.2011 or latest guidelines of Railway Board/RDSO/Zonal Railway. (2) Exceptional reports are to be generated by a computer connected to datalogger at the station and at a central location in Control Room. Datalogger software should be able to generate exceptional reports for maintenance, safety and operations as per latest guidelines of Railway Board/RDSO/Zonal Railway. Datalogger to be installed at Site by OEM. Manufacturing date of RTU and printer should be of current year at the time of supply. Inspection: RDSO"							
203	020501	1.00	Numbers	19811.00	19811.00	11.09	22008.04	
	Description:- "Installation, wiring, testing & commissioning of Micro Processor based Remote Terminal Unit (RTU) with 64/128 digital input & 16 analog input as per RDSO Spec. No. IRS (S) 99/2006 with Amdt. 3.0 or latest. It covers complete indoor relay room wiring from RTU to relay rack tag blocks, drawing/extension of power supply up to RTU. It includes relay room door lock checking arrangement, commercial power supply monitoring arrangement & DG sets, ELD (if installed), IPS, interlinking and networking of RTU. All material required for wiring, networking, power supply monitoring, door-locking arrangement etc. will be supplied by contractor. Note: Total numbers of relays and other signalling functions/gears required to be wired as per list circulated vide RDSO Letter No.STS/E/Data logger dtd.12.09.2011 or latest guidelines of Railway Board/RDSO/Zonal Railway. Networking of data logger includes extraction of data report from Control room. Exceptional reports are to be generated by a computer connected to datalogger at the station, EI Huts, LC Gates, AFTC Huts etc. and at a central location in Control Room. Datalogger software should be able to generate exceptional reports for maintenance, safety and operations as per latest guidelines of Railway Board/RDSO/Zonal Railway. Datalogger to be installed at Site by OEM. For networking, required communication channel (Quad/ OFC cable) will be arranged/provided by Rly in SM/ASM's room or in OFC/AUTO/EI Huts/LC Gates etc. and it will be extended by contractor up to location of data logger by using CAT-5/6 telecom cable with proper casing and capping. The contractor will supply all the material like CAT-5/6 telecom cable, casing & capping, nuts, bolts etc. The final commissioning will be done after filling up of Pre- Commissioning checklist (circulated by RDSO) with the OEM representative. Datalogger to be validated and commissioned before simulation test and put in network, validation statement should be jointly signed by railway engineer (open line), railway engineer (construction) & OEM'S engineer before simulation test with name, designation and date. Payment for this item will be released only after submission of duly signed pre-commissioning checklist of data logger in standard RDSO format, joint signature of validation statement. OEM'S engineer will also impart training to rly staff at site for proper functioning /working and applications of data logger. Inspection: Consignee."							
204	071002	3.00	Pair	988361.00	2965083.00	11.09	3293910.70	
	Description:- "Supply of Block Panel BPAC (Block Proving with digital axle counter) using UFSBI as per specification IRS: S-105/2012Ver.0 with latest amendment for single line operation. NOTE: One set will include equipment required for one complete Single Line Block Section except DAC. This includes Relay, Relay Base retaining clip & connectors to be supplied by the contractor along with the UFSBI. Inspection: RDSO."							
205	071004	3.00	Pair	68461.00	205383.00	11.09	228159.97	
	Description:- "Supply of Modem for UFSBI for use with secondary media OFC/Quad. The modem shall be complete with existing system as per RDSO/SPN/147/2005 with amendment -1 or latest. Inspection: Consignee"							
206	071005	3.00	Pair	18546.00	55638.00	11.09	61808.25	
	Description:- Installation and commissioning of modem & media change over as above. Note: all required materials for execution to be supplied by the contractor.							
207	071006	3.00	Pair	72276.00	216828.00	11.09	240874.23	
	Description:- Installation, Testing & commissioning of Block proving by Axle Counter (BPAC) including UFSBI equipment as per standard practice & directive of engineer in charge and as per OEM guidelines. Inspection: Consignee							

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

208	051203	100.00	Metre	1362.00	136200.00	11.09	151304.58	
	Description:- Supply and laying of 70 sq.mm PVC insulated flexible tinned electrolytic copper down conductor placed in a metallic / PVC protective covering wherever exposed to human intervention including saddles and all accessories as required. Supply material inspection by consignee.							
209	051204	3.00	Job	44808.00	134424.00	11.09	149331.62	
	Description:- "Supply & fixing of equipotential earth bonding unit between electrical & equipment Earthing in a explosion proof IP68 enclosure with inspection chamber for equipotential bonding during a surge. Supply material inspection by consignee."							
210	051205	60.00	Metre	1377.00	82620.00	11.09	91782.56	
	Description:- "Supply & laying of 25x3 mm pure electrolytic copper tape through suitable CLASS-'B' GI pipe for loop Earthing and bonding as per site requirement. Supply material inspection by consignee."							
211	142101	4.00	Numbers	23599.00	94396.00	11.09	104864.52	
	Description:- "Supply of 25-Watt VHF synthesised trans receiver set, synthesised in frequency band 136 MHz to 174 MHz (full band), with DTMF microphone and cords, with GP antenna, 30 m of feeder cable and suitable BNC connectors, with 3m of power cord and 12V/13.5V 10Amp/15Amp power supply suitable for 25W VHF set, as per RDSO spec. RDSO/SPN/TC/107/2018, Rev. 0.0 Amdt 1 or latest."							
212	142102	4.00	Numbers	20742.00	82968.00	11.09	92169.15	
	Description:- "Supply of DC-DC converter. for emergency communication through V.H.F. as per specification - the DC DC converter shall be independent for each vhf base equipment (voice equipment) and shall allow to work from -48V nominal input (-48V to -60V variation) & output 12V DC. The power capacity to deliver 10A current with output short circuit protection & ripple voltage less than 5mv for telecom circuit. Short circuit current not more than 2 mA, input-output insulation by 2.5 KV, load & output regulation +/-1% with ERTL certification. Make: DACS, Pune or Webfil Kolkata or Machronics, Kolkata or similar. Inspection: consignee."							
212	142103	4.00	Numbers	13837.00	55348.00	11.09	61486.09	
	Description:- "Supply of Buffer amplifier for emergency communication through V.H.F. As per voice frequency channel shall be 600 ohms balanced 4W (viz. 2W for transmit, 2W for receive) and 2W for E&M signalling. The nominal voice frequency signal shall be 0 dbm level the buffer amplifier should work of -48vdc or can from the DC-DC converter. Burn in of the complete equipment at 55 degree centigrade to avoid infancy failures. During the test the equipment shall be kept continuously on. Inspection - Consignee"							
213	142104	4.00	Numbers	6985.00	27940.00	11.09	31038.55	
	Description:- "Supply, fixing and wiring of surge protection device in attachment plug module with replaceable surge protection for coaxial signal, interfaces N-connector plug/socket installed as surge protection between antenna and 25 W VHF sets, make- Phoenix Contact model CN-UB-280DC-SB-2818148 or similar as per specifications. this includes mounting plate and reserve gas filled surge arrester (one no.) with all required connectors/clamp for commissioning of SPD at site. Inspection: Consignee"							
214	142105	4.00	Numbers	6190.00	24760.00	11.09	27505.88	
	Description:- "Installation, testing and mounting of G.P. antenna on a GI pipe which is to be fitted on the roof of equipment room and lightning arrestors also to be mounted on a GI pipe. All fixing materials to be supplied by the tenderer and left-over material to be returned to the railway store. N.B. G.P. Antenna, GI pipe (50 mm dia) and lightning arrester will be supplied by the railway. Installation to be done as per Technical advisory guide lines of PCSTE/E.Rly's vide Letter No-SG.203/3/RDSO Dated 26.09.2025"							
215	142106	4.00	Numbers	2102.00	8408.00	11.09	9340.45	
	Description:- "Installation, testing & commissioning of operating panel room VHF/SIMPLEX VHF base equipment, DCDC simplex VHF base equipment, DC-DC converter, buffer amplifier and laying of co-axial cable simplex VHF base equipment, DC-DC converter, buffer amplifier should be mounted on rack of suitable size and other fixing arrangement. Installation to be done as per Technical advisory guide lines of PCSTE/E.Rly's vide Letter No-SG.203/3/RDSO Dated 26.09.2025"							
216	122401	100.00	cum	3596.00	359600.00	11.09	399479.64	
	Description:- "Cement concrete work for miscellaneous items in the ratio 1: 3: 6. Item includes excavation, ramming, curing and plastering with cement & sand mixture (aggregate not exceeding 3.8 cm.) (Aggregate cement & sand to be supplied by the contractor). Wherever depth of 0.5 m cable trench is not feasible, cable shall be protected as: - Preparation of cement mixture 1:3:6 with contractor's own materials and spreading cement concrete mixture layer of 100 mm thick over the already laid cables in the excavated trench."							
217	122501	80.00	cum	1991.00	159280.00	11.09	176944.15	
	Description:- "Providing brick masonry in ratio 1:6 cement and mortar including plastering with 1:4 cement and sand mixture both sides, 20 mm thick each with contractor's owned class II bricks, including excavation, curing, grouting, bolting etc. wherever required. Bricks, sand and cement to be supplied by the contractor"							

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

218	100202	4.00	Numbers	2902.00	11608.00	11.09	12895.33	
	Description:- "Supply of Office Chair make Godrej CH-7B or similar of reputed brand.Inspection: Consignee"							
219	100203	2.00	Numbers	9032.00	18064.00	11.09	20067.30	
	Description:- "Supply of Office Revolving Chair Godrej Make Model No.9U02R Bravo or Similar of reputed brand. Inspection: Consignee"							
220	100205	3.00	Numbers	17163.00	51489.00	11.09	57199.13	
	Description:- Supply of Steel Plain Almirah with 4 adjustable slaves Size: 1980mm height, 915 mm width and 485 mm depth. Make: Godrej Storewel Plain Large or Similar of reputed brand. Inspection: Consignee							
221	100207	2.00	Station	608777.00	1217554.00	11.09	1352580.74	
	Description:- Supply , Installation, testing & commissioning of new modular / pyrotech workspace make or Cosmos or similar, new Modular control desk for provision of two numbers of monitors of size as advised by Site Engineer in "SLAT" system as per approved drawing (attached with tender document) This item includes : (i) Desktop made of 12 mm ASS + ASS 12 mm MDF (ii) structure : powder coated aluminium sturdy structure and extreme side aesthetic legs (iii) shutters : 18mm MDF (iv) proper cooling arrangement for CPR cabinet (v) 2mm thick extruded aluminium "SLAT" wall . The workspace will be provided for storage in SLAT system, this includes space for housing two numbers of embedded PC , 2 No. of FDMS and their power supply arrangement with proper ventilation. This includes supply of two chairs (Godrej PCH 7002 D or superior , as approved by Engineer in charge) for operators to be supplied. Inspection: Consignee							
222	071003	3.00	Pair	35182.00	105546.00	11.09	117251.05	
	Description:- Supply of Automatic Media changeover system of Modem working on redundant channel for data transmission on OFC/Quad/ microwave radio, for seamless operation of UFSBI over multiple media. Inspection: Consignee							
223	MISC	1.00	Lumpsum	5000000.00	5000000.00	11.09	5554500.00	
	Description:- Unforeseen Revised USSOR(S&T)-Nov'23							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 02-Group-B1 Non-SOR Items Category 1							46598621.00	Above/ Below/Par
01	NS01	10.00	Numbers	1813.00	18130.00	AT Par	18130.00	
	Description:- FIXING OF OUTDOOR CABLE TERMINATION BOX OR TERMINATION OF OUTDOOR PIJF TELECOM CABLE INSTALLATION PORTION INCLUDING FIXING OF CT BOX ON WALL / INSIDE LOCATION BOX TERMINATION OF CABLE IN CT BOX & SEALING. CABLE TERMINATION BOX. SPEC.NO. IRS-TC-18-75 OR LATEST. INSPECTION:CONSIGNEE.20 PAIRS. (i) SUPPLY							
02	NS02	10.00	Numbers	1474.00	14740.00	AT Par	14740.00	
	Description:- FIXING OF OUTDOOR CABLE TERMINATION BOX OR TERMINATION OF OUTDOOR PIJF TELECOM CABLE INSTALLATION PORTION INCLUDING FIXING OF CT BOX ON WALL / INSIDE LOCATION BOX TERMINATION OF CABLE IN CT BOX & SEALING. CABLE TERMINATION BOX. SPEC.NO. IRS-TC-18-75 OR LATEST. INSPECTION:CONSIGNEE.20 PAIRS. (ii) EXECUTION							
03	NS03	50.00	Numbers	126.00	6300.00	AT Par	6300.00	
	Description:- SUPPLY OF PIPE LOCK WITH KEYS. INSPECTION- CONSIGNEE.							
04	NS04	50.00	Numbers	1082.00	54100.00	AT Par	54100.00	
	Description:- SUPPLY & INSTALLATION OF TRACK BATTERY CHARGER FAILURE THROUGH LED DISPLAY INDICATION (RED-FAILURE, GREEN-OK) DISPLAY BOARD WITH AUDIO BUZZER AT ASM/SM ROOM USING POTENTIAL FREE CONTACTS OF TRACK BATTERY CHARGERS.INSPECTION-CONSIGNEE Note-One indication of RED and GREEN is quantified as one.							
05	NS05	400.00	cum	6114.00	2445600.00	AT Par	2445600.00	
	Description:- "PROVISION OF GUARD WALL TO PROTECT SIGNAL GEARS/LOCATION BOS TO TEALT INCLUDING SUPPLY OF ALL MATERIALS BY THE CONTRACTOR."							
06	NS06	3.00	IBH/LC Gate/Auto Hut	44852.00	134556.00	AT Par	134556.00	
	Description:- PAINTING OF ALL EQUIPMENTS SUCH AS SIGNALS, SHUNT SIGNALS / CALLING-ON SIGNALS, ELECTRIC POINT MACHINES, TRACK CIRCUIT EQUIPMENTS, APPARATUS CASES, ROD RUNS AND ITS ACCESSORIES, JUNCTION BOXES, TRACK LEAD JUNCTION BOXES INCLUDING EXISTING GEARS ETC. PAINTING SHALL CONSISTS "2 COATS" OF"PRIMER " AND "3 COATS " OF "FINAL PAINT".							
	NS07	2.00	IBH/LC Gate/Auto Hut	23070.00	46140.00	AT Par	46140.00	

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

07	Description:- MARKING OF ALL CIRCUIT PARTICULAR NEAR TERMINALS ON TERMINAL BOARD / RACK IN APPARATUS CASES, JUNCTION BOXES AND NOMENCLATURE RELAYS, FUSES, EQUIPMENTS AS PER APPROVED DRAWING.NOTE :- (i) BEFORE PAINTING CLEANLINESS TO BE CHECKED BY THE SITE ENGINEER.(ii)SCRAPPING, CLEANING, PAINTING AND LETTERING OF ALL NEW AND EXISTING GEARS. THIS INCLUDES SUPPLY OF ALL PAINT SYNTHETIC ENAMEL, RED LEAD, BERGER OR SIMILAR. (iii)ALL THE MATERIALS WILL BE SUPPLIED BY THE CONTRACTOR.						
08	NS08	4.00	Stn/IBH	42106.00	168424.00	AT Par	168424.00
	Description:- TRANSPORTATION OF RELEASED MATERIALS (INDOOR & OUTDOOR) EXCEPT RAIL POST OF OVER HEAD ALIGNMENT TO SCRAP YARD AT BELLUR OR NEAREST SCRAP DEPOT.						
09	NS09	8000.00	Kilometre	73.00	584000.00	AT Par	584000.00
	Description:- LOADING, UN-LOADING & TRANSPORTATION OF MATERIALS INCLUDING CABLES, LOCATION BOXES, RELAYS,POINT MACHINES AND MISCELLANEOUS ITEMS REQUIRED FROM VARIOUS PLACES IN 9MT OR BIGGER TRUCK TO THE RAILWAY STORES AS PER SITE ENGINEER. TRANSPORTATION OF MATERIALS						
10	NS10	20.00	Per Trip	2816.00	56320.00	AT Par	56320.00
	Description:- LOADING, UN-LOADING & TRANSPORTATION OF MATERIALS INCLUDING CABLES, LOCATION BOXES, RELAYS,POINT MACHINES AND MISCELLANEOUS ITEMS REQUIRED FROM VARIOUS PLACES IN 9MT OR BIGGER TRUCK TO THE RAILWAY STORES AS PER SITE ENGINEER. LOADING & UNLOADING						
11	NS11	2.00	Numbers	131698.00	263396.00	AT Par	263396.00
	Description:- TESTING & COMMISSIONING OF STATION WITH OUTDOOR SIGNALLING GEARS INSTALLED AT STATION & YARD AS A WHOLE INCLUDING PHASE WORKING. TESTING SHALL BE CARRIED OUT BY THE ENGINEER IN CHARGE OF WORK WITH THE HELP OF ENGINEER OF THE CONTRACTOR & OTHER TECHNICAL REPRESENTATIVE OF CONTRACTOR TO ENSURE COMPLIANCE OF SEM, RE MANUAL & GUIDE LINES ISSUED BY RAILWAY AUTHORITY / RAILWAY BOARD / RDSO. (I)STATION(Central mode) /CABIN (Distributed Mode)						
12	NS12	180.00	Man-Days	472.00	84960.00	AT Par	84960.00
	Description:- SUPPLY OF LABOUR (HELPER) FOR INSTALLATION & TAKING MEASUREMENT OF SIGNALLING GEARS, ASSISTANCE TO INSPECTORS/OFFICERS DURING SUPERVISION OF FIELD WORK IN MEASUREMENTS, BY ACTING AS LOOK OUT MEN, CHOWKIDARS, PATROLMEN, ETC AND TO ASSIST IN OFFICE WORK. AS PER INSTRUCTION OF ENGINEER-IN-CHARGE OR HIS REPRESENTATIVE. FOR SAFETY RELATED WORKS, COMPETENCY WILL BE ENSURED BY THE INSPECTOR CONCERNED. THE INSPECTOR CONCERNED WILL MAINTAIN PROPER RECORD OF SUPPLY OF LABOURERS BY THE AGENCY.						
13	NS13	75.00	Kilometre	2091.00	156825.00	AT Par	156825.00
	Description:- FINAL LOCATION SURVEY,CABLE ROUTE SURVEY, PREPARATION OF CABLE ROUTEPLAN, SYSTEM DESIGN AND EQUIPMENT LAYOUT PLAN AS PER TECHNICAL SUPPLEMENT.NOTE-FIRST PROPOSED CABLE ROUTE PLAN SHOULD BE PREPARED AND GET APPROVED THEN AFTER EXECUTION OF WORK EXACT CABLE ROUTE PLAN SHOWING ALL DETAILS SHOULD BE SUMMITTED.						
14	NS14	365.00	Day	2669.00	974185.00	AT Par	974185.00
	Description:- "RAPID MAINTENANCE & REPAIRING OF LAID CABLE/ EXISTING CABLES / EXPOSED CABLES / CUT CABLES DURING SITE WORK AS PER INSTRUCTION OF SITE ENGINEER. THE MAINTENANCE & REPAIRING GANG SHOULD HAVE THEIR OWN MAINTENANCE & REPAIRING TOOLS AND MEASURING INSTRUMENTS AND THEY SHOULD COMPRISES OF (1) ONE HIGHLY SKILLED STAFF(ii) ONE SKILLED STAFF & (iii) TWO UN-SKILLED STAFF FOR THIS PURPOSE OF WORK. ALL MATERIALS FOR THE MAINTENANCE & REPAIRING OF LAID CABLE/ EXISTING CABLES / EXPOSED CABLES / CUT CABLES WILL BE SUPPLIED BY RAILWAYS."						
15	NS15	3.00	System	425823.00	1277469.00	AT Par	1277469.00
	Description:- "RAPID MAINTENANCE & REPAIRING OF LAID CABLE/ EXISTING CABLES / EXPOSED CABLES / CUT CABLES DURING SITE WORK AS PER INSTRUCTION OF SITE ENGINEER. THE MAINTENANCE & REPAIRING GANG SHOULD HAVE THEIR OWN MAINTENANCE & REPAIRING TOOLS AND MEASURING INSTRUMENTS AND THEY SHOULD COMPRISES OF (1) ONE HIGHLY SKILLED STAFF(ii) ONE SKILLED STAFF & (iii) TWO UN-SKILLED STAFF FOR THIS PURPOSE OF WORK. ALL MATERIALS FOR THE MAINTENANCE & REPAIRING OF LAID CABLE/ EXISTING CABLES / EXPOSED CABLES / CUT CABLES WILL BE SUPPLIED BY RAILWAYS."						
16	NS16	120.00	Day	3376.00	405120.00	AT Par	405120.00
	Description:- PROVISION OF COMPUTER OPERATOR INCLUDING SUPPLY OF DESK TOP PC (CORE I5 - 4 GB RAM,500 GB HDD, 18.5" TFT SCREEN) WITH UPS, PRINTER (DESK JET D 1560 OR SIMILAR) ON HIRE BASIS AT SITE OR AS PER SITE ENGINEER. THIS INCLUDES SUPPLY OF PRINTING DOCUMENTS INCLUDING SUPPLY OF PRIINTER PAPER A - 4 & LEGAL SIZE - (4 + 1 = 5 REAMS PER MONTH) PRINTER CRTRIDGE hp 21 BLACK - 2 NOS & hp 22 TRICOLOUR - 2 NOS PER MONTH. THIS ALSO INCLUDES SUPPLY OF 2 NOS COMPUTER OPERATOR WITH KNOWLEDGE OF AT LEAST MS OFFICE, AUTO CAD ETC. TO OPERATE HIRED COMPUTER AND PERFORM COMPUTER ORIENTED WORK, PRINTING OF COMPUTED OUTPUT DOCUMENT ETC. AS PER DIRECTION OF SITE ENGINEER. Note-Printer Model and Cartridge No. may be changed as per latest models.						

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

17	NS17	60.00	Day	1291.00	77460.00	AT Par	77460.00	
	Description:- ROUND THE CLOCK MAINTENANCE OF THE ENTIRE SYSTEM FOR THE PERIOD OF 30 / 60 / 90 / 180 DAYS FOR EACH STATION AFTER COMMISSIONING OF STATIONS(PER SHIFT STAFF :- (1) SUPERVISOR - 1, (2) ARTISAN STAFF - 2) ALONG WITH THE RELEVANT MATERIALS REQUIRED FOR SMOOTH MAINTENANCE OF ENTIRE SYSTEM.							
18	NS18	6.00	Numbers	13831.00	82986.00	AT Par	82986.00	
	Description:- Supply of Ultrasonic rat/rodentrepellent device for S&T relay room/equipment room. Specification:coverage area minimum 2500 sq ft.,Sound output 80 db, input voltage100-240 AC 50 Hz, Operating Frequency :20-100 kHz, separate Volume &Frequency Adjustable Control knob of10 steps. Warranty as per make.Product to be make of ERSTE TECHNOLOGY, shyam innovations, ULTRARAT or similar reputed company							
19	NS19	200.00	Square Foot	857.00	171400.00	AT Par	171400.00	
	Description:- Supply and installation of STEEL WIREMESS WITH ALUMINIUM FRAME at thewindow of S&T relay room/equipmentroom. This includes supply,transportation of all the materialsrequired for the installation at the siteand fixing of wire mess by providingaluminium frame of required size andas per the direction of site engineer.							
20	NS20	2000.00	Metre	63.00	126000.00	AT Par	126000.00	
	Description:- LAYING/INSTALLATION OF SPLIT DOUBLE WALL CORRUGATED (DWC) PIPE IN THE CABLE TRENCH PARALLEL TO TRACK OR AS PER SITE ENGINEER AND APPROVED CABLE ROUTE PLAN. THIS INCLUDES SUPPLY OF SPLIT DOUBLE WALL CORRUGATED PIPES(DWC) OF HDPE CONFORMING TO IS:14930 (PART-II) (ISI MARKED ON PIPE) WITH IP:67 PROTECTION OF SIZE MINIMUM OUTER DIA 175 mm & MINIMUM INNER DIA 148 MM WITHOUT SOCKET/COUPLER. THE HDPE PIPE SHOULD HAVE ANTI RODDENT PROPERTIES & FIRE RESISTANT TO TEC SPECIFICATION GR/ DWC /34 / 01 SEPT'07 WITH LATEST AMMENDMENTS. INSPECTION:-BY RITES. (i) EXECUTION							
21	NS21	2000.00	Metre	731.00	1462000.00	AT Par	1462000.00	
	Description:- LAYING/INSTALLATION OF SPLIT DOUBLE WALL CORRUGATED (DWC) PIPE IN THE CABLE TRENCH PARALLEL TO TRACK OR AS PER SITE ENGINEER AND APPROVED CABLE ROUTE PLAN. THIS INCLUDES SUPPLY OF SPLIT DOUBLE WALL CORRUGATED PIPES(DWC) OF HDPE CONFORMING TO IS:14930 (PART-II) (ISI MARKED ON PIPE) WITH IP:67 PROTECTION OF SIZE MINIMUM OUTER DIA 175 mm & MINIMUM INNER DIA 148 MM WITHOUT SOCKET/COUPLER. THE HDPE PIPE SHOULD HAVE ANTI RODDENT PROPERTIES & FIRE RESISTANT TO TEC SPECIFICATION GR/ DWC /34 /01 SEPT'07 WITH LATEST AMMENDMENTS. INSPECTION:-BY RITES. (ii) SUPPLY							
22	NS22	500.00	Metre	71.00	35500.00	AT Par	35500.00	
	Description:- LAYING/INSTALLATION OF SPLIT DOUBLE WALL CORRUGATED (DWC) PIPE IN THE CABLE TRENCH PARALLEL TO TRACK OR AS PER SITE ENGINEER AND APPROVED CABLE ROUTE PLAN. THIS INCLUDES SUPPLY OF SPLIT DOUBLE WALL CORRUGATED PIPES(DWC) OF HDPE CONFORMING TO IS:14930 (PART-II) (ISI MARKED ON PIPE) WITH IP:67 PROTECTION OF SIZE MINIMUM OUTER DIA 250 mm & MINIMUM INNER DIA 217 MM WITHOUT SOCKET/COUPLER. THE HDPE PIPE SHOULD HAVE ANTI RODDENT PROPERTIES & FIRE RESISTANT TO TEC SPECIFICATION GR / DWC / 34 /01 SEPT'07 WITH LATEST AMMENDMENTS. INSPECTION : INSPECTION BY RITES [FOR VALUE OF MATERIAL ABOVE RS. 5.0 LAKHS.]. INSPECTION BY CONSIGNEE [FOR VALUE OF MATERIAL BELOW THAN RS 5.0 LAKH] (i) EXECUTION							
23	NS23	500.00	Metre	879.00	439500.00	AT Par	439500.00	
	Description:- LAYING/INSTALLATION OF SPLIT DOUBLE WALL CORRUGATED (DWC) PIPE IN THE CABLE TRENCH PARALLEL TO TRACK OR AS PER SITE ENGINEER AND APPROVED CABLE ROUTE PLAN. THIS INCLUDES SUPPLY OF SPLIT DOUBLE WALL CORRUGATED PIPES(DWC) OF HDPE CONFORMING TO IS:14930 (PART-II) (ISI MARKED ON PIPE) WITH IP:67 PROTECTION OF SIZE MINIMUM OUTER DIA 250 mm & MINIMUM INNER DIA 217 MM WITHOUT SOCKET/COUPLER. THE HDPE PIPE SHOULD HAVE ANTI RODDENT PROPERTIES & FIRE RESISTANT TO TEC SPECIFICATION GR/ DWC / 34 /01 SEPT'07 WITH LATEST AMMENDMENTS. INSPECTION : INSPECTION BY RITES [FOR VALUE OF MATERIAL ABOVE RS. 5.0 LAKHS.]. INSPECTION BY CONSIGNEE [FOR VALUE OF MATERIAL BELOW THAN RS 5.0 LAKH] (ii) SUPPLY							
24	NS24	1.00	Numbers	680000.00	680000.00	AT Par	680000.00	
	Description:- "Rail Drill Machine as per Specification attached. (Warranty Period : Upto 30 months from the date of supply"							
25	NS25	30.00	Metre	111.00	3330.00	AT Par	3330.00	
	Description:- FIXING OF ALLUMINIUM LADDERINSIDE THE EQUIPMENT ROOM FORDRAWING INTER CONNECTIONCABLES OR WIRES ETC . ITINCLUDES GROUTING OF LADDERON THE WALL OR AS DIRECTED BYENGINEER IN-CGARGE. ALL THEMATERIALS FOR FIXING THE SAMETO BE SUPPLIED BY THE TENDERER.THE RATE INCLUDESTRANSPORTATION OF LADDER FROMTHE RAILWAY STORE TO THEREPEATER STATION AND RETURNINGLEFTOVER MATERIALS TO THERAILWAY STORE,							
26	NS26	20.00	Numbers	1288.00	25760.00	AT Par	25760.00	
	Description:- SUPPLY OF PUSH BUTTON AUTOTELEPHONE RDSO SPEC. NO.DOT/TEC/G/TEL-02/02-DEC'95 ORLATEST. INSPECTION: CONSIGNEE							
	NS27	3.00	Set	73670.00	221010.00	AT Par	221010.00	

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

27	Description:- SUPPLY OF CONNECTORS, ADAPTORS& BARE FIBRE ADAPTORS FOROPTICAL HEADS INCLUDING PATCHCHORD. (i) TWO SETS FOR FIBCOMSTM (ii) TWO SETS FOR TEJAS STM.NOTE:- QUANTITY AS PER SITEENGINEER. INSPECTION-CONSIGNEE.						
28	NS28	3.00	Numbers	10772.00	32316.00	AT Par	32316.00
	Description:- SUPPLY OF FIBRE DISTRIBUTIONFRAME (24/48 FIBRE) AS PER TECSPECIFICATION NO. G/FDF-01/01JAN 93 WITH LATEST AMMENDMENTINCLUDING ALL MISCELLANEOUSITEM CONSUMABLES FOR FIBRESPLICING AND 24 NO FC/PC ORSC/PC OR AS SUITABLECONNECTOR. INSPECTION:CONSIGNEE.						
29	NS29	50.00	Numbers	757.00	37850.00	AT Par	37850.00
	Description:- SUPPLY OF PIG TAIL (10M LONG) ASPER TEC SPEC. NO. G/OF J-01/03JUN 99 WITH BLATEST AMENDMENT.INSPECTION: CONSIGNEE						
30	NS30	3.00	Numbers	33374.00	100122.00	AT Par	100122.00
	Description:- SUPPLY OF LI OPTICAL CARD FORSTM-1/STM-4 CROSS SECTION STM1OPTICAL LEVEL. NOTE -INSPECTION:CONSIGNEE.						
31	NS31	3.00	Numbers	31974.00	95922.00	AT Par	95922.00
	Description:- SUPPLY OF 8 PORT ELECTRICALETHERNET CARD OF 10/100 Mbps SUITABLE FOR ADM UNIT ABOVE-INSPECTION BY RDSO.						
32	NS32	10.00	Numbers	319.00	3190.00	AT Par	3190.00
	Description:- SUPPLY OF E CAT6 I/O BOX WITHMODULE. INSPECTION : CONSIGNEE						
33	NS33	10.00	Numbers	10.00	100.00	AT Par	100.00
	Description:- FIXING AND TERMINATION OF E CAT6 SINGLE I/O WITH MODULE						
34	NS34	10.00	Numbers	191.00	1910.00	AT Par	1910.00
	Description:- SUPPLY OF2 MTRS. E CAT6 PATCHCHORD CABLE (MAKE D LINK ORSIMMILAR). INSPECTION :CONSIGNEE						
35	NS35	500.00	Metre	54.00	27000.00	AT Par	27000.00
	Description:- SUPPLY OF MIC CABLE 2 CORECOTTON BRADED SIZE 19/40 FOR PASYSTEM MAKE ; FALCON/ MX/NEUTIC MINIMUM LENGTH 30METERS. Inspection: Consignee						
36	NS36	6.00	Numbers	1084.00	6504.00	AT Par	6504.00
	Description:- INSTALLATION OF HORN TYPE LOUDSPEAKERS AT DIFFERENTLOCATIONS AS PER SITEREQUIREMENT AS ADVISED BY THESITE ENGINEER. ALL THE FIXINGMATERIAL SHALL BE SUPPLIED BYTHE CONTRACTOR.						
37	NS37	50.00	Metre	34.00	1700.00	AT Par	1700.00
	Description:- SUPPLY OF ROLLED FLEXIBLE PVCCONDUIT PIPE 25 MM DIA WITH ISIMARK. INSPECTION : CONSIGNEE						
38	NS38	3.00	Pair	885508.00	2656524.00	AT Par	2656524.00
	Description:- SUPPLY AND INSTALLATION OF ELECTRONICS ALONG WITH OTHER REQUIRED ITEMS FOR UFSBI/SIL-4 MUX INTERFACE SHOULD BE CONFORMING TO IRS: S-104/2012 VER. 0 WITH LATEST AMENDMENT OR FAILSAFE NETWORK MULTIPLEXER AS PER RDSO DRAFT SPECIFICATION RDSO/SPN/211/2022 (LATEST VERSION) WITH PRE-WIRED CABINETS, MEDIA CHANGEOVER SYSTEM, SECONDARY MODEM ALONG WITH OTHER ACCESSORIES AS ALL TYPE OF RELAYS, IO GATHERER FOR EXCHANGE OF INFORMATION OF SIGNAL ASPECT, TRACK INFORMATION AND ANY OTHER VITAL INFORMATION BETWEEN HUTS,ACHIEVING THE FUNCTIONAL & CIRCUITRY REQUIREMENT FOR COMMISSIONING OF AUTOMATIC SIGNALLING SYSTEM IN THE SECTION.						
39	NS39	3.00	Numbers	66720.00	200160.00	AT Par	200160.00
	Description:- "Supply and installation of ""FRANKLIN ROD"" as per NFPA- 780 Standards. Installation to be done as per ER Drawing No. SI/TYP/103, dated 08.08.2025. It also includes connection of down conductor with Franklin Rod and running of down conductor through PVC pipes and connecting the same to nearby earth electrode. All material required for installation to be supplied by the contractor. Inspection- Consignee."						
40	NS40	20.00	Set	588820.00	11776400.00	AT Par	11776400.00
	Description:- Single Section Digital axle Counter Phase Reversal type as per RDSO Specification No. RDSO/SPN/177/2012 (Version -3) and latest if any. Each Set consists of following:- a) High frequency TX Coil and RX Coil with Cables (Each Set consists of CLAMP type TX Coil 2 Nos., RX Coil 2 Nos. along with 10 mtrs.Cable) = 2 Sets. One Set will be subtted with SSDAC during installation and one Set will be kept as Spare with the Consignee. b) Track Side Digital Axle Counter unit 2 Nos. c) VR Box 2 Nos. Each duly wired with 2 nos. of 24V, 6F/6B, 1000 ohm Q type relays. d) Clamp with deflector plates and hardware etc. 4 nos. e) Reset Box 2 nos. f) All other Equipment/Subsystem/literature as available in Standard Set as per RDSO Specification.(ii) Mushroom/Location Box suitable for housing Track side equipment = 2 nos Make: CEL of M/s Central Electronics Ltd., Shahibabad (i) Supply , Inspection - RITES						
	NS41	20.00	Set	106200.00	2124000.00	AT Par	2124000.00

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

41	Description:- Single Section Digital axle Counter Phase Reversal type as per RDSO Specification No. RDSO/SPN/177/2012 (Version -3) and latest if any. Each Set consists of following:- a) High frequency TX Coil and RX Coil with Cables (Each Set consists of CLAMP type TX Coil 2 Nos., RX Coil 2 Nos. along with 10 mtrs.Cable) = 2 Sets. One Set will be subtted with SSDAC during installation and one Set will be kept as Spare with the Consignee. b) Track Side Digital Axle Counter unit 2 Nos. c) VR Box 2 Nos. Each duly wired with 2 nos. of 24V, 6F/6B, 1000 ohm Q type relays. d) Clamp with deflector plates and hardware etc. 4 nos. e) Reset Box 2 nos. f) All other Equipment/Subsystem/literature as available in Standard Set as per RDSO Specification.(ii) Mushroom/Location Box suitable for housing Track side equipment = 2 nos Make: CEL of M/s Central Electronics Ltd., Shahibabad (i) Supply , Inspection - RITES (ii) Execution						
42	NS42	4.00	Numbers	1127.00	4508.00	AT Par	4508.00
42	Description:- Casting, concreting and curing of foundation (1:3:6)and erection of SLB/BSLB/SB/WB/Stop board as per DRG. NO S&T/ C /34 (NKG) all materials required for the work including cement, rail post etc. To besupplied by thecontractor. Thisincludes supply ofSLB/BSLB/SB/WB/Stop board as perRDSO DRG NO.SA-2375 (ADV.) (WITH LATESTAMDT.) forSLB/BSLB and asper RDSO DRGNO. 7235/ B (WITH LATESTAMDT.) forSB/WB/ StopBoard. Supply "For Calling-OnSignal LP's to Stophere" should bewritten on thisstop board withretro-reflecting.Inspection:Consignee						
43	NS43	4.00	Numbers	4823.00	19292.00	AT Par	19292.00
43	Description:- Casting,concreting andcuring offoundation (1:3:6)and erection ofSLB/BSLB/SB/WB/Stop board as perDRG. NO S&T/ C /34 NKG) allmaterials required for the workincluding cement,rail post etc. To besupplied by thecontractor. Thisincludes supply ofSLB/BSLB/SB/WB/Stop board as perRDSO DRG NO.SA-2375 (ADV.) (WITH LATESTAMDT.) forSLB/BSLB and asper RDSO DRGNO. 7235/ B (WITH LATESTAMDT.) forSB/WB/ StopBoard. Execution "For Calling-OnSignal LP's to Stophere" should bewritten on thisstop board withretro-reflecting.						
44	NS44	6.00	Numbers	1301018.0 0	7806108.00	AT Par	7806108.00
44	Description:- Microprocessor based Solid StateBlock Proving by Axle Counter(Digital) (SSBPAC(D)) complete forSingle line operation as per RDSOSpec. No. RDSO/SPN/175/2005 Ver.1or latest including Station Master'sBlock Panel, Wired Relay Racks withRelays, necessary Lightening & SurgeProtection Devices for Power Lines24V DC & Data Lines and BlockTelephone as perRDSO/SPN/191/2005 or latest (PerUnit = Set Per Block Section						
45	NS45	12.00	Pair	116951.00	1403412.00	AT Par	1403412.00
45	Description:- Automatic Media Changeover Card for SSBPAC(D) which includes One Voice Modem Circuit, for working on redundant channels for data transmission on OFC/Quad. Necessary Lightening & Surge protection devices for data lines need to be provided						
46	NS46	12.00	Pair	230060.00	2760720.00	AT Par	2760720.00
46	Description:- Industrial Grade E1 Modem with 8Nos. E&M VF channels suitable for connecting UFSBI/SSBPAC(D) block along with UP & DN Line HASSDAC. Compatible with 48V DC power supply						
47	NS47	6.00	Numbers	60008.00	360048.00	AT Par	360048.00
47	Description:- "Installation and commissioning of SSBPAC(D) complete including Station Master's Block panel and Automatic Media Changeover Card for Double line/Single line operation as per RDSO Spec. No. RDSO/SPN/175/2005 Ver.1or latest. (All misc items required for commissioning shall be supplied by contractor) (Per Unit = Set for Block Section) "						
50	NS50	7.00	Numbers	738738.00	5171166.00	AT Par	5171166.00
50	Description:- "Installation, wiring, testing, commissioning and earthing of DG Set. DG Set to be mounted on anti vibrating pad. All necessary materials including power cable of suitable capacity (ISI Makred) from DG Set to change Over switch as required for the work is to be supplied by the contractor. Seperate provision for Auto Mains Failure (AMF) Panel is to be made and installed to interface with Power Panel/Main Power Supply or as per site engineer. NOTE: All materials including Power Cable of sufficient capacity from DG Set to Change Over Switch is to be supplied by the contractor. Wiring to be made in such a way that DG Set can be made start and Stop from SM's operating room. This includes supply of Signle Phase 230 Volt silent Diesel generator Set, 10 KVA, , complete with AMF Panel, Fuel tank, Battery with loads and CPCB compliant, sound proof acoustic enclosurre and other accessories . DG Set to be accompanied with (i) Allen Keys (ii) Spanner(Taparia set) suitable for DG Set. (iii) Hammer-1NO(5lbs). DG Set should be of Kirloskar make of similar. Inspection : Consignee. Note: (i0 DG Set should conform to CPCB & ARAI regulations and as per Annexure- W. (ii) Manufacturing date of DG Set should be within 1 year at the time of supply to railway store.(ii)Supply. Inspection: RITES" Supply						
	NS51	7.00	Numbers	27622.00	193354.00	AT Par	193354.00

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

51	Description:- "Installation, wiring, testing, commissioning and earthing of DG Set. DG Set to be mounted on anti vibrating pad. All necessary materials including power cable of suitable capacity (ISI Makred) from DG Set to change Over switch as required for the work is to be supplied by the contractor. Seperate provision for Auto Mains Failure (AMF) Panel is to be made and installed to interface with Power Panel/Main Power Supply or as per site engineer. NOTE: All materials including Power Cable of sufficient capacity from DG Set to Change Over Switch is to be supplied by the contractor. Wiring to be made in such a way that DG Set can be made start and Stop from SM's operating room. This includes supply of Signle Phase 230 Volt silent Diesel generator Set, 10 KVA, , complete with AMF Panel, Fuel tank, Battery with loads and CPCB compliant, sound proof accoustic enclosurre and other accessories . DG Set to be accompanied with (i) Allen Keys (ii) Spanner(Taparia set) suitable for DG Set. (iii) Hammer-1NO(5lbs). DG Set should be of Kirloskar make of similar. Inspection : Consignee. Note: (i) DG Set should conform to CPCB & ARAI regulations and as per Annexure- W. (ii) Manufacturing date of DG Set should be within 1 year at the time of supply to railway store.(ii)Supply. Inspection: RITES" Execution							
52	NS52	6.00	Numbers	300184.00	1801104.00	AT Par	1801104.00	
	Description:- Supply and installation of Modular Power Supply Arrangement for VDU (42 inch to85 inch) and industrial PC (Embedded PC)with input and output redundancy arrangement and Hot pluggable modules. Consisting of Annexure Available under EIAAnnexure in Special Conditions ofcontracts of tender documents.Inspection: RITES 4.3.3 Details ofModular Power Supply Arrangement(Asper item 33 of Schedule B)- 1.Input O-Ring Diode Module with Potential freecontact(110V DC) Sources from IPS andsingle 110VDC Sources from IPS andsingle 110 VDC bus. 2.IsolatedInverters(Master/Slave)-2 NosInput:110VDC, Output:120VAC / 220VAC / 500 VA3.Isolated DC-DC Converters-2 Nos.Input 110 V DC, Output-24 VDC/10 A4.3U SS Rack with Back Panel MotherBoard/Front Panel Power Connectorsinverter Auto Changeover switch and allrequired over switch and all requiredprotection circuits as per RDSOSpecifications.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 03-Group-B2 Non-SOR Items Category 2							134183154.00	Above/ Below/P ar
01	NS2001	120.00	Kilometre	312243.00	37469160.00	AT Par	37469160.00	
	Description:- Supply of Underground Railway Jelly Filled Quad Cable for signalling and telecom installation of size 6 Quad x 0.9 mm copper conductor dia as per specification no. IRS-TC 30/2005 (Version-1) with Ammendment No. 5 (Warranty Period : Upto 30 months from the date of supply), Inspection - RDSO							
02	NS2002	290.00	Kilometre	236551.00	68599790.00	AT Par	68599790.00	
	Description:- PVC INSULATED, ARMoured, UNSCREENED, UNDERGROUND RAILWAY SIGNALLING CABLE [COPPER CONDUCTOR] OF SIZE 12 CORE X 1.5 SQ.MM AS PER RDSO SPECIFICATION NO. IRS:S-63/2014 [REV.4.0] (Warranty Period : Upto 30 months from the date of supply. Inspection - RDSO							
03	NS2003	25.00	Kilometre	252520.00	6313000.00	AT Par	6313000.00	
	Description:- UNDERGROUND, ARMoured, UNSCREENED, RAILWAY POWER CABLE (STRANDED 7 X 1.40 MM) WITH HIGH CONDUCTIVITY CIRCULAR COPPER CONDUCTOR OF SIZE: 2 CORE X 10 SQ. MM AS PER SPECIFICATION NO. IRS:S 63/2014 & IS 1554 PART-1 REV.4.0 Inspection - RDSO .							
04	NS2004	6.00	Kilometre	152534.00	915204.00	AT Par	915204.00	
	Description:- UNDERGROUND,ARMoured,UNSCREENED RAILWAY SIGNALLING CABLE(HEAVY DUTY) WITH HIGH CONDUCTIVITY COPPER CONDUCTOR OF SIZE: 6 CORE X 1.5 SQ MM AS PER SPECIFICATION NO.IRS: S- 63/2014(Rev.4.0) WITH LATEST AMENDMENT IF ANY UP TO THE DATE OF OPENING OF TENDER.Inspection - RDSO							
05	NS2005	300.00	Kilometre	69620.00	20886000.00	AT Par	20886000.00	
	Description:- "48 Fiber Armoured OFC cable confirming to RDSO Specification No. RDSO/SPN/TC/110/2020 Revision-0 or latest if any up to the date of tender opening (Warranty Period : Upto 30 months from the date of delivery.) Inspection - RDSO "							

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Important : All documents uploaded and remarks / confirmation entered by the bidders against any eligibility condition shall be opened as part of technical bid only

Special Financial Criteria

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or V 'whichever is less, where V= Advertised value of the tender in crores of Rupees N=Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet. It will follow as per item 10.2 or 17.15.2 of GCC'2022 with Advance Correction Slip with Letter No.:2022/CEI/CT/GCC- 2022/Policy New Delhi, dated: 14.07.2022	No	No	Allowed (Mandatory)
2	Bid Capacity as per as per Para 10.3 & 17.15.3 and Annexure VI of GCC'2022 with up to date amendments.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07(seven) years, ending last day of month previous to the one in which tender is invited: Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or One similar work each costing not less than the amount equal to 50% of advertised value of the tender. It will follow as per item 10.1 of GCC'2022 with Advance Correction Slip with Letter No.:2022/CEI/CT/GCC-2022/Policy New Delhi, Dated:14.07.2022	No	No	Allowed (Mandatory)
2	The Similar Nature of Work required as qualifying criteria in this case of tender is: "Electronic Interlocking Work {Indoor or (Indoor+ Outdoor)} And /Or Panel Interlocking Work {Indoor or (Indoor +Outdoor)} And /Or Route Relay Interlocking Work {Indoor or (Indoor + Outdoor)}".	No	No	Allowed (Mandatory)

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)
----	---

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Important : All documents uploaded and remarks / confirmation entered by the bidders against any compliance condition shall be opened as part of technical bid only.

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Power of Attorney on Notarized Stamp Paper.	No	No	Allowed (Mandatory)
2	NEFT Details as Per Annexure-T as per tender document	No	No	Allowed (Mandatory)
3	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	All documents in support of fulfilment of eligibility criteria with respect to completion of Similar nature of work for Technical Eligibility Criteria and Total contract value for Financial Eligibility Criteria should be furnished along with the tender and should be submitted online at the time of tender bidding. Tenders not accompanied by documentary evidence in support of eligibility criteria will be summarily rejected. No post tender communication ,in any form will be made or entertained, after opening of tenders, in this regard. Railways may however call for the originals of the credentials or verification or any clarifications/confirmations on the contents of the documents submitted	No	No	Not Allowed
2	Tenderers shall note that the submission of other supporting SCANNED documents namely-Constitution of firm/JV firm, Work in hand, Arbitration/Court cases, Tools - Plants, Technical Personnel /Man Power and Association of Railway Officers, at the time of on line bidding of tender, is important and they shall ensure the same. However Railway may seek clarifications/details/documents in this regard.	No	No	Not Allowed
3	ALL THE OFFERERS ARE BEING REQUESTED TOPLEASE CONTACT WITHDDY.CSTE/CON/EASTERNRAILWAY OF THAT DIVISIONWELL IN ADVANCE FOR ANY QUARIES RELATEDWITH THIS TENDER IF REQUIRED	No	No	Not Allowed

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

4	The related Clauses mentioned in the Tender document will be as per the IRGCC issued on 2022 with up to date modifications Following items are to be read along with schedule for interpretation of item-(I) ALL SMITHY /MASSNASYMATERIALS INCLUDING CEMENT , BOLT, BARS,ANGLES ETC. ARE REQUIRED FOR EXECUTIONS SHALL BE SUPPLIED BY THE CONTRACTOR. (ii) ALL SUPPLY MATERIALS FOR WHICH INSPECTING AUTHORITY HAS NOT BEEN INDICATED IN THE TENDER SCHEDULE BUT WILL BE USED FOR INSTALLATION IS REQUIRED TO BE INSPECTED BY THE RAILWAY AUTHORISED REPRESENTATIVE OF DY CSTE/CONHWH//E.RLY. BEFORE THEY ARE EITHER PROCESSED FOR MANUFACTURE AS PER SCHEDULE OR USED DIRECTLY. (iii) THE MATERIAL TO BE SUPPLIED BY THE CONTRACTOR AT SSE/IG/CON/BANDEL'S/STORE AT BANDEL AND SHOULD BE TRANSPORTED AT SITE FREE OF COST. (iv) THE MATERIAL SUPPLIED BY THE RAILWAY FROM SSE/SIGNAL/CON BANDEL'S STORE AT BANDEL AND TO BE TRANSPORTED BY THE CONTRACTOR AT SITE FREE OF COST. (v) VARNISH WHEREVER REQUIRED FOR CARPENTRY WORKS AS PER REQUIREMENT OF RAILWAY SHALL BE SUPPLIED BY THE CONTRACTOR. (vi) EACH MATERIALS SUPPLIED BY THE CONTRACTOR SHOULD BEAR THE CONTRACT NO. EMBOSSED/PAINTED/WRITTEN BY PERMANENT INK ON THESE. CONTRACTOR SHOULD MAKE NECESSARY ARRANGEMENT TO COMPLETE. (vii) EVERY FORTNIGHT CONTRACTOR SHOULD SENT THE PROGRESS OF WORK TO THE EXECUTIVE AS WELL AS CSTE/CON/ER FOR KEEPING SMOOTH PROGRESS OF WORK. (viii) ALL NUTS AND BOLTS SHOULD BE ADEQUATELY GALVANISED & PERFORMANCE GUARANTEE SHOULD BE GIVEN BY THE CONTRACTOR AGAINST RUSTING. (ix) PAYMENT WILL BE MADE AS PER ACTUAL WORK DONE ON PRORATA BASIS. IF REQUIRED DEPTH/LENGTH/SPACE/QUANTITY (AS APPLICABLE) IS NOT AVAILABLE AT SITE. (x) THE VEHICLE FOR SITE MOVEMENT AND WORK FOR RAILWAY OFFICIAL TO BE ARRANGED BY THE CONTRACTOR. (xi) WHERE EVER SUPPLY IN SCHEDULE IS LESS THAN EXECUTION, MATERIAL WILL BE SUPPLIED BY RAILWAY SUBJECT TO AVAILABILITY IN STORE. (xii) Execution of item will include all accessories to complete the execution.	No	No	Not Allowed
---	--	----	----	-------------

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The Railway reserves the right to verify all statements, information and documents submitted by the bidder in his tender offer, and the bidder shall, when so required by the Railway, make available all such information, evidence and documents as may be necessary for such verification. Any such verification or lack of such verification by the Railway shall not relieve the bidder or its obligations or liabilities hereunder nor will it affect any rights of the Railway thereunder. In case of any wrong information submitted by tenderer, the contracts shall be terminated. Earnest Money Deposit (EMD), Performance Guarantee (PG) and Security Deposit (SD) of Contract forfeited and agency barred as per GCC'2022 with up to date modifications.	No	No	Not Allowed

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Bar chart to comply the work in given time frame must be submitted. (For supply as well as execution both)	No	No	Allowed (Mandatory)
2	Tenderers shall note that the submission of other supporting SCANNED documents namely- Constitution of firm/JV firm, Work in hand, Arbitration/Court cases, Tools- Plants, Technical Personnel /Man Power and Association of Railway Officers, at the time of on line bidding of tender, is important and they shall ensure the same. However Railway may seek clarifications/details/documents in this regard.	No	No	Allowed (Mandatory)

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

3	Scanned copy -in PDF format- of the details regarding association of Railway Officer(s) with the firm, during the last three years - for details please refer Annexure-IA of Tender document. Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer	No	No	Allowed (Mandatory)
4	Scanned copy -in PDF format- of the details of the works awarded to the firm, during the last three years for details please refer Annexure-II of Tender document	No	No	Allowed (Mandatory)
5	Scanned copy -in PDF format- of the details of the Works in progress / in hand during the last 3 years -for details please refer Annexure-III of Tender document	No	No	Allowed (Mandatory)
6	Scanned copy -in PDF format- of the details of the List of the Arbitration -Court cases during the last 3 years -for details please refer Annexure-IV of Tender document	No	No	Allowed (Mandatory)
7	Scanned copy - in PDF format- of the details of Equipment's proposed to be inducted - for details please refer Annexure-V of Tender document	No	No	Allowed (Mandatory)
8	Scanned copy - in PDF format- of the details of technical personals available in hand of the agency ,available on hand for details please refer Annexure-VI of Tender document	No	No	Allowed (Mandatory)
9	Scanned copy - in PDF format- of the details of technical personals available in hand of the agency ,available on hand for details please refer Annexure-VI of Tender document	No	No	Allowed (Mandatory)
10	Scanned copy -in PDF format- of any other letters/documents etc. -If agency intends to submit.	No	No	Allowed (Mandatory)
11	List of Deviation as per Annexure-E of Tender Document.	No	No	Allowed (Mandatory)
12	Complete Postal Address, Mail id and Mobile Number As per Part-A Details of The tenderer of Tender Document. All communication of Railway Will be done on these address/Mail id and Mobile Number	No	No	Allowed (Mandatory)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions	No	No	Not Allowed
2	I/ We have visited the works site and I / We am / are aware of the site conditions	No	No	Not Allowed
3	I have quoted rates considering all payment terms, special condition of contracts, taxes and other incidental charges etc	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	IRGCC2022.pdf	IRGCC 2022
2	ACS-1.pdf	ACS1 PDF
3	ACS-2.pdf	ACS2 PDF
4	ACS-3.pdf	ACS 3
5	ACS-4_-10merged_compressed.pdf	ACS 4 to 10
6	ACS-4_-10merged_compressed_1.pdf	ACS 4 to 10
7	Drillmachine.pdf	drill machine
8	Dualdetectionworks3.pdf	Dual detection letter
9	JPOonCablecutLatest.pdf	JPO on cable cut
10	microtunneling110-Jan-202416-38-50.pdf	Micro tunneling Guideline

**ER-CAO-C-HQ-S AND T/EASTERN RLY
TENDER DOCUMENT**

Tender No: SANDT-CON-16-HWH-2026

Closing Date/Time: 26/02/2026 11:00

11	MonitoringofDualBPAC-MSDAC.pdf	Monitoring Dual MSDAC
12	TechnicalCircular111.pdf	Tech Cir 111
13	QualityChecklist30-09-2024Signed.pdf	Quality Check list
14	RevisionofTypicaldiagramEarthElectrode1.pdf	Typical Diagram of earth electrode
15	ClassArateanddesign.pdf	Claas A Lighting drawing
16	yardplanRampurhat-Dumkadoubling2.pdf	Conceptual Plan
17	25WVHFtechnicaladvisory.pdf	VHF Circular
18	TechnicalCircular124AModifiedregardingPolicyoflayingofOFCcablesforSTworks.pdf	Tech Circular 124A
19	RDSOSpecBatteryChargerChange.pdf	Spec Battery Charger
20	DrawingsDetailsofIPSforCentralEndGoomtyABS-IB-LC.pdf	Drawing details of IPS
21	RPH-DMKATenderDocumentF.pdf	Tender Document

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: ADITYA AMBAR
Designation : Dy.CSTE/CON/HWH