

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

Dy.CSTE/CON/Nagpur/SECR acting for and on behalf of The President of India invites E-Tenders against Tender No **765-ST-Con-NGP-G-BPQ** Closing Date/Time 18/06/2026 12:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	S&T cable clearance/utility shifting work in connection with doubling work (Phase-I) for Gondia(G)-Chandafort(CAF) section facilitating engineering earth work, S&T works for ROB/RUB for LC Gate GCF 60 S&T works for alteration in existing EI of CAF for connectivity with Babupeth Station, and provision of miscellaneous items/features like latest Earthing and Bonding System, Fire Alarm System etc. for Wadsa-Gadhchiroli Section of Nagpur Division of S.E.C. Railway.		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Two Packet System
Tender Closing Date Time	18/06/2026 12:00	Date Time Of Uploading Tender	27/05/2026 19:58
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	119861931.30	Tendering Section	TENDER
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	2397200.00	Validity of Offer (Days)	90
Tender Doc. Cost (Rs.)	0.00	Period of Completion	24 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	04/06/2026		
Are JV allowed to bid	Yes	Number of JV Member Allowed	2
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-Execution of Out Door Signalling work							25563578.00	Above/ Below/P ar
1	A	10.00	Kilometre	92115.00	921150.00	AT Par	921150.00	
	Description:- Excavation of trench and clearing of roots of trees, bushes, ballast and reconditioning etc., including bailing out water and disposal of extra soil. All soils including soft rocky area. Depth 1.2 Mtr. & width 0.3 Mtr.							
2	A	15.00	Kilometre	76590.00	1148850.00	AT Par	1148850.00	
	Description:- Excavation of trench and clearing of roots of trees, bushes, ballast and reconditioning etc., including bailing out water and disposal of extra soil. All soils including soft rocky area. Depth 1.0 Mtr. & width 0.3 Mtr.							
3	A	1000.00	Metre	115.00	115000.00	AT Par	115000.00	
	Description:- Excavation of trench and clearing of roots of trees, bushes, ballast and reconditioning etc., including bailing out water and disposal of extra soil. Hard rocky area including concreting. Chase cutting and smoothening of inside surface of sizes 0.08 m deep and 0.17 m width at platform and cemented floor area.							
4	A	150.00	Numbers	582.00	87300.00	AT Par	87300.00	
	Description:- Excavation of trench and clearing of roots of trees, bushes, ballast and reconditioning etc., including bailing out water and disposal of extra soil. Hard rocky area including concreting. Cutting the masonry wall to the depth of 0.25m to 0.75m at the entry of room placing of flexible HDPE pipe or G.I.Pipe (including supply) of suitable size as per drawing No. RE/S&T/ALD/SK/161/81.							
5	A	500.00	Metre	1080.00	540000.00	AT Par	540000.00	

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

6	Description:- Excavation of trench and clearing of roots of trees, bushes, ballast and reconditioning etc., including bailing out water and disposal of extra soil. Track crossing, Road Crossing by pushing method (HDD method) at culverts/ track / pucca road crossing at a depth not less than 1 meter with reference to bottom of rail/road surface including supply of HDPE pipe. HDPE pipe/DWC pipe (4 inch dia).						
	A	5000.00	Metre	2246.00	11230000.00	AT Par	11230000.00
7	Description:- Excavation of trench and clearing of roots of trees, bushes, ballast and reconditioning etc., including bailing out water and disposal of extra soil. Track crossing, Road Crossing by pushing method (HDD method) at culverts/ track / pucca road crossing at a depth not less than 1 meter with reference to bottom of rail/road surface including supply of GI pipe. GI pipe with 76 mm dia, Spec. No. -1239 medium grade (for the length of pushing more than 05 meters).						
	A	150.00	Kilometre	16740.00	2511000.00	AT Par	2511000.00
8	Description:- Laying of Signalling Cable/Power/Quad cable / PIJF cable in the excavated trench to Drg.No:CON/SK/T/5.Transportation, supply of 'U' clamps and anchoring of cable at every 10 Mtrs with 'U' clamp to Drg.No:CSTE/C/Cable/81 including back filling with excavated earth and ramming of trenches after cable laying.						
	A	5.00	Kilometre	25526.00	127630.00	AT Par	127630.00
9	Description:- Laying of Power cable in the same excavated trench to Drg.No:CON/SK/T/5.Transportation, supply of 'U' clamps and anchoring of cable at every 10 Mtrs with 'U' clamp to Drg.No:CSTE/C/Cable/81. Transportation, supply and placement of 2nd class bricks in the trench length wise between power cable & other signalling/quad cable in the same trench all along the trench (4.5 bricks approx per Mtr.) including back filling with excavated earth and ramming of trenches after cable laying.						
	A	1300.00	Metre	761.00	989300.00	AT Par	989300.00
10	Description:- Laying and Fixing of galvanised iron pipe (GI Pipe) with threaded collars (for jointing pipe) of 80 mm nominal dia Spec.No.IS-1239 medium grade, on bridges, culverts, drains including supply and transportation of GI pipes and all other materials required for fixing the pipe to Drg.No.Con/SK/T/2 and drawing of Signal/Power/Quad cables inside the pipe with masonry works over the entire length of the bridge and at entry and exit of the culvert and curing for 72 hrs, drilling of holes on the pipe at 10 cm apart to be clamped 2 Mtrs apart on culvert, for the Signalling, quad, power cable.						
	A	700.00	Metre	775.00	542500.00	AT Par	542500.00
11	Description:- Laying of RCC pipe including supply of required quantity at site with collars (for jointing pipe) 150 mm nominal dia to Spec.No:IS-458 in excavated trench and laying of Signalling/Power cable/PIJF cable/ Quad cables/HDPE pipe through RCC pipe. Power cable shall be laid in the same trench alongwith signalling/Quad cables but in a separate pipe RCC pipe at track/pucca road/ Platform crossing/ level crossing gate etc.						
	A	3000.00	Metre	254.00	762000.00	AT Par	762000.00
12	Description:- Laying of half round RCC hume pipe with 150 mm dia & 1 mtr long including supply at site on single/multiple cable laid in the trench.						
	A	23.00	Kilometre	32603.00	749869.00	AT Par	749869.00
13	Description:- Laying of second class bricks including supply of required quantity at site on single/multiple cable laid in the trench (Approx 9 bricks per mtr). NOTE : (1) This includes guarding of cables, relaying of cables and redoing of cable jointing in case of the thefts or otherwise at contractor's own cost for item no. 1 to 11 as mentioned above till commissioned.						
	A	200.00	Drum-Km	1282.00	256400.00	AT Par	256400.00
14	Description:- Shifting of cables in roll with or without wooden drums from other than nominated consignee depot and meggering before loading and after laying, and recording the values in cable insulation register along with representative of Railways. Here unit Drum/Km stands for Drum/Roll.						
	A	60.00	Numbers	17067.00	1024020.00	AT Par	1024020.00
	Description:- The excavation of pit, casting of concrete foundation including surrounding earthwork along the foundation, erection, installation and wiring of steel apparatus case, fixing of terminals, fuse, locks, signal transformer, current transformer, filament switching unit, track battery chargers, adjustable/fixed resistances, choke coils, Fuses, Relays, E type locks, termination of cables, cable insertion, wiring to draw 110V AC therefore in the new apparatus case as required, testing, commissioning including subsequent alterations (if required), bunching of cables, earthing of cable, armours etc. Painting of the apparatus case inside and outside after clearing the surface thoroughly and first coating of anti -corrosive paint and subsequent two coatings of Alluminium paint outside and Red Oxide inside and lettering. 18mm Hylum sheet for location box shelf and 12 mm for cable termination in location box. Steel appartus case (Large) to Drg.No. CON/SK/T/8 with 4 Nos. of foundation bolts 20mm x460mm to Drg.No. SA-112 A/M or latest. NOTE : for item Payment can be released in a part for the above said works after completion of (i) Foundation- 30%,(ii) Erection - 15% ,(iii)Wiring, testing, painting, sand filling, plastering, earthing & writings etc - 45% ,(iv)Commissioning - 10% of the rate.						
	A	10.00	Numbers	8534.00	85340.00	AT Par	85340.00

**DYCS-TE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

15	Description:- The excavation of pit, casting of concrete foundation including surrounding earthwork along the foundation, erection, installation and wiring of steel apparatus case, fixing of terminals, fuse blocks, signal transformer, current transformer, filament switching unit, track battery chargers, adjustable/fixed resistances, choke coils, Fuses, Relays, E type locks , termination of cables, cable insertion, wiring to draw 110V AC therefore in the new apparatus case as required, testing, commissioning including subsequent alterations (if required), bunching of cables, earthing of cable, armours etc. Painting of the apparatus case inside and outside after clearing the surface thoroughly and first coating of anti -corrosive paint and subsequent two coatings of Alluminium paint outside and Red Oxide inside and lettering. 18 mm Hylum sheet for location box shelf and 12 mm for cable termination in location box. Steel appartus case (half) with 4 Nos. of SS foundation bolts 20mm x 460mm to Drg.No. SA-112 A/M or latest. NOTE : for item Payment can be released in a part for the above said works after completion of (i) Foundation- 30%,(ii) Erection - 15% ,(iii)Wiring, testing, painting, sand filling, plastering, earthing & writings etc - 45% , (iv)Commissioning - 10% of the rate.						
16	A	10.00	Numbers	4266.00	42660.00	AT Par	42660.00
16	Description:- The excavation of pit, casting of concrete foundation including surrounding earthwork along the foundation, erection, installation and wiring of steel apparatus case, fixing of terminals, fuse blocks, signal transformer, current transformer, filament switching unit, track battery chargers, adjustable/fixed resistances, choke coils, Fuses, Relays, E type locks , termination of cables, cable insertion, wiring to draw 110V AC therefore in the new apparatus case as required, testing, commissioning including subsequent alterations (if required), bunching of cables, earthing of cable, armours etc. Painting of the apparatus case inside and outside after clearing the surface thoroughly and first coating of anti -corrosive paint and subsequent two coatings of Aluminums paint outside and Red Oxide inside and lettering. 18 mm Hylum sheet for location box shelf and 12 mm for cable termination in location box. eel appartus case (Quarter) to Drg.No. RE/S&T/Sig./Tender/SK/5A/91 with 4 Nos. of SS foundation bolts of size 20mm x 300mm or latest. NOTE : for item Payment can be released in a part for the above said works after completion of (i) Foundation- 30%,(ii) Erection - 15% ,(iii)Wiring, testing, painting, sand filling, plastering, earthing & writings etc - 45% , (iv)Commissioning - 10% of the rate.						
17	A	20.00	cum	2943.00	58860.00	AT Par	58860.00
17	Description:- Cement Concrete of proportion 1:3:6 with graded aggregate of size 25mm. and below.						
18	A	190.00	Each	1941.00	368790.00	AT Par	368790.00
18	Description:- Excavation of earth pit, transportation, placing and fixing of earth electrode with construction of cement encloser to Drg.No.CON/SK/T/9 and CON/SK/T/9A and drawal of GI wire wrapped on MS strip (35 x 6 mm) from earth electrode to all signalling equipments, including fixing and soldering of lugs at both end of the wire.						
19	A	30.00	Numbers	19551.00	586530.00	AT Par	586530.00
19	Description:- Installation of signal posts for Multiple Aspect Colour Light Signals complete with signal units, bases, LED unit, fixing and wiring of current transformers of LED units, ladders & other fittings, excavation of pit, casting of cement concrete foundations with necessary water outlets, erection and fixing of complete fittings of the signal/signal post with necessary earthed screen protection arrangement, including drawing of cable through signal posts, termination of cables, wiring, testing and commissioning, two coat painting and lettering, supply and fixing of speed boards if required for the following:- NOTE:- The foundation for Multiple Aspect Colour Light Signal Post drg. No. Con/SK/T/12 and the foundation bolts shall be of sizes 24 mm x 915 mm to Drg. No. SA- 116A/M and bolts for each foundation for above shall be of size 20 mm x 305 mm to Drg. No. SA- 110A/M (4 nos. for each) with two nuts and two washers each per bolt. 3 ASPECT/4 ASPECT NOTE : for item Payment can be released in a part for the above said works after completion of-(i) Foundation- 30%,(ii) Erection - 15% ,(iii)Wiring, testing, painting, sand filling, plastering, earthing & writings etc - 45% ,(iv) Commissioning - 10% of the rate.						
20	A	10.00	Numbers	4629.00	46290.00	AT Par	46290.00
20	Description:- Fixing of calling-on signals/dependent shunt signals with enameled markers including drawing of cable through the signal post, termination of cables, wiring, fixing of calling-on/dependent shunt signal legend board, LED, two coat painting and lettering, testing and commissioning as required.NOTE : for item Payment can be released in a part for the above said works after completion of-(i) Foundation- 30%,(ii) Erection - 15% ,(iii)Wiring, testing, painting, sand filling, plastering, earthing & writings etc - 45% ,(iv) Commissioning - 10% of the rate.						
21	A	15.00	Numbers	3856.00	57840.00	AT Par	57840.00
21	Description:- Installation, testing and commissioning of Position Light shunt signal (Independent), posts complete with lamps/LED lamps, LED units, Bases and other fittings, excavation of pit, casting of cement concrete foundation, fixing of complete fittings of signal, LED lamps, current regulator including foundation bolts, washers, nuts, termination of cables, wiring, painting and lettering as required. NOTE:- The foundation for position light shunt signal Drg. No. Con/SK/T/13 and bolts for each foundation for above shall be of size 20 mm x 305mm to Drg. No. SA-110A/M (4 nos. for each) with two nuts and two washers each per bolt. NOTE : for item Payment can be released in a part for the above said works after completion of-(i) Foundation- 30%,(ii) Erection - 15% ,(iii) Wiring, testing, painting, sand filling, plastering, earthing & writings etc - 45% ,(iv) Commissioning - 10% of the rate.						
	A	10.00	Numbers	2110.00	21100.00	AT Par	21100.00

**DYCS-TE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

22	Description:- Fixing, cable drawing and termination, wiring, painting, lettering, testing and commissioning of Junction type Route indicator complete along with lamp/LED unit : 1/2 Way.						
	A	5.00	Numbers	3086.00	15430.00	AT Par	15430.00
23	Description:- Fixing, cable drawing and termination, wiring, painting, lettering, testing and commissioning of Junction type Route indicator complete along with lamp/LED unit : 3/4 Way.						
	A	8.00	Numbers	1274.00	10192.00	AT Par	10192.00
24	Description:- Alteration/modification, testing, commissioning, two coat painting, lettering o f the existing 2 Aspect/3 Aspect/4 aspect signals/shunt signals/calling on signal/ LC gate to suit the circuit per approved wiring diagram including fixing of LED/Singal lamps and their wiring.						
25	A	2.00	Numbers	1064.00	2128.00	AT Par	2128.00
	Description:- Installation, testing and commissioning of route indicator LED type.						
26	A	50.00	Each	308.00	15400.00	AT Par	15400.00
	Description:- Supply of retro reflective signal/shunt signal enameled number legend board of size-300mm X 200mm X 3mm (minimum) made up of alluminium composite - 4 panel (ACP) with white back ground and alphabets/numbers in black along with fixing clamps.						
27	A	50.00	Each	77.00	3850.00	AT Par	3850.00
	Description:- Installation of retro reflective signal/shunt signal enameled number legend board.						
28	A	10.00	Each	9427.00	94270.00	AT Par	94270.00
	Description:- Excavation & casting of pedestal foundation for left/right hand boom of lifting barriers.						
29	A	10.00	Each	1453.00	14530.00	AT Par	14530.00
	Description:- Excavation & casting of foundation for stop post.						
30	A	5.00	Set	17912.00	89560.00	AT Par	89560.00
	Description:- Erection and commissioning o f Lifting Barrier assembly complete including boom support, positive boom locking device, Emergency crank handle attechment, Timer unit to adjust the time for operating the barrier, Fixing of Hooters/Flashers on either side of gate barriers, 1 (one) control panel, weather proof painting, lettering, Neccessary MS weight for balancing the booms, etc.						
31	A	25.00	Numbers	232.00	5800.00	AT Par	5800.00
	Description:- Dismantling of the Signal posts/BSLB/SLB/Stop Board.						
32	A	150.00	Numbers	232.00	34800.00	AT Par	34800.00
	Description:- Dismantling of the Steel apparatus case with fittings.						
33	A	50.00	Numbers	360.00	18000.00	AT Par	18000.00
	Description:- Dismantling of the Relay racks with all fittings, battery racks complete, Equipment rack complete, SM's slide.						
34	A	80.00	Numbers	60.00	4800.00	AT Par	4800.00
	Description:- Dismantling of the TLJB/Point JB.						
35	A	25.00	Numbers	1087.00	27175.00	AT Par	27175.00
	Description:- Dismantling of the Location Foundation (By hydraulic breaker).						
36	A	10.00	Numbers	2174.00	21740.00	AT Par	21740.00
	Description:- Dismantling of the Signal Foundation(upto ground level by hydraulic breaker).						
37	A	15000.00	Job	38.00	570000.00	AT Par	570000.00
	Description:- Collecting, stacking with deployment of Man power, Hydra etc for Loading/ Unloading and Transportation of Materials (Fresh/Released/ Unused) from (i) work site to GSD/Raipur, (ii) work site to the store of SSE(SIG)/CON,(iii) any store depot to any other store depot over Indian railways as decided by Railway Administration by suitable Trucks and stacking properly. Here JOB unit stand for TON-KM.						
38	A	5.00	Set	37853.00	189265.00	AT Par	189265.00
	Description:- Installation, testing and commissioning of sliding boom LC gates complete which includes casting of concrete foundation including surrounding earthwork along the foundation (Dia-30 cm & depth-100 cm total ten numbers per gate), fixing and welding of channel, fixing of clamps, cutting of rail post, fixing of lock post with two numbers excavation of Pit casting of concrete foundation for "B" type foundation per gate, laying of cable for road crossing and fixing of MS plate/channel also as requirement of the site condition.						
39	A	100.00	Man-Days	266.00	26600.00	AT Par	26600.00
	Description:- Supply of Unskilled labour for immediate restoration of normal traffic by jointing Signalling/Telecom/Power cables of damaged during excavation of earth work of engineering department or for shifting, stacking of stores materials. Unskilled staff will remain available in working hours.						
40	A	1250.00	Numbers	415.00	518750.00	AT Par	518750.00

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

	Description:- Fixing of concrete cable route marker at 30-40 meter and at diversion point including supply & transportation of cable route marker at site. Detail size & fixing of cable route marker should be followed as per drawing no. SDO/Cable laying/020.							
41	A	1500.00	Per Conductor	24.00	36000.00	AT Par	36000.00	
	Description:- Switching/shifting of working cables conductors from the existing CTR/CRR/Location box to the new CTR/CRR/Location box with parallel patching without interfering the working signalling circuits in presence of Railway engineer at site.							
42	A	10.00	Numbers	3623.00	36230.00	AT Par	36230.00	
	Description:- Dismantling of the LC gate /Lifting barrier complete.							
43	A	5.00	Per Unit	30189.00	150945.00	AT Par	150945.00	
	Description:- Shifting of existing cables by providing location boxes and pieces of signalling cables as required in the yard to facilitate the engineering department for earth work for laying new lines. (work will be executed in presence of Railway representative). The cost towards new location foundation shall be given vide item No.14/15/16) when the length of trench is less than 150 meters. Note: Unit Per unit read as Per site.							
44	A	500.00	Metre	241.00	120500.00	AT Par	120500.00	
	Description:- Physical tracing and opening/locating of existing working cables by precession digging for diversion of cables in connection with cable clearance for engineering earth work without interfering the circuits as per the advice of Railway site engineer							
45	A	20.00	Numbers	17378.00	347560.00	AT Par	347560.00	
	Description:- Installation of signal posts for Multiple Aspect Colour Light Signals complete with signal units, bases, LED unit, fixing and wiring of current transformers of LED units, ladders & other fittings, excavation of pit, casting of cement concrete foundations with necessary water outlets, erection and fixing of complete fittings of the signal/signal post with necessary earthed screen protection arrangement, including drawing of cable through signal posts, termination of cables, wiring, testing and commissioning, two coat painting and lettering, supply and fixing of speed boards if required for the following:- NOTE:- The foundation for Multiple Aspect Colour Light Signal Post drg. No. Con/SK/T/12 and the foundation bolts shall be of sizes 24 mm x 915 mm to Drg. No. SA- 116A/M and bolts for each foundation for above shall be of size 20 mm x 305 mm to Drg. No. SA- 110A/M (4 nos. for each) with two nuts and two washers each per bolt.(a) (i) 2 ASPECT NOTE : for item Payment can be released in a part for the above said works after completion of-(i) Foundation- 30%,(ii) Erection - 15% ,(iii)Wiring, testing, painting, sand filling, plastering, earthing & writings etc - 45% ,(iv) Commissioning - 10% of the rate.							
46	A	100.00	Numbers	2548.00	254800.00	AT Par	254800.00	
	Description:- Alteration/ Modifications in the existing location boxes, fixing of equipments, cable insertion, termination, wiring, testing & commissioning, two coat painting, lettering to suit the circuits as per approved wiring diagrams. This includes filling with sand and plastering the same.							
47	A	150.00	Numbers	3580.00	537000.00	AT Par	537000.00	
	Description:- Shifting of existing location boxes to facilitate earthwork of Engg./Con. This includes filling with sand and plastering inside location boxes.							
48	A	3.00	Set	48608.00	145824.00	AT Par	145824.00	
	Description:- Installation, Testing and Commissioning of Digital Axle Counter and field training (One man day per set) at site and training to the field staff at site for three days.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-SUPPLY OF FERROUS MATERIALS							4230482.00	Above/ Below/Par
1	B	20.00	Numbers	32681.00	653620.00	AT Par	653620.00	
	Description:- Supply of 2 Aspect signal unit in FRP body without Lenses and transformer as per RDSO spec. No. RDSO/SPN/194/2006 . Inspection by RITES.							
2	B	30.00	Numbers	35227.00	1056810.00	AT Par	1056810.00	
	Description:- Supply of 3 Aspect signal unit in FRP body without Lenses and transformer as per RDSO spec. No. RDSO/SPN/194/2006. Inspection by RITES.							
3	B	4.00	Numbers	39820.00	159280.00	AT Par	159280.00	
	Description:- Supply of 4 Aspect signal unit in FRP body without Lenses and transformer as per RDSO spec. No. RDSO/SPN/194/2006. Inspection by Rep. of CSTE/Con/BSP.							
4	B	10.00	Numbers	6078.00	60780.00	AT Par	60780.00	
	Description:- Shunt signal position light type complete with post base Drg No. SA 23840 Adv.Alt.1, S-23203 Adv., with 90 mm dia mounting socket Drg No S-23845 (Adv.). Inspection by Rep. of CSTE/Con/BSP.							
	B	10.00	Numbers	4498.00	44980.00	AT Par	44980.00	

**DYCS-TE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

5	Description:- Shunt signal dependent type Drg.No.SA-23840(Adv) Alt.1 & S-23845 Adv. with off-set bracket to Drg. No. SA23080 Adv. Alt. 1 & specn. No. IRS:S-10/78 to suit 140mm. Outside dia post complete. Inspection by Rep. of CSTE/Con/BSP.								
6	B	10.00	Numbers	2732.00	27320.00	AT Par	27320.00		
	Description:- Calling on signal (CLS Type) Drg.No: SA-24351(Adv.), Spec.No.IRS-S-10/78, IRS :S-26/64. Inspection by Rep. of CSTE/Con/BSP.								
7	B	10.00	Numbers	16567.00	165670.00	AT Par	165670.00		
	Description:- Route Indicator junction direction 5 lamp type with Arms and drum complete but without lens and lamps, 3 way RH/LH. Drg.No.SA23403 (Adv) for 3 way.Spec.No.IRS:S-66/84 with latest amd, IRS:S- 23/88, IRS:S-10/78, IRS:S-26-64. Inspection by Rep. of CSTE/Con/BSP.								
8	B	25.00	Numbers	2857.00	71425.00	AT Par	71425.00		
	Description:- Tubular post for CLS 5.5 Mtr. Spec.IRS.S-6/81. Inspection by Rep. of Railway Engineer.								
9	B	25.00	Numbers	7134.00	178350.00	AT Par	178350.00		
	Description:- Signal base 140mm.dia(type tube) Drg.No.S-2011/M. Inspection by Rep. of Railway Engineer.								
10	B	25.00	Numbers	4082.00	102050.00	AT Par	102050.00		
	Description:- Ladder 5.5 Mtr for CLS Drg.No.SA-23156(Adv)Alt-1.Spec. No. IRS-S-10. Inspection by Rep. of Railway Engineer.								
11	B	10.00	Numbers	974.00	9740.00	AT Par	9740.00		
	Description:- Off set bracket for colour light 140 mm. outside dia post Drg. No. SA-23080(Adv) Alt-1.IRS-S- 10-78. Inspection by Rep. of CSTE/Con/BSP.								
12	B	1.00	Numbers	62959.00	62959.00	AT Par	62959.00		
	Description:- Supply of Multi lamp Route Indicator (LED single digit) from 1 to 9 with white LED (without housing); details- Single digit LED route indicator capable of displaying 1 to 9, visibility of 400m in clear day light, option for white colors chromaticity as per BS-1376 standard, LED's with junction temperature>100 degree C, lamp proving compatible with normal bulb type multi lamp route indicator, retrofits the existing conventional multi lamp type route indicators, input operating voltage 110V AC +-20%, uniform intensity over entire operating range operating temperature -10 degree C to +60 degree C. Inspection by Rep. of CSTE/Con/BSP.								
13	B	60.00	Numbers	15782.00	946920.00	AT Par	946920.00		
	Description:- Steel Apparatus Case(Large) as per Drg.No.Con/SK/1/1/86 , with E type lock on both side having ward No.32. Inspection by RITES.								
14	B	5.00	Numbers	9386.00	46930.00	AT Par	46930.00		
	Description:- Relay Rack for 'Q' Series Relay as per Drg. No: SK/DRG/OL/SER/192 SH 2/2. The relay racks must be powder coated of stone grey colour. Inspection by Rep. of Railway Engineer.								
15	B	20.00	Numbers	226.00	4520.00	AT Par	4520.00		
	Description:- Negative Bus bar16 way 18 ". Inspection by Rep. of Railway Engineer.								
16	B	10.00	Numbers	1213.00	12130.00	AT Par	12130.00		
	Description:- Earth Electrodes to Drg. No: Con/SK/8/3/84. Inspection by Rep. of Railway Engineer.								
17	B	5000.00	Kg	59.00	295000.00	AT Par	295000.00		
	Description:- Supply of Wire IG 8 SWG for Bonding.Inspection by Rep. of Railway Engineer. Note:- This item will be issued to contractor from Railway store only for picking of existing track circuits during Pre-Pre-NI & Pre-NI work.								
18	B	5000.00	Metre	66.00	330000.00	AT Par	330000.00		
	Description:- Supply of PVC insulated GI flexible wire for lead wire of track circuit used in Railway signalling. Dia 6mm (19 Sqmm cross sectional area) Constrction 7x7 core WSC. Lay Right Hand ordinary. Finish Galvanised. Tensile strength 125-140kgf/sqmm. Confirming to IRS S3-61. PVC thickness 1mm. O.D. 8mm. Colour of PVC Red- 50% & Black-50%. Make:Bharat or similar. Inspection by Rep. of Railway Engineer. Note:-This item will be issued to contractor from Railway store only for picking of existing track circuits during Pre-Pre-NI & Pre-NI work.								
19	B	1998.00	Numbers	1.00	1998.00	AT Par	1998.00		
	Description:- Channel pin 7 mm dia. Inspection by Rep. of Railway Engineer. Note:-This item will be issued to contractor from Railway store only for picking of existing track circuits during Pre-Pre-NI & Pre-NI work.								
	S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	
								Bidding Unit	
Schedule () C-Execution of Telecom work								18708640.00	Above/ Below/P ar
	C	10.00	Job	950.00	9500.00	AT Par	9500.00		

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

1	Description:- Location survey of cable route and preparation of tentative and final cable route plan as per approved format in the section including supply of final route plan after the cables are laid and commissioned indicating clearly the exact position of the cable, joints and other critical items with reference to OHE mast & other fixed point, etc. in 12(twelve) Nos. hard bound copies on white bond paper of maximum A-3 size (well documented and bound with plastic covers). Here Job unit stands Rkm.						
2	C	20.00	Kilometre	93076.00	1861520.00	AT Par	1861520.00
	Description:- Excavation of trenches of following depth and width at the bottom of the trench including clearing of roots bushes etc. for all types of soils including morrum, hard soil mixed with boulders etc. This work include back filling the trench, ramming, consolidation of soil as well as disposal of extra soil after cable is placed in the trench. After mansoon the route is to be attended for back filling the rain cuts, wash out of soils where ever found. Depth 1.2 Mtr. & Width 0.3 Mtr.						
3	C	15.00	Kilometre	77389.00	1160835.00	AT Par	1160835.00
	Description:- Excavation of trenches of following depth and width at the bottom of the trench including clearing of roots bushes etc. for all types of soils including morrum, hard soil mixed with boulders etc. This work include back filling the trench, ramming, consolidation of soil as well as disposal of extra soil after cable is placed in the trench. After mansoon the route is to be attended for back filling the rain cuts, wash out of soils where ever found. Depth 1.0 Mtr. & Width 0.3Mtr.						
4	C	5.00	Kilometre	336450.00	1682250.00	AT Par	1682250.00
	Description:- Excavation of trenches including clearing of roots of trees etc. in hard/rocky soil by chiseling up to a depth of minimum 0.6 Mtr. and width 0.3 Mtr. at the bottom, supply and placing RCC hume pipe section as per drawing on sieved soil of 30mm over cable / HDPE pipe and concreting through - out the length upto a layer of 75mm. Then back filling the trench and then ramming of soil.						
5	C	500.00	Metre	540.00	270000.00	AT Par	270000.00
	Description:- Cutting the chase upto a depth of minimum 500 mm. and smoothening of inside surface in concrete and beds of rocks, cable laying/ placing HDPE pipe & concreting upto the ground level.						
6	C	1000.00	Metre	432.00	432000.00	AT Par	432000.00
	Description:- Cutting of solid rocks making channels 150 mm wide at the bottom X 200 mm deep by chase cutting & concreting upto the ground level after cable laying/ placing HDPE pipe.						
7	C	1500.00	Metre	748.00	1122000.00	AT Par	1122000.00
	Description:- Laying and Fixing of galvanised iron pipe (GI Pipe) with threaded collars (for jointing pipe) of 80 mm nominal dia Spec.No.IS-1239 medium grade, on bridges, culverts, drains including supply and transportation of GI pipes and all other materials required for fixing the pipe to Drg.No.Con/SK/T/2 and drawing of Signal/Power/Quad cables inside the pipe with masonry works over the entire length of the bridge and at entry and exit of the culvert and curing for 72 hrs, drilling of holes on the pipe at 10 cm apart to be clamped 2 Mtrs apart on culvert, for the Signalling, quad, power cable.						
8	C	2000.00	Metre	763.00	1526000.00	AT Par	1526000.00
	Description:- Laying of RCC pipe including supply of required quantity at site with collars (for jointing pipe) 150mm nominal dia to Spec.No:IS-458 in excavated trench (at bridges, culverts, roads, under railway track, Platform crossing, level crossing gate etc.) and drawing of HDPE pipe/ Power cable/ Quad cables/Jelly filled cables , etc. through pipe.						
9	C	500.00	Metre	1062.00	531000.00	AT Par	531000.00
	Description:- Track crossing, Road Crossing by pushing method (HDD method) at culverts/ Railway track / pucca road/Kuchha road at a depth not less than 1 meter with reference to bottom of rail/road surface including supply of HDPE pipe/DWC pipe(4 inch dia)						
10	C	2000.00	Metre	2210.00	4420000.00	AT Par	4420000.00
	Description:- Track crossing, Road Crossing by pushing method (HDD method) at culverts/ Railway track / pucca road/Kuchha road at a depth not less than 1 meter with reference to bottom of rail/road surface including supply of GI pipe with 76 mm dia, Spec. No. -1239 medium grade (for the length of pushing more than 05 meters).						
11	C	50.00	Kilometre	7762.00	388100.00	AT Par	388100.00
	Description:- Transportation including loading/unloading of HDPE pipe from the stores of railway to the work site, laying of the same (with 4 mm nylon rope pre-inserted inside the HDPE pipe) in excavated trench/already laid GI/RCC pipes/tubes, jointing, levelling and end sealing the pipes.						
12	C	50.00	Kilometre	18672.00	933600.00	AT Par	933600.00
	Description:- Transportation, loading/unloading of OFC from the stores of railway to the work site with care, pushing/pulling OFC through the HDPE pipes, sealing of the duct by sealling /caps plugs. The cable is to be laid by mechanised means. At inaccessible places where mechanised laying is not possible, the cable is to be laid manually by pulling through pre inserted rope. This also includes testing of cable drums in the store premises before transportation and submissions of results thereof. Empty cable drums to be returned by the contractor. The cable drums with unused cable at site to be returned by the contractor to the stores depot of SSE/Tele/Con/AJNI.						

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

13	C	50.00	Kilometre	16479.00	823950.00	AT Par	823950.00	
	Description:- Laying of Quad Cable, PIJF cable of different sizes, power cable of different size in the excavated trench, inside GI,RCC and HDPE pipes. This includes loading/unloading & transportation of cables from the stores of railway as per the availability. Wherever several cables of different categories have to be laid in the same trench/path, the provision of separation of various cable should be as advised by the site incharge of the Railway. Empty cable drums to be returned by the contractor. The cable drums with unused cable at site to be returned by the contractors from site to Stores depot AJNI.							
14	C	5.00	Kilometre	14419.00	72095.00	AT Par	72095.00	
	Description:- Supply and placing of warning tape Orange colour of 100 mm wide printed in black as "CAUTION OFC CABLE" at every 1 mtr. interval (minimum) and to be laid in the trench in station area and as directed by the representative of Railway.							
15	C	5.00	Kilometre	21869.00	109345.00	AT Par	109345.00	
	Description:- Supply, transportation, placing and positioning breadth-wise of standard second class bricks in excavated trench on the laid cable at the rate of 9 bricks per metre in the stations (Home signal to Home Signal) and colony area and at the locations as advised by site incharge of Railway.							
16	C	1200.00	Numbers	408.00	489600.00	AT Par	489600.00	
	Description:- Fixing of concrete cable route marker at 50 meter(approx) and at diversion point including supply & transportation of cable route marker at site. Detail size & fixing of cable route marker should be followed as per drawing no. SDO/Cable laying/020. Marker should be written as "RLY TELE"(both side).							
17	C	50.00	Numbers	573.00	28650.00	AT Par	28650.00	
	Description:- Cutting the masonry wall to the depth of 0.25m to 0.75m at the entry of room placing of flexible HDPE pipe or G.I.Pipe (including supply) of suitable size as per instructions of Railway site in charge and repairing of masonry wall and cement plastering after the cable is taken inside the flexible HDPE pipe/G.I. Pipe with clamps as per drawing No. RE/S&T/ALD/SK/161/81.							
18	C	50.00	Numbers	19019.00	950950.00	AT Par	950950.00	
	Description:- Transportation, installation of optical fibre joint closure and splicing of Optical fibre cable (2 x 24 fibres) and testing. Optical fibre cable splicing shall be done in the presence of Railway's representative. Only joint closure shall issued by the Railway. All other tools/test equipments required shall be arranged by the Contractor. This also includes excavation of earth for construction of masonry pit of bricks (inside complete plastered), the inner size of pit 1.2m x 1.2m (depth 0.75m) in all types of soils for keeping cable coils at the location of OFC joints, filling the pit with sand after jointing of cables, ramming and covering with RCC slab as per Drg. and instructions of site incharge of Railway.							
19	C	20.00	Numbers	21705.00	434100.00	AT Par	434100.00	
	Description:- Transportation, installation of Optical Fibre termination box and splicing of Optic Fibre Cable (24/48 fibre) inside the termination box with provision of taking out fibre of OFC as required. This includes supply of installation accessories (as required) as detailed in technical specification and advised by Railway's Engineer-at-site. This also includes End to End testing of all fibres of the optical fibre cable terminated between cable hut to cable hut of each station.							
20	C	50.00	Numbers	1993.00	99650.00	AT Par	99650.00	
	Description:- Transportation & Execution of following kinds of joints on Quad Cable using thermoshrink jointing kit. This also includes excavation of cable joint pit of size 1.2m x 1.2m x 1.0m in all types of soil for jointing of copper cables, back filling and ramming after jointing. Derivation/transformer joints with V.F. Transformers and derivation joint for L.C.Gate & Pump House on Quad/Jelly filled Telecom Cable.							
21	C	70.00	Numbers	1385.00	96950.00	AT Par	96950.00	
	Description:- Transportation & Execution of following kinds of joints on Quad Cable using thermoshrink jointing kit. This also includes Excavation of cable joint pit of size 1.2m x 1.2m x 1.0m in all types of soil for jointing of copper cables, back filling and ramming after jointing. straight through joint on Quad cable/10-20-50 pairs PIJF Cable.							
22	C	10.00	Numbers	792.00	7920.00	AT Par	7920.00	
	Description:- Transportation and fixing of following types of C.T.Box and termination of cable as per details of jointing schedule approved by the Railway Engineers. 10 pair C.T.Box (wago type)							
23	C	50.00	Numbers	792.00	39600.00	AT Par	39600.00	
	Description:- Transportation and fixing of following types of C.T.Box and termination of cable as per details of jointing schedule approved by the Railway Engineers. 20 pair C.T.Box (wago type)							
	C	50.00	Numbers	11504.00	575200.00	AT Par	575200.00	

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

25	Description:- Supply transportation, fixing, wiring, termination of cable, erection of rail post of size 2.8mtrs including foundation of post in cement concrete (1:2:4) as per the direction of the site Engineer incharge of Railway, testing and commissioning of six pin emergency socket box complete cast iron make as per Drg. No. SE/T/50/76. This include transportation of rail posts (provided by the Railway) from Bilaspur or any place in the section to work site, fixing of 40 mm dia G.I.Pipe and emergency socket box. Cast iron emergency socket box with complete fittings are to be first supplied to the stores of SSE/Con/Tele/AQ and then collected from there for execution. Supply of U-bolt for fixing emergency socket, cutting of Rails to the size and welding of G.I.Pipe on the rail post will be done by the Contractor. This work includes painting of rail posts with black and white paints after two times primer coating. Note :- 10 Nos of emergency sockets with complete fittings including Cast iron box to be supplied extra as spare within the same cost.							
26	C	50.00	Numbers	990.00	49500.00	AT Par	49500.00	
	Description:- Transportation, Wiring and installation of magneto telephone at L.C.Gate/pump house or the places as advised by the site incharge. This includes supply and fixing of Telephone rack of approved design by the contractor.							
27	C	50.00	Numbers	892.00	44600.00	AT Par	44600.00	
	Description:- Dismantaling of unused/old emergency socket post approximate dimention Height - 1.25 mtr * cross section- 15 c m x 15 cm (drg enclosed) and transportation from site to GSD store/Raipur, which includes excavation of soil/ concrete to a depth of 15 cm from the surface and back filling and ramming after cutting the post. This is required to avoid projection of remain of post over the ground level. The contractor must ensure, that rail post shall be cut below the normal ground surface area.							
28	C	20.00	Numbers	1053.00	21060.00	AT Par	21060.00	
	Description:- Shifting/ re-location, fixing, erection of rail post of size 2.8mtrs and testing of emergency socket as per direction of site engineer of railway. This includes excavation of trenching for shifting the existing 10/20 PIJF cable, clearing of existing Rail post with foundation and re-erection of same rail post.							
29	C	50.00	Numbers	480.00	24000.00	AT Par	24000.00	
	Description:- Transportation, installation, testing & commissioning of 4W way station equipment DTMF type and way station 4W control telephone including termination of the electric wires, battery wires, switch board cable on the equipment. The termination shall be done using eyelets of required size. The way station equipments shall be fixed over the wall on board of approved design. Board and all the materials required for fixing and termination to be supplied by the contractor.							
30	C	20.00	Numbers	480.00	9600.00	AT Par	9600.00	
	Description:- Transportation, installation and commissioning of 12V. Power supply unit for telecom installations at wayside stations on wall mounting stand of approved design including termination of Power supply cable all other materials required for fixing and termination to be supplied by the contractor.							
31	C	5.00	Station	44126.00	220630.00	AT Par	220630.00	
	Description:- Transportation, Installation & commissioning of SDH ADM, Primary D/I MUX with all accessories and power supply, racks, runway ladder etc. in cable huts including wiring of all the equipments up to C.T. Box install for Outdoor/ Derivation cables as per the requirement at each station. Note:- The work involves fixing of 19" rack, Installation & wiring of equipment connecting to 48 V. bus bar including supply of all wires and connectors. The equipment shall be mounted in shelves of standard 19" racks. All 21 E1 streams shall be suitably terminated on Digital Distribution Frame. All the wiring shall be done in accordance with wiring instructions given in as per Annexure-VII .							
32	C	5.00	Numbers	49643.00	248215.00	AT Par	248215.00	
	Description:- Supply, Installation and commissioning of Surge & Lightning protection arrangement in the cable huts for all the equipments including all the circuits derived from MUX at the stations and Ring Earth (Six Earth pits). Each earth shall be as per RDSO Specification no. RDSO/SPN/197/ 2008 (drawings enclosed).							
33	C	5.00	Numbers	944.00	4720.00	AT Par	4720.00	
	Description:- Installation and commissioning of Fibre Distribution Frame.							
34	C	500.00	Metre	43.00	21500.00	AT Par	21500.00	
	Description:- Supply and fixing of PVC casing caping 25mm x 25mm size for indoor wiring. This includes drawal of wires in the casing caping and termination of wire at end point. The work should be carried out as per the instruction of Railway site Engineer.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () D-Supply of Telecom materials							5384563.00	Above/ Below/ Par
	D	50.00	Numbers	3483.00	174150.00	AT Par	174150.00	

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

1	Description:- Supply of Optical fibre joint closure for straight through joint with modification for 24 fibre OFC as per Specification. No. RDSO/SPN/TC/68/2013 (with latest amendment) complete with all accessories (sealing with mechanical clamp facility) make Raychem or similar. Inspection by Rep. of CSTE/Con/BSP.						
	D	50.00	Numbers	3425.00	171250.00	AT Par	171250.00
2	Description:- Supply of Universal thermoshrink jointing kit for derivation/ transformer joint for Jelly filled Six quad cable conforming to RDSO Spec. No :IRS-TC-77/2006(Rev.1) (With latest amendment). Inspection by RDSO.						
	D	5.00	Numbers	1037.00	5185.00	AT Par	5185.00
3	Description:- Supply of VF Tapping Transformer 1120:470 (rack mountable) as per specification No. IRS- TC-22/76(With latest amendment). Inspection by Rep. of Railway Engineer.						
	D	5.00	Numbers	1120.00	5600.00	AT Par	5600.00
4	Description:- Supply of VF Tapping Transformer 1120:1120 (rack mountable) as per specification No. IRS TC-22/76(With latest amendment). Inspection by Rep. of Railway Engineer.						
	D	5.00	Numbers	1120.00	5600.00	AT Par	5600.00
5	Description:- Supply of VF Tapping Transformer 1120:600 (rack mountable) as per specification No. IRS- TC-22/76(With latest amendment). Inspection by Rep. of Railway Engineer.						
	D	30.00	Kilometre	99200.00	2976000.00	AT Par	2976000.00
6	Description:- Supply of permanently lubricated HDPE pipe with outer dia 50mm, inner dia - 42mm thickness - 4mm with suitable couplers, plugs, end caps etc. as per technical specification No. G/CDS-08/01 Dec. 1999. Supply to be made in length of 500 mtrs with + /-10% tolerance. Inspection by RITES.						
	D	10.00	Numbers	6657.00	66570.00	AT Par	66570.00
7	Description:- Supply of 4 wire Way-station Control Equipment DTMF type as per IRS Spec. No. : TC 60/2007(with latest amendment) including way station control telephone as per RDSO spec. no.IRS TC 38-97(latest amendment). Inspection by Rep. of Railway Engineer.						
	D	10.00	Numbers	7456.00	74560.00	AT Par	74560.00
8	Description:- Supply of 12 V. Power supply unit for Telecom. Installation for way-side equipment in 25 KV Electrified area suitable for 6 equipment of DTMF type as per IRS Spec. No : TC 72-97(with latest amendment) including 12V, 7AH maintenance free battery. Inspection by Rep. of Railway Engineer.						
	D	50.00	Numbers	1892.00	94600.00	AT Par	94600.00
9	Description:- Supply of one quad VF transformer assembly 2T for quad cable (470 : 1120) for derivation joints to specification No. IRS-TC-76/2000 (With latest amendment). Inspection by Rep. of Railway Engineer..						
	D	30.00	Numbers	2865.00	85950.00	AT Par	85950.00
10	Description:- Supply of following type of Wago Make Terminal block(with lever type disconnection & reconnection facility) duly fitted in C.T. box of approved quality, suitable for termination of 0.9mm wire.20 Pair. Inspection by Rep. of Railway Engineer.						
	D	100.00	Metre	24.00	2400.00	AT Par	2400.00
11	Description:- Supply of following types of twisted pair PVC switch board cable, conductor of size 0.6mm. dia annealed copper conforming to IRS-TC-24/91 or ITD 1138. Inspection by Rep. of CSTE/Con/BSP. 5 pair						
	D	200.00	Metre	39.00	7800.00	AT Par	7800.00
12	Description:- Supply of following types of twisted pair PVC switch board cable, conductor of size 0.6mm. dia annealed copper conforming to IRS-TC-24/91 or ITD 1138. Inspection by Rep. of Railway Engineer. 10 pair.						
	D	200.00	Metre	66.00	13200.00	AT Par	13200.00
13	Description:- Supply of following types of twisted pair PVC switch board cable, conductor of size 0.6mm. dia annealed copper conforming to IRS-TC-24/91 or ITD 1138. Inspection by Rep. of Railway Engineer. 20 pair.						
	D	3050.00	Metre	37.00	112850.00	AT Par	112850.00
14	Description:- Supply of UTP CAT 6 Cable (Roll is 305 Mtr). Make Amp or Molex. Inspection by Rep. of Railway Engineer.						
	D	3.00	Numbers	311694.00	935082.00	AT Par	935082.00
15							

**DYCS-TE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

15	Description:- Supply of managed expandable rack type STM-4, equipped STM-1, ADMS 1.1, as per technical Specification no. TECGRNO. GR/SDH-10/02 March 05 (with latest amendment) with 2 Nos. STM-1 aggregate Optical interface upgradable to STM-4, 21E1s, and minimum 8 Nos. of 10/100 base T Ethernet port, Order wire, Power supply unit, subrack, DDF, Installation materials, manuals and other accessories. The equipment should be TEC/BSNL/RDSO approved. The equipment should be fully wired for its ultimate capacity and provide redundancy for Power supply and Synchronisation. It shall be possible to use the full capacity of the equipment by adding additional tributary cards. The upgradation of STM-1 to STM-4 shall be without change of any internal hardware of the STM equipment. The STM equipment shall have in-built L2 switch for Ethernet ports. Make-Tejas, compatible to existing STM System in the section. Inspection by RDSO							
	D	3.00	Numbers	217922.00	653766.00	AT Par	653766.00	
16	Description:- Supply of programmable Primary Digital Drop Insert Multiplexer complete with all accessories from RDSO approved vendor as per RDSO specification IRSTC68-12 (with latest amendment) including connectors and cables required for installation including 100 pair Krone type MDF. Each channel card shall have minimum four channels per card. The single subrack shall be capable of being equipped up to min. 60 Channels without additional power supply unit. Specification as per Annexure I. The MUX shall be wired & equipped for 30 channels, with following circuits:- 16 Nos. VF2W/4WE&M circuits, 8 nos. of 2 wire FXO circuits, 6 Nos. 2W.Subs/Hotline circuits along with ringer card., compatible to existing PUNCOM make MUX. Inspection by RDSO							
	D	3.00	Numbers	217922.00	653766.00	AT Par	653766.00	
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A1-Execution of Indoor Signalling work							766560.00	Above/ Below/Par
1	A1	5.00	Numbers	48363.00	241815.00	AT Par	241815.00	
	Description:- Q-series/Composite Relay Racks and cable termination racks (New). NOTE: Payment can be released in a part for the above said work after completion of- (i) Erection-15%, (ii) Wiring, testing, painting, earthing & writings etc- 75% , (iii) Commissioning of Relay rack/ Composite rack/CTR- 10% of Schedule rate.							
2	A1	25.00	Numbers	19785.00	494625.00	AT Par	494625.00	
	Description:- Alteration of existing Q-series/Composite Relay Racks and cable termination racks. NOTE: Payment can be released in a part for the above said work after completion of- (i) Erection-15%, (ii) Wiring, testing, painting, earthing & writings etc-75%, (iii) Commissioning of Relay rack/Composite rack/CTR- 10% of Schedule rate.							
3	A1	20.00	Each	507.00	10140.00	AT Par	10140.00	
	Description:- Installation and wiring of Rotary key transmitters/KLCR on teak wood board enclosed inside a suitable box with front transparent check cover with locking arrangement. This includes 3/4" thick teak wood boards, transparent sheet for box, locking arrangement. 2 nos. of locks for box and 1 No. lock for front transparent sheet.							
4	A1	20.00	Numbers	999.00	19980.00	AT Par	19980.00	
	Description:- Installation, cable termination, wiring, testing of magneto telephones.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A2-Signalling Design & Drawing							390326.00	Above/ Below/Par
1	A2	10.00	Station	2511.00	25110.00	AT Par	25110.00	
	Description:- Design & development of cable corage plan in size U(A3) as per SEM.							
2	A2	350.00	Sheet	1004.00	351400.00	AT Par	351400.00	
	Description:- Design and development of Circuit Diagram/Logic in size B(A3) as per SEM sheet including contact analysis.							
3	A2	10.00	Station	1256.00	12560.00	AT Par	12560.00	
	Description:- Design & development of cable route plan in size U(A3) as per SEM.							
4	A2	1.00	Station	1256.00	1256.00	AT Par	1256.00	
	Description:- Design & development of Track bonding plan in size U(A3) as per SEM.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B1-Supply of Signalling Battery							607200.00	Above/ Below/Par
	B1	200.00	Numbers	3036.00	607200.00	AT Par	607200.00	

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

1	Description:- Low maintenance lead acid stationary secondary cells for S&T installations made of PP-CP container and with initial charging of nominal voltage 2 volts as per Specn.No.IRS-S-88/2004 with latest amd. Inspection by RDSO. i) 80 AH							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B2-Supply of Signalling materials							1048434.00	Above/ Below/P ar
1	B2	1.00	Kilometre	10784.00	10784.00	AT Par	10784.00	
	Description:- Cable PVC insulated single core unsheathed with plain annealed copper conductor as per the colour coding scheme of Railways. Spec. no: IRS-S-76/89 with latest amendment. Inspection by RDSO. 16/0.2 mm dia.							
2	B2	50.00	Each	5172.00	258600.00	AT Par	258600.00	
	Description:- Track feed Battery chargers 110V-AC 50 C/S with boost and trickle charging for 1 or 2 or 3 cells 80 A.H.Spec.No.IRS:S-89/2013 with latest amd. Inspection by RDSO.							
3	B2	100.00	Numbers	1039.00	103900.00	AT Par	103900.00	
	Description:- Track lead Junction Box(4-way) made of fibre re-inforced plastic Drg. SI-10272 Alt. 'B'. as per Spec. No. IRS: S- 10/78. This also includes 4 nos. of PBT terminals for the same.Inspection by Rep. of CSTE/Con/BSP.							
4	B2	50.00	Numbers	171.00	8550.00	AT Par	8550.00	
	Description:- Track feed resistance 30 ohms (2,4,8,16 Ohms) Drg. No. SA-20166 (Adv.) Spec. No: IRS. S/23. Inspection by RDSO.							
5	B2	100.00	Numbers	4594.00	459400.00	AT Par	459400.00	
	Description:- Choke coil 'B' Type as per spec. no:IRS:S-65/83 with latest amendment if any. Inspection by RDSO.							
6	B2	500.00	Numbers	81.00	40500.00	AT Par	40500.00	
	Description:- Non-deteriorating type low voltage electric fuse for Railway signalling, rated voltage 240 V AC/DC fuse with cylindrical cap without indication size :14x 51 mm. Spec. no: IRS-S-78/92 with latest amendment if any. Inspection by RDSO. 04 Amp fuse catridge.							
7	B2	500.00	Numbers	189.00	94500.00	AT Par	94500.00	
	Description:- Fuse Block for above fuse catridge, Spec. no: IRS-S-75/2006 (rev-2) with latest amendment if any. Inspection by RDSO.							
8	B2	200.00	Numbers	361.00	72200.00	AT Par	72200.00	
	Description:- ARA terminal for Signalling Installation with PBT materials. Inspection by RDSO. 6 Way (ARA terminal) Drg No.SA-23756 Alt3, Specn No. IRS-S-75/2006 (Rev.-2) with latest amd.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B3-Supply of Electrical & Electronics materials							7357037.00	Above/ Below/P ar
1	B3	35.00	Numbers	23526.00	823410.00	AT Par	823410.00	
	Description:- Earthing and bonding system as per RDSO Spec. No.RDSO/SPN/197/2008, RDSO Drg. No. SDO/RDSO/E&B/001 dt. 19.09.08 and RDSO Drg. No. SDO/RDSO/ E&B/002 dt.19.09.08. Earthing and bonding system for Relay Room , IPS Room ,SPD Box, Operator panel in SM's room, signalling equipments in Station building, Block circuit, SSDAC, etc. Inspection by RDSO. Engineer. Supply of Permanent and Maintenance Free Earth pits materials: (i)17 mm diameter and minimum 3 m long Copper Bonded Steel Rod - 1No, (ii) GEM- 25 lb - 3 Bags, (iii) 25*6*150 mm Cu Bus Bar- 2 Nos. (iv) Cu lugs and nut bolt 2 nos. (v) Supply for Connection between Earth pits and MEBB It includes 35 sq.mm multi-strand pvc insulated single core Cu cable (15 mtr Lump Sum), (vi) Supply for Internal connection from MEBB To SEBB and to other equipments.(50 mtr Lump Sum).It includes 16 sq mm and 10 sq mm multi strand pvc insulated single core Cu cable.							
2	B3	35.00	Numbers	5882.00	205870.00	AT Par	205870.00	
	Description:- Installation, testing and commissioning of Permanent and Maintenance Free Earth pits. Installation charges : Earth pit (1 Set) It includes, Civil works related to earth pit digging, PMF earth pit installation, backfilling and chamber making. Materials for chamber including Chamber Cover.							
3	B3	3.00	Set	548759.00	1646277.00	AT Par	1646277.00	
	Description:- Electrically operated lifting barrier complete as per RDSO SPN no. 208/2012 Ver-2 with latest Amendment, operating voltage 110V AC, without hand generator, length of the boom is 9.76 meter/32 feet. Inspection by RDSO. Note:- Spare shall also be supplied as per RDSO specifications (rates for them are included above).							
	B3	5.00	Set	37882.00	189410.00	AT Par	189410.00	

**DYCS-TE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

4				Description:- Supply of fuse indication cum monitoring and automatic changeover system as per RDSO specification no. RDSO/SPN/209/2012 Rev. 0 or latest. The system shall be supplied along with all standby fuses placed in the system. In addition to it, spare quantity of 100% fuses of each type shall also be supplied along with the system. Inspection by RDSO. For 32 fuses per set (Upto 4 Amps).			
5	B3	20.00	Numbers	9469.00	189380.00	AT Par	189380.00
				Description:- Transportation, installation, testing & commissioning of fuse indication cum monitoring and automatic changeover system as mentioned above.			
6	B3	50.00	Numbers	3821.00	191050.00	AT Par	191050.00
				Description:- Relay, Non-AC Immune, plug-in type, Style "QN1", Neutral line, 24V DC 8F.8B contacts, front and back contacts metal to carbon with plug board, retaining clip & connectors conforming to BRS:930, IRS:S 34 & IRS:S 23. The interlocking code for this unit shall be ABCDF. Inspection by RDSO.			
7	B3	10.00	Numbers	6489.00	64890.00	AT Par	64890.00
				Description:- Relay AC Immune, plugin type, STYLE QBAT, DC Biased track, 90hms, 2F-2B, Contacts, front and back contacts metal to carbon complete with plug-board, retaining clip and connectors conforming to RDSO/SPN/84-88, IRS:S34&IRSS:23. The interlocking code for for this unit shall be ABEJX. Inspection by RDSO.			
8	B3	200.00	Numbers	6770.00	1354000.00	AT Par	1354000.00
				Description:- Relay Plug in type Style'QL1', Magnetically latched neutral line, 24VDC 11F/4B contacts each, front and back contact metal to carbon ,complete with plug board, retaining clips and connectors conforming to BRS:935A, IRS:S 34 & IRS:S 23. Interlocking code of this unit shall be ABDEG. Inspection by RDSO.			
9	B3	1.00	Numbers	367404.00	367404.00	AT Par	367404.00
				Description:- Cable Route locator, make- 3M Dynatel, Model no- 2250- U3P3 microprocessor based system or similar for tracing of path of underground cables, both copper & fibre optics having specification:- Coupler Size 3.00 Inch; Direct Connect Cable- Large Clips;Number of Frequencies- 4; Operating Temperature Range -20 to 50 Degree Celsius; Storage Temperature -40 to 70 Degree Celsius; Transmitter Output- 3 Watt. Inspection by Rep. of Railway Engineer.			
10	B3	20.00	Numbers	4804.00	96080.00	AT Par	96080.00
				Description:- Relay, ACImmune, plug-intype, Style "QNA1K", Neutral line, 24VDC1000ohms 6F.6Bcontacts, front and back contacts metal to carbon with plug board, retaining clip & connectors conforming to BRS:931A, IRS:S60, IRS:S34&IRS:S23&RDSO Spec. no. STS/E/Relay/UEA(PI). The interlocking code for this unit shall be CDEKY. Inspection by RDSO.			
11	B3	3.00	Numbers	3808.00	11424.00	AT Par	11424.00
				Description:- Supply of isolator devices for every 20 detectors, complying to the RDSO/SPN/217/2016 Ver 1 or latest. Inspection by RDSO.			
12	B3	3.00	Station	17553.00	52659.00	AT Par	52659.00
				Description:- Installation, Testing and commissioning of all above items as per requirement at site. The work will execute as per Inspection by RDSO.			
13	B3	200.00	Numbers	4944.00	988800.00	AT Par	988800.00
				Description:- Relay, AC Immune, plug-in type, Style 'QSPA1', Neutral line, slow to pickup, 24V DC, 8F.4B contacts, front and back contacts metal to carbon, complete with plug board, retaining clip & connectors conforming to BRS:933A, IRS:S 60, IRS:S 34 & IRS:S 23. The interlocking code for this unit shall be ABDEJ. Inspection by RDSO.			
14	B3	100.00	Numbers	5015.00	501500.00	AT Par	501500.00
				Description:- Universal relay, plug in type, style AC/LED all aspects AC lamp proving relay unit with in built current transformer type, slow release neutral line relay 4F/4B contacts, front and back contacts metal to carbon, shall be suitable for working in series with the 110AC LED signal lamp rated at 15W conforming to RDSO specn. no. BRS:941A , STS/E/RELAYS/AC LIT/LED Signal/09-2002, Amdt-1 with latest. Inspection by RDSO.			
15	B3	3.00	Numbers	83776.00	251328.00	AT Par	251328.00
				Description:- Supply Fire Alarm System of Microprocessor based intelligent, addressable, modular, 1 loop (minimum 125 detector/devices per loopexpandableto 2 loops) Fire Alarm Control Panel with LCD display with 320 Character with soft keys for displaying alarm, events and operating functions, Day/ Night operation function, Remote maintenance service feature etc. The panel should be multi-protocol ie able to support at least 2 additional different makes of addressable detectors. The panel should have minimum two relay outputs & 1Monitored Sounder Output. It should have provision to be connected to repeater panels in future. The panel shall capable to operate on240 volts AC power supply, automatic battery charger, 24 volts, sealed lead acid maintenance free batteries sufficient for 24 hours normal working and then be capable of operating the system for 30 minutes during emergency condition as per detailed specifications complete as required. Panel Should Be VdS/UL/FM/EN/LPCB Certified as per RDSO Specification No. RDSO/SPN/217/2016 Ver 1or latest. Inspection by RDSO. Annexure: E			
	B3	75.00	Numbers	3712.00	278400.00	AT Par	278400.00

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

16	Description:- Supply of Analogue Addressable Multisensor Detector with multiple sensitivity(adjustable at site) levels , programmable for timed automatic sensitivity selection with base, and other accessories as required and Detectors shall be dS/UL/FM/EN/LPCB listed. The Detectors shall comply to the RDSO/SPN/217/2016 Ver 1 or latest. Inspection by RDSO.							
17	B3	6.00	Numbers	5712.00	34272.00	AT Par	34272.00	
18	Description:- Supply of Manual call points, Push type & resettable with key, with In-built isolator. Shall be VdS/UL/FM/EN/LPCB compliant and shall comply to the RDSO/SPN/217/2016 Ver 1 or latest. Inspection by RDSO.							
19	B3	3.00	Numbers	8949.00	26847.00	AT Par	26847.00	
20	Description:- Supply of Output Module which will provide potential free (NO/NC) contact to existing Data Logger. Complying to the RDSO/SPN/217/2016 Ver 1 or latest. Note:- The contractor will provide potential free contact for goomty and Relay Room only. The connectivity with existing data logger will be done by Railway. Inspection by RDSO.							
21	B3	6.00	Numbers	7806.00	46836.00	AT Par	46836.00	
22	Description:- Supply of Hooter cum Strobe complying to the RDSO/SPN/217/2016 Ver 1 or latest. Inspection by RDSO.							
23	B3	300.00	Numbers	124.00	37200.00	AT Par	37200.00	
24	Description:- Supply of 2C 1.5 sq mm twisted shielded armoured copper cable. Inspection by RDSO.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () NS1-Supply & Installation of Non SOR							41582552.50	Above/ Below/P ar
1	NS1	1.00	Pair	32709.00	32709.00	AT Par	32709.00	
2	Description:- Supply of Automatic Media changeover of modem working on redudent channels for data transmission on OFC/Quad to suit Dual redudent arrangement of UFSBI . Inspection by Rep. of Railway Engineer.							
3	NS1	1.00	Pair	58410.00	58410.00	AT Par	58410.00	
4	Description:- Supply of Modem for UFSBI(for use of secondary media OFC/Quad) to suit Dual redudent arrangement of UFSBI. Railway shall define Secondary media before placing of order. Inspection by Rep. of Railway Engineer.							
5	NS1	2.00	Numbers	25437.00	50874.00	AT Par	50874.00	
6	Description:- Tranportation, Installation, wiring and commissiiong of 48V, 200AH VRLA battery bank and battery charger at each OFC installations, distribution of AC supply to the charger including Supply of wiring materials, commissioning of AC&DC power supply Distribution system including earthing protection arrangement and wiring of Battery Chargers & Batteries etc as per manufacturer's instructions and railway's directions. It includes supply of battery rack of approved desin, as per site requirement. All the wiring shall be done in accordance with wiring instructions given in as per Annexure-VII.							
7	NS1	50.00	cum	7113.00	355650.00	AT Par	355650.00	
8	Description:- Concreting of Chasing ratio 1:3:6 cement, sand & stone of size 20mm approximate height of 80mm built on wire mesh of minimum 19 SWG of across area section 50 mm. works is to be executed as per the instruction of Railway site engineer. (The width & height of concreting is to be decided by the site incharge as per the site condition) all materials required for the execution of the work is to be.							
9	NS1	1000.00	Metre	825.00	825000.00	AT Par	825000.00	
10	Description:- Excavation of trench and clearing of roots of trees, bushes, ballast and reconditioning etc., including bailing out water and disposal of extra soil.(iii) Preparation of Cable duct upto depth 0.7 mtr & width 0.3 mtr in hard rocky area with the help of hydrolic breaker and supply and placing of half round hume pipe and concreting upto 100mm(proportion 1:3:6) using concrete mixture after laying of cables. It includes all materials required at site for concreting including cement and curing upto72 hrs and then back filling.							
11	NS1	200.00	Job	5500.00	1100000.00	AT Par	1100000.00	
12	Description:- Tracing & testing of exisiting cables (OFC & 6 Quad) for identification of faulty location with the deployment of LABOUR for digging pits, OTDR Tools, like megger, cable fault, locator ,cable route tracer, OFC splicing Machine supported.							
13	NS1	2000.00	Metre	2108.00	4216000.00	AT Par	4216000.00	
14	Description:- Supply, placing & covering of RCC duct as per para 6.4, 6.5& 7.1 and Annexure 9 of RDSO guidelines for cable laying detailed in technical specification. This includes trenching of 1.0 Mtr. depth and backfilling. Notes mentioned in Annexure 9 are to be complied necessarily.							
15	NS1	8000.00	Metre	616.00	4928000.00	AT Par	4928000.00	

**DYCS-TE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

8	Description:- Horizontal direction drilling(HDD)/Trenchless digging/machine drilling without damage to surface road track for laying/insertion of HDPE/GI/DWC pipe. The bore shall be done of min. diameter 120mm & at the depth of minimum 1400mm from the ground level. The ground level shall be considered ignoring the bank height of the bank of the road. Note:-DWC/HDPE/GI Pipe Supply is not covered under this item. Contactor shall provide all material required for work and adequate nos, of labours for proper laying of cables into the bore. Cable shall be laid cautiously so that it should not get damage due to rough handling & pressure on cable. Payment of boring shall be made only after two nos. of DWC/HDPE(40/50 mm dia.)/GI pipe is laid in the bore.						
9	NS1	30.00	Numbers	6303.00	189090.00	AT Par	189090.00
	Description:- Relay, Non-AC Immune, plug-in type, Style "QN1", Neutral line, 50V DC 8F/8B contacts, front and back contacts metal to carbon with plug board, retaining clip & connectors conforming to BRS:930, IRS:S 34 & IRS:S 23. The interlocking code for this unit shall be ABCDF. Inspection by RDSO.						
10	NS1	730.00	Day	954.00	696420.00	AT Par	696420.00
	Description:- Hiring of Skilled Labour assistance SE/JE in day today works i.e. assisting for supervising cable laying work, noting of daily work status, carrying the tools & equipments etc watch & ward during the course of execution of work as per the instructions of concerned SE/JE (c)						
11	NS1	30.00	Numbers	3658.00	109740.00	AT Par	109740.00
	Description:- Slave telephone of Electronic LC Gate communication system as per RDSO Specification No. RDSO/SPN/TC/51/2021 (Rev. 3.0) Amend-1 or latest with Surge Protection and Line Connection Unit. Inspection by RDSO. Make:- EPSILON/ BENTRON or Similar.						
12	NS1	6.00	Numbers	33040.00	198240.00	AT Par	198240.00
	Description:- Master Telephone of Electronic LC gate communication with Voice Logger as per RDSO Specification No. RDSO/SPN/TC/51/2021 (Rev. 3.0) Amdt. 1 or latest. Inspection by RDSO. Make:- EPSILON/ BENTRON or Similar						
13	NS1	20.00	Numbers	5133.00	102660.00	AT Par	102660.00
	Description:- 24V DC Power supply Unit with MF battery for Master & slave phones for LC Gate Telephone System as per RDSO Specification No; DSO/SPN/TC/51/2021 Rev. 1.0 or latest. Inspection by RDSO. Make:-EPSILON/BENTRON or Similar.						
14	NS1	4.00	Numbers	2159.00	8636.00	AT Par	8636.00
	Description:- Transportation, Installation, testing commissioning of 25 Watt VHF set, antenna on roof with the help of GI pipe and clamp.						
15	NS1	20.00	Numbers	10384.00	207680.00	AT Par	207680.00
	Description:- Supply of 24F fully loaded FMS suitable for Railway's OFC System Complete with 24 nos. 0db adaptor and 24 nos. 1m length Pigtails and 6 nos. 1m Pigtail on spare. All are "SC" type connectors. Inspection by Rep. of Railway Engineer.						
16	NS1	50.00	Numbers	986.00	49300.00	AT Par	49300.00
	Description:- Supply of Optical fibre Patch cords with SC-LC or suitable connectors on both ends as per site requirement for interconnection between FMS and Optical Modem length 10 Mtrs. Each as per TEC Specification No. G/OFJ-01/03 JUN 99 (With latest amendment). Max Permissible loss-0.2dB. Inspection by Rep. of Railway Engineer.						
17	NS1	5.00	Numbers	70130.00	350650.00	AT Par	350650.00
	Description:- Supply of digital Multi meter fluke make model 289 or latest or Philips. Inspection by Rep. of Railway Engineer.						
18	NS1	5.00	Numbers	3259.00	16295.00	AT Par	16295.00
	Description:- Supply And Transportation of PA screen Cable Roll at Site (Roll 50 Mtrs each). Inspection by Rep. of Railway Engineer.						
19	NS1	1.00	Numbers	499729.00	499729.00	AT Par	499729.00
	Description:- Automatic Fusion Splicer for single mode Optical fibre cable, along with accessories as per TEC spec. TEC/GR/TX/OSM - 001/04/SEP-12 or latest of make: Superior/Fujikura or similar. Make: INDIGENOUS. (Warranty Period : Upto 30 months from the date of delivery.) Inspection by Rep. of Railway Engineer.						
20	NS1	2.00	Numbers	23261.00	46522.00	AT Par	46522.00
	Description:- Supply of Optical Power meter(wave length, 1310 nm &1550 nm user selectable, measuring range +3dbm to-60dbm, as per technical spec.no. GR/OPM 01/03.Jan 5.(Type B) or latest specification. Inspection by Rep. of Railway Engineer.						
21	NS1	5.00	Numbers	835.00	4175.00	AT Par	4175.00
	Description:- Supply of Crimping tool suitable for RJ45 and RJ11 connector. Inspection by Rep. of Railway Engineer.						
22	NS1	2.00	Numbers	530886.00	1061772.00	AT Par	1061772.00

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

	Description:- Supply of OTDR as per TEC Specification No. TEC/GR/TX/OTD-02/04/Aug19(with latest amendment) and additional requirements. Make: STANLAY/APL2PLUS-502C or Similar Make : Stanlay (Warranty Period : Upto 30 months from the date of delivery.) Inspection by Rep. of Railway Engineer.						
23	NS1	2000.00	Metre	34.22	68440.00	AT Par	68440.00
	Description:- 6 fibre optic Single Mode armoured Out Door (OFC) cable. Make Finolex, Syrotech, and Sterlite.						
24	NS1	2.00	Numbers	24750.00	49500.00	AT Par	49500.00
	Description:- Supply of Transmission measuring set (TMS kit) complete with tone generator and Db meter as RDSO specification IRS: TC-43/87 or latest, make Anu vidhyut or equivalent Note: - The sample must be approved by the consignee before actual delivery. Firm's Offer-Make/Brand-Self or similar. Inspection by Rep. of Railway Engineer.						
25	NS1	2.00	Numbers	48400.00	96800.00	AT Par	96800.00
	Description:- Digital Cross Talk Meter measuring set as per SPN IRS TC: 45/88 with latest amdt. Make Anu vidyut or Aplab or Similar Accepted. Inspection by Rep. of Railway Engineer.						
26	NS1	5.00	Numbers	90832.00	454160.00	AT Par	454160.00
	Description:- Supply of Microcontroller based Quad Cable Conductor's Earth Resistance Sensing Unit, for 24nos. conductors with measuring facility for one conductor at a time as per attached specification. Inspection by RITES.						
27	NS1	50000.00	Numbers	12.00	600000.00	AT Par	600000.00
	Description:- Supply & Installation of ferrules of different colour, printing termination details / Functions in different colours as per Railway specification and installation in Relay room, Location Box and Power board etc, at various stations and LC gates as per instruction of Engg. in charge. All materials required for the work shall be supplied by the contractor. Inspection by Rep. of Railway Engineer.						
28	NS1	250.00	Numbers	10376.00	2594000.00	AT Par	2594000.00
	Description:- Supply of relay AC Immune, Plug-in type, Style - QBCA1 DC biased point contractor, 24V DC, 2F(HD)-4B contacts. Front contacts(heavy duty) and Back contacts metal to carbon, complete with plug board, retaining clip and connectors with latest amendment conforming to BRS: 943, IRS: S 34 and IRS: S 23. The interlocking code for this unit shall be BCEJK. Inspection by RDSO.						
29	NS1	20.00	Numbers	5778.00	115560.00	AT Par	115560.00
	Description:- Supply of Fire Extinguisher CO2 Type, Capacity:- 4.5 kg Aluminum as per IS:15683 Latest. Test certificate of all fire extinguishers should be from NABL accredited laboratory. ACCEPTED MAKE/BRAND -E cofire or similar. Inspection by Rep. of Railway Engineer.						
30	NS1	2.00	Numbers	301400.00	602800.00	AT Par	602800.00
	Description:- Supply and installation of Class-A protection as per RDSO Drg. Circulated vide letter no. STS/L/SSI/CA/US&S dated 26.07.2011 for EI system. Inspection by Rep. of CSTE/Con/BSP. (Work to be done as per extant guidelines and instruction of representative of Dy. CSTE/CON/NGP.)						
31	NS1	100.00	Numbers	165.00	16500.00	AT Par	16500.00
	Description:- Rubber Painting of the Steel apparatus case (Large) having Drg.No. CON/SK/T/8 outside upto 30 cm from bottom after clearing the surface thoroughly.						
32	NS1	1.00	Pair	198885.00	198885.00	AT Par	198885.00
	Description:- Supply, Installation, testing and commissioning of Automatic changeover device for DAC/ UFSBI V.21/ V.23 to Optical fibre, STM(E1), Standard 19" rack mountable device consisting of two E1 port supporting 120 ohms interface; dual optical ports with (1+1) hot stand by (dual core path and single core path) 20 Kms driving distance and four V.21/V.23 (E&M) 2W/4W interfaces with auto change over mechanism to Quad ports 2W/4W ; each port configurable as 2W or 4W no restriction in configuration ; unit to support Potential free contacts four numbers can be linked with datalogger / RTU for E1 Status, Quad Status & Power Supply status : Unit support front panel resettable audible buzzer in case of main link fails (optical or E1) ; Unit to support power OFF fail safe mechanism when the unit is switched OFF the inputs is bypassed to the Quad cable automatically unit supports ; Unit supports front panel LED indicators for Quad health status : E1 dual ; Optical dual path ; Dual DC power supply 18 VDC to 72 VDC range ; make : Team link/ Team Engg/Cygnus/FABIO1CX - 4P or superior. Inspection by RITES.						
	NS1	240.00	Kilometre	59155.00	14197200.00	AT Par	14197200.00

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

33	Description:- Programming and Geo Tagging by taking latitude & longitude by using Integrated Locator or similar in Existing/New S&T cable route with Digital mapping through mobile application. Provision of soft and hardcopy of Digital route plan, Geo-tagging Data long with Railway track to cable distance on digital mapping considering following conditions; i. Survey of existing underground cable using latest technology equipment like-Cable Route Tracer and having RTK based GPS tagging facility using Catalyst correction service capturing depth and location of U/G cables with GNSS coordinates with accuracy, & capturing distance of cable from fixed structure/nearest track from fixed structure/ nearest track. Preparation of such cable route plan by using suitable software tools. Report will show location, depth of under ground cables, and distance from fixed structure/mast with suitable intervals as decided by Railway. Data to be handed over to railway after survey are: - (i) Soft copy/ Coordinates acquired as per the Railway requirement in suitable USB. (ii) Hardcopy of cable route showing depth, Location (coordinates), distance from fixed structure, as decided by Railway representative, in 01 Tracing & 02copies of Final Paper print. ii. S&T cable route locating by Geo-Tagging per Route Km of Trench for signalling cable & Telecom cable etc, should be with accuracy, with Minimum depth of cable In trench based on Ground Level at that location to be indicated. Data Output should be mapped provided on (.kml) format with integrated depth data of cables mapped. iii. Equipment utilized should have Utility mapping software used on mobile phone (Mobile phone with Utility mapped software should take data via Bluetooth from both Cable locator & RTK Global Navigation Satellite System receiver with autocorrection service simultaneously to provide integrated data output). iv. Additional map required with Cabled istanc from nearest Track to be included and provided as hard copy map with G coordinates of cable mentioned. Cable Join locations to be indicated in Route Map. v. Separate colour code to be used for different trench for S&T cables, if applicable.vi. In Route Map, Geo Tagging may be placed a an interval distance of 20metre fo approximate straight path. For track crossing diversion, culvert, jointing locations, interval distance shall be less than 20Mtrs or as per site condition. vii- Data output to be provided on: 1. USB 2. Hard copy print Training on Geo -Tagging of cable Route to be included. NOTE:-Work should be done through OEM.						
34	NS1	1.00	Numbers	1375208.00	1375208.00	AT Par	1375208.00
	Description:- Supply of GNSS based cable route tracer kit with receiver with built in mount for GNSS receiver, 12W or higher power transmitter with >=130V Voltage boost, suitable for detecting & mapping underground cables with accuracy up to 25 cm, with current direction up/down arrows. Supply shall include locating receiver with RTK receiver powered by locator receiver, transmitter, compatible dual Bluetooth android phone, mobile application pre-installed in android device with 5years subscription & PC database software access for direct map generation & download including depth data, 5 years subscription for GNSS correction service & standard accessories, per specification attached. Make/Model: Rycom Pathfinder PLDL Route locator with Trimble DA2 GNSS receiver or similar. Detailed specification as per Annexure:-D". Inspection by RITES. (Item should be compatible to execute with item no.33)						
35	NS1	250.00	Numbers	2780.00	695000.00	AT Par	695000.00
	Description:- Relay, AC Immune, plug-in type, Style 'QTA2 relay; DC Neutral track relay, 9 ohm, 2F.1B contacts, front and back contacts metal to carbon, complete with plug-board, retaining clip and connectors conforming to BRS:939A, BRS:966 (Appendix F2), IRS:S 34 & IRS:S 23. Inspection by RDSO.						
36	NS1	2.00	Numbers	173975.00	347950.00	AT Par	347950.00
	Description:- Supply of APLAB make Cable Fault Locator Model 3049 or latest or similar, Inspection by Rep. of Railway Engineer.						
37	NS1	1000.00	Metre	3214.00	3214000.00	AT Par	3214000.00
	Description:- Supply of channel (Injection-molded cable of size width int/ext) 240/340mm, height (int/ext) 155/230mm, length 1 meter (+/- 10mm), weight per meter 8KG (Top and Bottom) Material Polyolefin Engineering Plastic with fire protection class K-1, following DIN-53438 part I, for laying Signalling/Telecom Cables. Kg (Top As per Technical Specification STS/ Cable Laying practices Vol. IV Dt.09.05.2018 & DIN54348 parts -II RDSO (Inspection by RITES).						
38	NS1	1000.00	Metre	546.00	546000.00	AT Par	546000.00
	Description:- Laying of Polyolefin cable channels of all sizes by digging of the trench of the required size that top of the channel is not less than 0.3 Meter below earth/ground level and at the concrete surface to be laid with suitable fasteners with Contractor.						
39	NS1	5.00	Numbers	9171.00	45855.00	AT Par	45855.00
	Description:- Transportation, installation, testing & commissioning of Microcontroller based Quad Cable Conductor's Earth Resistance Sensing Unit for 24 nos. conductors with metering facility for one conductor at a time. This also includes wiring of PFC with Data Logger for remote monitoring, if any. NOTE: Equipment is treated as commissioned only after successful installation & validation.						
	NS1	1.00	Set	1257142.50	1257142.50	AT Par	1257142.50

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

40	Description:- Supply of Insulation Monitoring Device with fault locator kit for Railway signaling and telecommunication (S&T) systems. 1. This Includes (i) iso685-D-P Insulation Monitoring Device (IMD) with integrated locating current injector, (ii) EDS195PM Insulation fault locator, (iii) PSA3052 Measuring clamp 52mm, (iv) PSA3352 Measuring clamp 52mm, (v) EDS195PM Accessories for 1 no of USB power supply unit: Primary : 100...240 V, 50...60Hz Secondary: DC 5 V, +/- 10%, Power consumption 0.5 W, (vi) iso685-D-P Accessories for 3 nos of safety measuring cable black along with clamps and 2nos Safety measuring cable green/yellow along with clamps for system connection and 1 no Auxiliary supply cable, 2. Two (02) days of onsite training will be provided at 5 locations. Make: M/s Bender India or similar. Inspection by RITES.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () NS2-Modification/Alteration of Electronic Interlocking							3150000.00	Above/ Below/P ar
	NS2	1.00	Station	3150000.00	3150000.00	AT Par	3150000.00	
1	Description:- Modification/Alteration in existing Electronic Interlocking of a Station in connection with elimination of LC and/or some minor alterations to suite modified SIP as per latest RDSO guidelines/TAN. It includes: Design and modification in existing interface and Interlocking circuits and logic of EI system including, modification in the VDU(Video Display Unit)/ LCP(LocalControl panel)/ CCIP (Control cum Indication Panel). Maintenance terminal (MPC). Data Logger, Relay rack wiring. The complete work should comply with the latest RDSO specifications and guidelines and as per approved SIP and circuit diagrams. All the material (Interface cards/ relays/ wiring material/ connectors/ fuses/ communication devices etc.) shall be provided by the contractor. The work also includes the supply of modified Selection table, Interface Circuits. VDU/LCP/CCIP diagram etc. to suit the modified SIP. It also includes the carrying out of FAT, SAT (as applicable) jointly with Railways and satisfactory commissioning. All plans/drawings/circuits etc. should be prepared by IRSTE/IRSTELO license holder on AUTOCAD, soft copy to be supplied on Pen Drive and 01 set of approved tracing print along with 06 sets of hard copies (paper print in A3 size) also to be supplied.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () NS3-Earthing & Bonding system and lightening protection							5493346.00	Above/ Below/P ar
1	NS3	48.00	Numbers	4836.00	232128.00	AT Par	232128.00	
	Description:- Supply of spike air terminals of 17.2 mm dia. & 2000 mm long. The air terminal shall be manufactured with Cu bonded steel rod The air terminal shall be fixed with base plate arrangement. Inspection by RITES.							
2	NS3	300.00	Metre	1404.00	421200.00	AT Par	421200.00	
	Description:- Conductor for catenary : Supply of 6mm (25 sqmm) dia 250 Microns CU Boded Steel round conductor for air termination network at parapet and for making mesh at terrace level and shall meet the requirement. Inspection by RITES.							
3	NS3	48.00	Numbers	936.00	44928.00	AT Par	44928.00	
	Description:- Supply of catenary Conductor holder (GUV Clamp) for holding of 6mm(25 sqmm) dia to 17.2 mm dia LA CU Boded Steel. Inspection by RITES.							
4	NS3	250.00	Metre	1872.00	468000.00	AT Par	468000.00	
	Description:- Supply of 8 mm(50sqmm) dia 250 Microns CU Boded Steel round conductor for Down conductors to be installed with PVC conduit or PVC insulated on vertical wall, facade of masonry / glass / metallic work with supporting accessories. Inspection by RITES.							
5	NS3	400.00	Metre	2184.00	873600.00	AT Par	873600.00	
	Description:- Supply of 25x2mm CU tape for Ring Earthing 500 below ground level with 10kg per mtr earth enhancement compound to filled in ground and to be connected one earth pit to another earth pit.It shall meet the requirements. Inspection by RDSO.							
6	NS3	8.00	Numbers	4524.00	36192.00	AT Par	36192.00	
	Description:- Supply Test Link Joint Kit in a IP 55 weather proof enclosure of suitable dimension to disconnect the down conductor from the earth termination network for regular checks of the earth termination resistance value which shall be of CU and suitable for connecting 8mm round conductor to 8mm conductor. Inspection by Rep. of CSTE/Con/BSP.							
7	NS3	3.00	Set	7995.00	23985.00	AT Par	23985.00	

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

	Description:- Supply of basic earthing 1set as per spec no RDSO/SPN/197/2008 or latest consisting of (a) Copper bonded steel electrode of 3.0 m long, 17.2 mm dia with copper bonding thickness of minimum macrons and UL listed and marked = 1 no. (b) Earth enhancement material supplied in sealed bags of minimum 10 kg = 3 nos. (c) Copper strip of 200x25x6 mm, exothermically welded to terminate earth rod= 1 no. (d) Copper strip of 300x25x6 mm (MEEB) = 1 no. (e) Copper strip of 150x25x6mm (SEEB) = 1 no. Inspection by RDSO.						
8	NS3	3.00	Numbers	14040.00	42120.00	AT Par	42120.00
	Description:- Supply of 6 digit lightning strike counter to be installed at any of the down conductor at convenient height to view the log. Inspection by RITES.						
9	NS3	3.00	Set	39197.00	117591.00	AT Par	117591.00
	Description:- Isolation Spark Gap SPD Required for Earthing Pit with following specification Rated DC withstand voltage 200 V, Rated AC withstand voltage 140 V, Max. discharge current 100 kA, Impulse current by pole 50 kA, IP67 & Wire (BF PS) wire terminal (BF PC) connection Type. Inspection by RITES.						
10	NS3	12.00	Numbers	92904.00	1114848.00	AT Par	1114848.00
	Description:- Earthing and bonding system as per RDSO Spec. No. RDSO/SPN/197/2016 Ver 1 , RDSO Drg. No. SDO/RDSO/E&B/001 dt. 19.09.08 and RDSO Drg. No. SDO/RDSO/E&B/002 dt. 19.09.08. Earthing and bonding system for OFC room/FP/SSP etc. (a) Supply of "Permanent and Maintenance Free Earth pits materials". 1 Set PMF earth pit consisting of:- (i) 17 mm diameter and minimum 3 m long Copper Bonded Steel Rod- 3 Nos. (ii) GEM- 25 lb- 9 Bags (iii) 25*6*200 mm Cu bus bar (At Electrode) -3 No. (iv) 25*6*300 mm Cu Bus Bar (MEEB) - 1 No (v) 25*6*200 mm Cu Bus Bar (SEEB) - 3 Nos . (b) Supply for Interconnection of earth pits Copper Earth Tape of 25 x 2 mm (lump Sum 10 meter) (c) Supply for Connection between Earth pits and MEEB, It includes 35 sq mm multi-strand pvc insulated single core Cu cable (30 mtr Lump Sum). (d) Supply for Internal connection from MEEB To SEEB and to other equipments.(50 mtr Lump Sum). It includes 16 sq mm and 10 sq mm pvc insulated single core Cu cable. (e) Cad weld joints (Exo thermic welding):- (i) For interconnection between earth pits - 3 Nos LS), (ii) Joint between Cu tape & electrode- 1 No LS, (iii) Connection between electrode to MEEB - 4 Nos LS, (iv) Between MEEB TO SEEB - 6 Nos LS, (f) Supply of fixing accessories as Cu lugs & steel nuts -bolts. 50 Nos. LS. Inspection by RDSO.						
11	NS3	11.00	Set	4905.00	53955.00	AT Par	53955.00
	Description:- Supply and Installation of type 3/Class D monobloc compact SPD for 24V AC/DC System, In 1.5KA (8/20s), I _{max} 3 KA, Uc 30V DC & Up 0.2KV NO/NC contact, Max load current 25A DIN Rail Mounted & Indicative type (LED indication). Withstand on Combination waveform IEC 61643-11 is Uoc 3KV (The parameter Should be printed on SPD), Admissible short-circuit current 10KA CE Certified. Make ABB/SCHNEIDER/CITEL. Inspection by RITES.						
12	NS3	11.00	Numbers	4661.00	51271.00	AT Par	51271.00
	Description:- Supply and Installatin of type 3/Class D monobloc compact SPD for 120V AC/DC System, In 5KA (8/20s), I _{max} 10 KA, Uc 150V AC & 200V DC & Uoc 10KAV NO/NC contact, Max load current 25A DIN Rail Mounted & Indicative type (LED indication). Withstand on Combination waveform IEC 61643-11 is 10KV and KEMA Certified Make ABB/SCHNEIDER/CITEL. Inspection by RITES.						
13	NS3	2.00	Numbers	39264.00	78528.00	AT Par	78528.00
	Description:- Supply and Installation of type 1+2+3 SPD/Class B+C, 230V AC required. combination of Gas filled Spark gap (GSG) along with series Varistor (MOV+GSG) for L-N and Single High-Capacity Gas filled Spark Gap (GSG) for N-PE. SPDs connected between each phase should have no leakage/Residual currents and no line follow currents. I imp 25KA (L-N) & Iimp 50KA (N-PE) Make ABB/SCHNEIDER/CITEL.Inspection by RITES.						
	NS3	3.00	Job	195000.00	585000.00	AT Par	585000.00

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

14	Description:- Installation of above items, It includes, (i) Civil works related to earth pit digging, PMF earth pit installation, back filling & making of earth enclosure with cover. (ii) Materials for earth enclosures with Cover. (iii) Drilling and fixing of MEBB & SEBB. (iv) Installation for inter-Connection of earths; it includes Civil work for 02 ft. depth x 01 ft. width excavation of trench & back filling with GEM & Black soil. Installation of earthing must be carried out as per RDSO Dog. No. SDO/RDSO/E&B/001 & RDSO TAN-STSE/TAN/3006 Version 2.2 & Version 3.1 or latest, (as per latest ammendmt. of RDSO). NOTE: (i) OEM shall be responsible for Complete Supply, installation & Commissioning of Earthing & bonding and lightening protection System for EI. The Warranty of such system shall be 60 months from date of Commissioning and any failure of earthing, bonding & lighting protection System due to inferior materials/ poor workmanship shall be attended free of cost by OEM during above mentioned period of 60 months. (ii) Contractor must be arranged for inspection of Rep. of RDSO at Concern site stations of NGP Division for Installation of Earthing & lightening protection System before commissioning. Payment of item no. (10) of Schedule-NS-3 shall be released only after approval/certification of work by RDSO that installation of above items have been carried out at site as per latest RDSO drawings/specification and TAN of earthing, bonding and lightening protection system for EI. (iii) All items of RDSO Checklist of earthing, bonding & lightening protection system must be complied and jointly Signed by OEM & Railway Engineer. OEM Certificate shall be issued by OEM duly certifying warranty period of 60 months and any defects found during this period shall be rectified by OEM free of cost . (iv) Water proof painting/drawing of earthing system on nearest wall of station building/goomties duly showing all electrodes, connectivity and earthing value etc. in suitable size or as advised by Railway engineer. Here Job unit stands for Location							
15	NS3	3000.00	Metre	450.00	1350000.00	AT Par	1350000.00	
	Description:- Supply of Multistrand 35 sq mm wire single core cable green IS 694. Inspection by Rep. of Railway Engineer.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () NS4-Axle counter							1720848.00	Above/ Below/P ar
1	NS4	3.00	Set	480236.00	1440708.00	AT Par	1440708.00	
	Description:- Supply of Single section Digital Axle counter as per RDSO specification no.RDSO/SPN/177/2012 (Ver- 3)or latest, Phase Reversal Type, consisting of the following:- (a) High frequency Tx coil & Rx coil (Each set consists of clamp type 2 nos.Tx and 2 nos. Rx coil) =1 set. (b) Track side digital axle counter unit DACF-710P =2Nos. (c) Vital Relay box duly wired =2 nos. each with 2nos. of 24 V, 1000 ohms, "Q" type relays. (d) Clamp with deflector plates and hardware etc =4 Nos. (e) Reset box = 2Nos. (f) Surge voltage protection device box =2 Nos. Inspection by RDSO.							
2	NS4	6.00	Set	46690.00	280140.00	AT Par	280140.00	
	Description:- High frequency Tx coil & Rx coil = 1 set , including mouting accessories, fasterning parts, protective tubes, etc, (Each set consists of clamp type 2 nos. Tx and 2nos. Rx coil with 15 m cable). Inspection by RDSO.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () NS5-Fire Alarm System							3858364.80	Above/ Below/P ar
1	NS5	600.00	Metre	1365.00	819000.00	AT Par	819000.00	
	Description:- Supply, Installation, Testing & commissioning of Resettable Analogue Type Linear Heat Sensing(LHS) Cable complying toRDSO/SPN/217/2025 Ver-3.1 or latest. Inspection by RDSO.							
2	NS5	3.00	Numbers	129488.00	388464.00	AT Par	388464.00	
	Description:- Supply, Installation, Testing & commissioning of Resettable Analogue Type Linear Heat Sensing(LHS) Cable Interface Module with all accessories for single stretch complying to RDSO/SPN/217/2025Ver-3.1 or latest. Inspection by RDSO. Note :- Supply and installation of interfacing unit with fire alarm system.							
3	NS5	6.00	Numbers	395216.80	2371300.80	AT Par	2371300.80	
	Description:- Supply, Installation, Testing and Commissioning of Single Channel Laser or High power LED Based Aspiration Detection Unit with programmable 4 stage alarm generation & with 4 addressable modules along with compatible interface module to interface fire alarm panel. It should have Auto cleaning facility in optical chamber, electronic discrimination of particle size, ultrasonic airflow sensing Auto learn feature with TCP/IP network Capability. The aspiration system shall also include external power supply unit with battery backup. Approval-UL/CE/LPCB/VDS Listed and shall comply to RDSO/SPN/217/2025 Ver3.1 or latest. Inspection by RDSO.							
4	NS5	300.00	Metre	932.00	279600.00	AT Par	279600.00	

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

Description:- Supply, installation testing commissioning of UL/LPCB/VDS listed CPVC pipe 25mm Dia & Pipe Accessories for the Aspiration detection. Approval - UI and shall comply to RDSO spec. no.RDSO/SPN/217/2025 Ver 3.1 or latest. Inspection by RDSO.
--

3. ITEM BREAKUP

No item break up added

4. ELIGIBILITY CONDITIONS

Important : All documents uploaded and remarks / confirmation entered by the bidders against any eligibility condition shall be opened as part of technical bid only

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or 'V' whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet.	No	No	Allowed (Mandatory)
2	Bid Capacity: - Clause no. 10.3 of GCC-2022 with their qualifying criteria will be applicable in case of Bid Capacity	No	No	Allowed (Mandatory)
3	Joint Venture: - Clause no. 17 of GCC-2022 with their qualifying criteria will be applicable in case of Joint Venture (JV).	No	No	Allowed (Mandatory)
4	Partnership firm :- Clause no. 18 of GCC-2022 with their qualifying criteria will be applicable in case of partnership firm.	No	No	Allowed (Mandatory)

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**DYCS-TE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

1	The tenderer must have successfully completed or substantially completed any one of the following categories of work(s) during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (i) Three similar works each costing not less than the amount equal to 30% of advertised value of the tender, or (ii) Two similar works each costing not less than the amount equal to 40% of advertised value of the tender, or (iii) One similar work costing not less than the amount equal to 60% of advertised value of the tender. Similar work means:- (i)Indoor work involving supply, installation, testing & commissioning of Electronic Interlocking/RRI/PI (OR) (ii)Both Indoor and Outdoor works involving supply, installation, testing & commissioning of Electronic Interlocking/RRI/PI (OR) (iii)Intermediate Block Signalling/Automatic Block Signalling/Provision or replacement of any type of block instruments/LC Gate Interlocking work/ Yard Remodelling work involving installation or alteration to Electronic Interlocking/RRI/PI (OR) (iv)MACLS outdoor signalling work which includes one or more works like cable trenching & laying/location erection and wiring/point machine installation or replacement (including power operated siding points) / signal foundation and erection/ track circuiting/ double distant/ BPAC installation/ Axle Counter installation. NOTE: If the works involves installation and/or alteration of EI System, then following conditions shall be satisfied: (i) The successful bidder shall submit an undertaking from RDSO approved EI OEM, before the supply of material, to confirm compliance with extant RDSO guidelines and to meet contract specific requirements. Note for Technical Eligibility Criteria: - Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organization, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate.	No	No	Allowed (Mandatory)
---	--	----	----	------------------------

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.

**DYCSTE-C-NGP-S AND T/SOUTH EAST CENTRAL RLY
TENDER DOCUMENT**

Tender No: 765-ST-Con-NGP-G-BPQ

Closing Date/Time: 18/06/2026 12:00

9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Important All documents uploaded and remarks / confirmation entered by the bidders against any : compliance condition shall be opened as part of technical bid only.

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	GCC-Apr-2022.pdf	GCC 2022
2	GCCACS1to11_compressed.pdf	GCC CS 1 TO 11
3	Tele_Cir_diggingofcable.pdf	CABLE DIGGING
4	TAN3006ver3.1earthing_compressed.pdf	TAN FOR EARTHING
5	765Annexure.pdf	General instructions Annexures
6	765SCC_1.pdf	765 SCC
7	765Scopeofwork.pdf	SCOPE OF WORK
8	LocationBoxDrawing.pdf	LOCATIONS DRAWINGS

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: KUMAR CHANCHAL PRIYDARSHI

Designation : Dy.CSTE/Nagpur/SECR